JUD C HICKEY CENTER

105 LUTHERAN DRIVE
AUGUSTA, GA 30907

SITE MAP

PROJECT DIRECTORY

OWNER:
JUD C. HICKEY CENTER FOR ALZHEIMER'S CARE
1901 CENTRAL AVENUE
AUGUSTA, GA 30904
PH: (706) 738-5039
CONTACT: JENNIFER PENNINGTON
EMAIL: JENNIFER@JUDCHICKEYCENTER.ORG

ARCHITECT:
DICKINSON ARCHITECTS
771 BROAD STREET, SUITE 200
AUGUSTA, GEORGIA 30901
PH: (706) 722-7488
CONTACT: ERIN ARMSTRONG, AIA
EMAIL: EARMSTRONG@DICKINSONARCHITECTS.COM

STRUCTURAL ENGINEER:
PRYCO STRUCTURAL
1450 GREENE ST., STE 82
AUGUSTA, GA 30901
PH: (706) 303-4400
CONTACT: JOSE R. HERNANDEZ, P.E., S.E.
EMAIL: JRH@PRYCOSTRUCTURAL.COM

ELECTRICAL ENGINEER:
ELECTRICAL DESIGN CONSULTANTS, INC.
1201 BROAD STREET, SUITE 1A
AUGUSTA, GA 30901
PH: (706) 724-3551
CONTACT: ASHLEY PAULK, P.E.
EMAIL: APAULK@EDCAUGUSTA.COM

MECH./PLUMBING ENGINEER:
PFA ENGINEERING, INC.
1201 BROAD STREET, SUITE 3A
AUGUSTA, GA 30901
PH: (706) 722-3959
CONTACT: MARTIN FORD, P.E.
EMAIL: JMFORD@PFAENGINEERS.COM

CIVIL: (UNDER SEPARATE CONTRACT)
CIVIL DESIGN SOLUTIONS
371 W MAIN STREET
WARRENTON, GA 30828
PH: (706) 465-0900
CONTACT: SCOTT JOHNSON, P.E.
EMAIL: SLJOHNSON@CIVILDESIGNSOLUTIONS.COM

SYMBOLS LEGEND

- NUMERICAL / BUILDING SECTION / SHEET DRAWN ON SHEET REFERENCE TO (TYP.)
- NUMERICAL / WALL SECTION / SHEET DRAWN ON SHEET REFERENCE TO (TYP.)
- NUMERICAL / DETAIL / SHEET DRAWN ON SHEET REFERENCE TO (TYP.)
- VIEW / NUMERICAL / INTERIOR ELEVATION
- NUMERICAL / DOOR SYMBOL
- ALPHABETICAL / WINDOW SYMBOL
- ROOM NUMBER
- NUMERICAL / REVISION
- ALPHABETICAL / TOILET ACCESSORY
- NUMERICAL / WALL TYPE
- NUMERICAL / KITCHEN EQUIPMENT

INDEX OF DRAWINGS

		35% SET - 04/16/21	65% SET - 11/17/21	ISSUE FOR PERMIT - 02/16/22	OWNER REVISIONS - 09/09/22
GENERAL PROJECT INFORMATION					
T100	TITLE SHEET	X	X	X	X
T101	CODE DATA	X	X	X	X
T102	ACCESSIBILITY GUIDELINES	X	X	X	
LIFE SAFETY					
LS101	LIFE SAFETY PLAN	X	X	X	X
LS102	UL DETAILS & FIRESTOPPING DETAILS		X	X	
ARCHITECTURAL					
A100	ARCHITECTURAL SITE PLAN	X	X	X	
A101	DIMENSION FLOOR PLAN	X	X	X	X
A102	REFERENCE FLOOR PLAN - PHASE 1	X	X	X	X
A102.1	PARTIAL PLANS & ELEVATIONS - PHASE 2				X
A105	ROOF PLAN - PHASE 1	X	X	X	X
A106	FIRST FLOOR ROF - PHASE 1	X	X	X	X
A201	BUILDING ELEVATIONS - PHASE 1	X	X	X	X
A202	BUILDING ELEVATIONS PHASE 2				X
A301	BUILDING SECTIONS		X	X	X
A302	BUILDING SECTIONS		X	X	X
A303	BUILDING SECTIONS		X	X	X
A310	WALL SECTIONS		X	X	X
A311	WALL SECTIONS		X	X	X
A312	WALL SECTIONS		X	X	X
A313	WALL SECTIONS PHASE 1				X
A321	EXTERIOR DETAILS			X	X
A322	EXTERIOR DETAILS			X	X
A323	EXTERIOR DETAILS			X	X
A331	INTERIOR DETAILS			X	X
A401	ENLARGED TOILET PLANS	X	X	X	X
A402	ENLARGED TOILET PLANS	X	X	X	X
A403	ENLARGED TOILET PLANS	X	X		
A410	ENLARGED KITCHEN PLANS			X	
A601	WALL TYPES	X	X		
A701	DOOR SCHEDULE, TYPES, & DETAILS	X	X	X	X
A702	DOOR DETAILS	X	X		
A710	WINDOW SCHEDULE, TYPES, & DETAILS	X	X	X	X
A801	INTERIOR FINISH SCHEDULE			X	X
A810	FIRST FLOOR FINISH PLAN	X	X	X	X
A821	INTERIOR ELEVATIONS		X	X	X
A822	INTERIOR ELEVATIONS		X	X	X
A823	INTERIOR ELEVATIONS		X	X	X
A824	INTERIOR ELEVATIONS			X	X
A850	MILLWORK PLAN			X	X
A851	MILLWORK DETAILS			X	
A852	MILLWORK DETAILS			X	
A853	MILLWORK DETAILS			X	
A854	MILLWORK DETAILS			X	
STRUCTURAL					
S100	STRUCTURAL NOTES	X	X	X	
S110	SPECIAL INSPECTIONS	X	X	X	
S200	FOUNDATION PLAN	X	X	X	
S201	FOUNDATION PLAN PHASE 2				X
S300	FRAMING PLAN	X	X	X	
S301	FRAMING PLAN PHASE 2				X
S400	BUILDING SECTION	X	X	X	
S500	FOUNDATION DETAILS	X	X	X	
S700	FRAMING DETAILS	X	X	X	

		35% SET - 04/16/21	65% SET - 11/17/21	ISSUE FOR PERMIT - 02/16/22	OWNER REVISIONS - 09/09/22
PLUMBING					
P100	PLUMBING PLAN - WASTE AND VENT			X	X
P101	PLUMBING PLAN - WATER AND GAS	X	X	X	X
P200	PLUMBING DETAILS	X	X	X	
P201	PLUMBING SCHEDULE AND SPECIFICATIONS			X	X
FIRE PROTECTION					
FP100	FIRE PROTECTION PLAN	X	X	X	X
FP101	FIRE PROTECTION PLAN - ATTIC	X	X	X	X
FP200	FIRE PROTECTION SPECIFICATIONS			X	X
MECHANICAL					
M101	HVAC PLAN	X	X	X	X
M201	HVAC PIPING PLAN	X	X	X	X
M301	HVAC DETAILS & SPECIFICATIONS	X	X	X	
M401	HVAC SCHEDULES			X	X
ELECTRICAL					
E100	LEGEND, NOTES, DETAILS, AND FIXTURE SCHEDULE	X	X	X	X
E101	ELECTRICAL SITE PLAN	X	X	X	X
E201	LIGHTING PLAN	X	X	X	X
E201.1	LIGHTING PLAN - PHASE 1				X
E301	POWER PLAN	X	X	X	X
E302	ENLARGED POWER PLAN - KITCHEN			X	X
E401	MECHANICAL POWER PLAN	X	X	X	X
E402	MECHANICAL CONNECTION SCHEDULES			X	X
E501	FIRE ALARM SYSTEM PLAN	X	X	X	X
E502	SYSTEMS PLANS	X	X	X	X
E600	POWER RISER DIAGRAM AND PANELBOARD SCHEDULES	X	X	X	X
E601	PANELBOARD SCHEDULES			X	X
E700	DETAILS	X	X	X	X

ABBREVIATIONS

A/C	AIR CONDITIONER	HM	HOLLOW METAL
ALT.	ALTERNATE	HORIZ.	HORIZONTAL
ALUM.	ALUMINUM	HP	HORSE POWER
@	AT	HR	HOUR
A.F.F.	ABOVE FINISH FLOOR	HVAC.	HEATING VENTILATING,AIR CONDITIONING
A.L.	ARCH LENGTH	HWS	HOT WATER SUPPLY (CWS - COLD)
A.C.P.	ACOUSTICAL CEILING PANEL	HWR	HOT WATER RETURN (CWR - COLD)
A.V.	AUDIO VISUAL	I.D.	INSIDE DIAMETER
AWG	AVERAGE WIRE GAUGE	INSUL.	INSULATION
BD.	BOARD	INT.	INTERIOR
BOTT. B/	BOTTOM	J	JUNCTION
BM.	BEAM	JT.	JOINT
BRG.	BEARING	J/B	JOIST BEARING
B.S.	BOTH SIDES	L.P.	LATEX PAINT
BTUH	BRITISH THERMAL UNIT/HOUR	LAM.	LAMINATED
BULKHD	BULKHEAD	MAT.	MATERIAL
B.W.	BOTH WAYS	MAX.	MAXIMUM
CB	CERAMIC BASE	MECH.	MECHANICAL
CC	COLORED CONCRETE	MFGR.	MANUFACTURER
CEIL'G	CEILING	MIN.	MINIMUM / MINUTE
CFM	CUBIC FEET PER MINUTE	MISC.	MISCELLANEOUS
CG	CORNER GUARD	M.O.	MASONRY OPENING
C.I.	CAST IRON	MR.	MOISTURE RESISTANT
C.J.	CONTROL JOINT	MTD.	MOUNTED
℄	CENTER LINE	MTL.	METAL
CL	CLEARANCE	MUL.	MULLION
CLG	CEILING	N.E.C.	NATIONAL ELECTRICAL CODE
CMU	CONCRETE MASONRY UNIT	N.F.P.A.	NATIONAL FIRE PROTECTION ASSOCIATION
CO	CLEAN OUT	N.I.C.	NOT IN CONTRACT
COL.	COLUMN	O.A.	OUTSIDE AIR
CONC.	CONCRETE	O.C.	ON CENTER
COND.	CONDUCTIVE	O.D.	OUTSIDE DIAMETER
CONST.	CONSTRUCTION	O.H.	OVERHEAD
CONT.	CONTINUOUS	PL.	PLATE
CPT	CARPET	PLAM.	PLASTIC LAMINATE
CPTB	CARPET BASE	PLYW'D	PLYWOOD
C.T.	CERAMIC TILE	P.S.F.	PAINTED SMOOTH FINISH
CWC	CERAMIC WALL COVERING	P.S.I.	POUNDS/SQUARE INCH
DBL.	DOUBLE	PT	PRESSURE TREATED
DETECT.	DETECTOR	PNT.	PAINTED
DET.	DETAIL	Q.T.	QUARRY TILE
DIA ~	DIAMETER	REINF.	REINFORCING
DIAG.	DIAGONAL	R.	RADIUS
DN.	DOWN	RB	RUBBER BASE
DR.	DOOR	R.D.	ROOF DRAIN
D.S.	DOWNSPOUT	RDL.	ROOF DRAIN LINE
EA.	EACH	REQ'D	REQUIRED
E.C.	ELECTRICAL CONDUIT	RTU	ROOF TOP UNIT
E.C.F.	ELECTRICAL CONDUIT FLEX.	R.W.L.	RAIN WATER LEADER
EF	EXHAUST FAN	S.B.C.	STANDARD BUILDING CODE
E.I.F.S.	EXTERIOR INSULATING FINISH SYSTEM	S.C.	SOLID CORE
E.J.	EXPANSION JOINT	SHT.	SHEET
ELECT.	ELECTRICAL	SIM.	SIMILAR
E.P.	EPOXY PAINT	S.S.	STAINLESS STEEL
EQUIP.	EQUIPMENT	SQ.	SQUARE
E.W.	EACH WAY	ST. GT.	STEEL GRATE
EXIST.	EXISTING	STD.	STANDARD
EWC	ELECTRIC WATER COOLER	STG.	STORAGE
EXT.	EXTERIOR	STL.	STEEL
EXP	EXPOSED	STRUCT.	STRUCTURAL
FACP	FIRE ALARM CONTROL PANEL	TELE.	TELEPHONE
FBOIBO	FURNISHED BY OWNER, INSTALLED BY OWNER	TEMP.	TEMPERED
FBOIBC	FURNISHED BY OWNER, INSTALLED BY CONTRACTOR	T/	TOP
FCB	FIBER CEMENT BOARD	T/B	TOP OF BEAM
FD	FLOOR DRAIN	T/F	TOP OF FOOTING
FE	FIRE EXTINGUISHER	T.H.	THRESHOLD
FEC	FIRE EXTINGUISHER CABINET	T/J	TOP OF JOIST
FIN.	FINISH	T.O.	TOP OF
F.F.L.	FINISH FLOOR LEVEL	T.O.W.	TOP OF WALL
FLR	FLOOR	TS	TUBE STEEL
F.R.	FIRE-RATED	TXS	TEXTURED SURFACE
F.R.P.	FIBERGLASS REINF. PANELS	TYP.	TYPICAL
FT.	FOOT	U.L.	UNDERWRITERS LABORATORY
FTG.	FOOTING	U.N.O.	UNLESS NOTED OTHERWISE
F.V.	FIELD VERIFY	V.CONT.T.	VINYL CONDUCTIVE TILE
G	GROUND	VCT	VINYL COMPOSITION TILE
GA	GAUGE	VM	VENDING MACHINE
G.C.	GENERAL CONTRACTOR	W/	WITH
GL	GLASS	W/IN	WITHIN
GPM	GALLONS PER MINUTE	W/O	WITHOUT
GYP BD.	GYPSUM BOARD	WB	WOOD BASE
HB	HOSE BIBB	WD.	WOOD
HC	HANDICAP	WF	WOOD FLOOR
HCEWC	HANDICAP ELECTRIC WATER COOLER	W.P.	WORK POINT
HDWR	HARDWARE	W.W.F.	WELDED WIRE FABRIC
HGT.	HEIGHT		

ARCHITECTURAL GENERAL NOTES

1. DO NOT SCALE DRAWINGS- DIMENSIONS GOVERN.

2. LARGER SCALE PLANS & DETAILS WILL TAKE PRECEDENCE OVER SMALLER SCALE DRAWINGS.

3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL REQUIRED BUILDING PERMITS.

4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL WORK AND MATERIALS IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS, AND ORDINANCES HAVING JURISDICTION.

5. MATERIALS, DIMENSIONS AND ALL OTHER CONDITIONS NOT OTHERWISE INDICATED IN THESE CONSTRUCTION DOCUMENTS SHALL BE INTERPRETED AS HAVING THE SAME MEANING AS THOSE MOST SIMILARLY DETAILED AND MORE FULLY DEFINED ELSEWHERE WITHIN THESE DOCUMENTS.

6. THE CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS INDICATED WITHIN THESE DOCUMENTS AND SHALL NOTIFY THE ARCHITECT OF ANY VARIATION PRIOR TO THE PURCHASING OF MATERIALS, STARTING FABRICATION OR BEGINNING CONSTRUCTION.

7. THE CONTRACTOR, UPON AWARDING CONTRACTS TO SUBCONTRACTORS, SHALL SUBMIT TO THE ARCHITECT AND THE OWNER A LIST OF ALL ITEMS AND THEIR DELIVERY SCHEDULES. THE CONTRACTOR SHALL IDENTIFY ALL LONG-LEAD TIME ITEMS ON THE PROJECT (I.E., MATERIALS, FABRICS, HARDWARE, ETC.). THE CONTRACTOR, PRIOR TO ORDERING AN ITEM, SHALL BE RESPONSIBLE FOR NOTIFYING THE ARCHITECT AND THE OWNER OF ANY ITEM WHICH MAY CAUSE THE PROJECT TO BE DELAYED.

8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DELAY TO MOVE-IN DATE CAUSED BY SCHEDULING WITHIN HIS SCOPE, I.E., DELIVERY DATES OF MATERIALS, ETC.

9. FLOOR TOLERANCE: IN LAYING OUT AND DETAILING THE WORK TO BE COMPLETED, CONSIDERATIONS SHALL BE GIVEN TO VARIATIONS IN THE FLOOR LEVELNESS RESULTING FROM CONSTRUCTION QUALITY AND LIVE AND DEAD LOADS IMPOSED ON THE STRUCTURE. FIELD VERIFICATION SHALL BE MADE OF CONDITIONS TO VERIFY CONSTRUCTION TOLERANCES. ALIGNMENT OF THE DOOR HEADS AND OTHER HORIZONTAL ELEMENTS SHALL BE MAINTAINED AT A CONSTANT LEVEL AND SHALL NOT FOLLOW VARIATIONS IN FLOOR PLANE. LEVEL FLOORS AS REQUIRED USING APPROVED LEVELING COMPOUND.

10. CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL NECESSARY REINFORCING TO ACCOMMODATE INTERIOR FINISHES, FIXTURES AND EQUIPMENT AS DESCRIBED IN THESE DOCUMENTS.

11. THE EXTENT OF WORK SHALL BE LIMITED TO THAT INDICATED IN THE CONTRACT DOCUMENTS. NO ADDITIONAL WORK SHALL BE DONE WITHOUT PRIOR WRITTEN APPROVAL OF THE ARCHITECT OR OWNER. ANY ADDITIONAL WORK PERFORMED WITHOUT WRITTEN APPROVAL SHALL BE AT THE CONTRACTOR'S EXPENSE.

12. ALL FASTENERS AND ATTACHMENTS SHALL BE FULLY CONCEALED FROM VIEW, UNLESS NOTED OTHERWISE.

13. DIMENSIONS NOTED AS "CLEAR" OR "CRITICAL" SHALL BE MEASURED FROM FINISHED FACE TO FINISHED FACE.

14. ALL GYPSUM WALLBOARD AND METAL STUD CONSTRUCTION SHALL BE IN ACCORDANCE WITH RECOMMENDATIONS AND INSTRUCTIONS PUBLISHED BY U.S. GYPSUM COMPANY'S "GYPSUM CONSTRUCTION HANDBOOK", LATEST EDITION.

15. ALL FINISH CARPENTRY AND MILLWORK SHALL BE IN ACCORDANCE WITH THE ARCHITECTURAL WOOD-WORKS INSTITUTE (AWI) STANDARDS FOR SELECTION OF MATERIALS HARDWARE, FABRICATION, WORKMANSHIP, AND FINISHING.

16. EQUIPMENT AND APPLIANCES: THE CONTRACTOR SHALL PROVIDE AND INSTALL EQUIPMENT AND/OR APPLIANCES SPECIFIED UNLESS OTHERWISE NOTED. THE CONTRACTOR SHALL PROVIDE AND COORDINATE INSTALLATION OF OWNER FURNISHED EQUIPMENT AND/OR APPLIANCES WHERE DESIGNATED. CONTRACTOR SHALL VERIFY THE PLUMBING AND ELECTRICAL REQUIREMENTS OF ALL SUCH APPLIANCES.

17. PATCH AND SEAL ALL PENETRATIONS IN THE FLOOR AND PARTITIONS TO COMPLY WITH APPLICABLE BUILDING AND/OR FIRE, LIFE SAFETY CODES.

18. "TYPICAL" MEANS THE REFERENCED DETAIL SHALL APPLY FOR ALL SIMILAR CONDITIONS UNLESS OTHERWISE NOTED.

19. ALL FLOOR FINISH CHANGES SHALL OCCUR UNDER CENTER LINE OF DOOR IN CLOSED POSITION.

20. WHERE ELECTRICAL, MECHANICAL, AND/OR OTHER WALL MOUNTED DEVICES OCCUR AT THE SAME LOCATION BUT AT DIFFERENT HEIGHTS, THEY SHALL BE CENTERED ABOVE EACH OTHER.

21. THE CONTRACTOR IS RESPONSIBLE FOR ALL MECHANICAL AND ELECTRICAL ITEMS INDICATED ON THE ARCHITECTURAL MECHANICAL, PLUMBING, AND ELECTRICAL DRAWINGS. ALL ITEMS INDICATED ON ANY DRAWING ARE TO BE INCLUDED AS A COMPLETE SYSTEM.

22. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION OF STRUCTURAL, MECHANICAL, ELECTRICAL, PLUMBING WORK WITH ARCHITECTURAL DRAWINGS. HE SHALL BE RESPONSIBLE TO IDENTIFY ANY DISCREPANCIES ON THE DOCUMENTS AND SHALL INFORM THE ARCHITECT.

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, INC. IT WAS PREPARED FOR THE USE ON THIS SITE. IT MAY NOT BE USED FOR OTHER PURPOSES, REPRODUCED, OR THE SAME - OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS TO BE RETURNED UPON REQUEST.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REV #	DATE	APRV'D BY	REVISION
	4/16/21	EA	35% SET
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moselley Armstrong
CERTIFICATE NO. RA012777
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
TITLE SHEET

DRAWING NO:
T100

1. OCCUPANCY CLASSIFICATION

IBC 2018

SECTIONS 303.3, 303.4, 304, 308.5
ASSEMBLY GROUP A (A-2)
ASSEMBLY GROUP A (A-3)
BUSINESS GROUP B
INSTITUTIONAL GROUP (I-4)

SECTION 508 MIXED USE AND OCCUPANCY
I-4, A-2, A-3, & B REGULATED PER
508.3 NONSEPARATED OCCUPANCIES

2018 NFPA LIFE SAFETY

CHAPTER 12/13 - NEW & EXISTING ASSEMBLY OCCUPANCIES
CHAPTER 16/17 - NEW & EXISTING DAY-CARE OCCUPANCIES
CHAPTER 38/39 - NEW & EXISTING BUSINESS OCCUPANCIES

SECTION 6.1 MULTIPLE OCCUPANCIES
DAY-CARE, ASSEMBLY, & BUSINESS REGULATED PER
6.1.14.3 MIXED OCCUPANCIES

2. CONSTRUCTION TYPE

IBC 2018
SECTION 601
TYPE VB

3. FIRE SPRINKLERS

IBC 2018
SECTION 506.3
AUTOMATIC
FIRE SPRINKLER

2018 NFPA LIFE SAFETY
SECTION 16.3.5

EXTINGUISHING IS REQUIRED.

3.1 FIRE ALARM

2018 NFPA LIFE SAFETY
SECTION 16.3.4

FIRE ALARM SYSTEM IS REQUIRED.

4. HEIGHT / AREA LIMITATIONS

PER IBC 2018 TABLES 504.3, 504.4, 506.2

PER IBC 2018 506.3 FRONTAGE INCREASE: EQUATION 5-5:

$I_f = [F/P - 0.25]W/30$

$I_f = .62$

PER IBC 2018 506.2 FRONTAGE INCREASE: EQUATION 5-1:

$A_a = A_t + (NS \times I_f)$

ASSEMBLY (A-2 & A-3) ALLOWABLE AREA:

A_a = 24,000 SF + (6,000 SF x .62)

A_a = 27,720 SF

BUILDING AREA BREAKDOWN:

INTERIOR	24,312 SF
COVERED EXTERIOR	2,991 SF
TOTAL:	27,303 SF

AREA:	MAX ALLOWABLE AREA (TABLE 506.2)	FRONTAGE AREA INCREASE ALLOWABLE	ACTUAL BUILDING AREA
BUILDING AREA	24,000 SF	27,720 SF	27,303 SF

HEIGHT:	MAX ALLOWABLE HEIGHT (TABLES 504.3, 504.4)	ACTUAL BUILDING HEIGHT
HEIGHT IN FEET	60'	30'
HEIGHT IN STORIES	2	1

5. OCCUPANCY LOAD

NOTES:

1. CALCULATIONS ARE PER NFPA TBL. 7.3.1.2
2. TOTAL OCCUPANCY INCLUDES OCCUPANTS IN THE INTERNAL COURTYARD, BUT THAT AREA IS NOT INCLUDED IN THE BUILDING AREA., PER IBC. EGRESS THROUGH AND OUT OF THE BUILDING FOR THESE OCCUPANTS IS INCLUDED IN THE BUILDING DESIGN.

	AREA / FACTOR = OCCUPANTS		TOTAL OCCUPANCY
TOTAL	24,312 SF	VARIES, SEE LIFE SAFETY PLAN	928

6. EGRESS REQUIREMENTS

PER NFPA 101 TABLE 7.3.3.1

	LEVEL COMPONENT .2" PER OCCUPANT		STAIR COMPONENT .3" PER OCCUPANT	
	MIN.	ACTUAL	MIN.	ACTUAL
1st FLOOR	36"	72"	36"	N/A

NUMBER OF EXITS		
	MIN. PER NFPA 101	ACTUAL
1st FLOOR	3	3

7. TRAVEL DISTANCE

NOTES:
1. PER NFPA 101 TABLE A7.6.

TRAVEL DISTANCE LIMIT		DEAD-END LIMIT		COMMON PATH LIMIT	
NFPA 101 TABLE A7.6	ACTUAL	NFPA 101 TABLE A7.6	ACTUAL	NFPA 101 TABLE A7.6	ACTUAL
200 FT.	< 128 FT	20 FT.	< 13 FT	20/75 FT.	< 28 FT

8. APPLICABLE CODES - STATE OF GEORGIA

LIFE SAFETY CODE	NFPA 101, 2018 EDITION
INTERNATIONAL BUILDING CODE	2018 EDITION, WITH GEORGIA AMENDMENTS
AMERICANS WITH DISABILITIES ACT	2010 WITH REVISED STANDARDS
INTERNATIONAL MECHANICAL CODE	2018 EDITION, WITH GEORGIA AMENDMENTS
INTERNATIONAL PLUMBING CODE	2018 EDITION, WITH GEORGIA AMENDMENTS
NATIONAL ELECTRIC CODE	2020 EDITION, WITH GEORGIA AMENDMENTS
INTERNATIONAL FIRE CODE	2018 EDITION, WITH GEORGIA AMENDMENTS
INTERNATIONAL FUEL GAS CODE	2018 EDITION, WITH GEORGIA AMENDMENTS
INTERNATIONAL ENERGY CONSERVATION CODE	2015 EDITION, WITH GEORGIA AMENDMENTS
NFPA 13	2019 EDITION
NFPA 96	2017 EDITION

TABLE 102.10: CODES REFERENCE GUIDE	PRIMARY	SUPPLEMENT
OCCUPANCY CLASSIFICATION	LSC	IBC
BUILDING CONSTRUCTION TYPES INCLUDING ALLOWABLE HEIGHT, ALLOWABLE BUILDING AREAS, AND THE REQUIREMENTS FOR THE SPRINKLER PROTECTION RELATED TO MINIMUM BUILDING CONSTRUCTION TYPES	IBC	LSC
MEANS OF EGRESS	LSC	NONE
STANDPIPES	IBC	IFC
INTERIOR FINISH	LSC	NONE
HVAC SYSTEMS	IMC	NONE
VERTICAL OPENINGS	LSC	NONE
SPRINKLER SYSTEMS MINIMUM CONSTRUCTION STANDARDS	LSC	NONE
FIRE ALARM SYSTEMS	LSC	NONE
SMOKE ALARM AND SMOKE DETECTION SYSTEMS	STATE STATUTE & LSC	NONE
PORTABLE FIRE EXTINGUISHERS	IFC	NONE
COOKING EQUIPMENT	LSC & NFPA	NONE
FUEL FIRED APPLIANCES	IFGC	NFPA 54
LIQUID PETROLEUM GAS	NFPA 58	NFPA 54 & IFGC
COMPRESSED NATURAL GAS	NFPA 52	NONE

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND MAY NOT BE REPRODUCED WITHOUT WRITTEN PERMISSION. THIS DRAWING AND ALL INFORMATION, DESIGNS, OR DRAWINGS ARE FOR ANY - STATE - PURPOSE - DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS THE EXCLUSIVE PROPERTY OF DICKINSON ARCHITECTS, P.C.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	4/16/21	EA	35% SET
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. R-041277
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
CODE DATA

DRAWING NO:
T101

NOTE: ACCESSIBLE DOOR SURFACE TO MAINTAIN A SMOOTH SURFACE ON THE PUSH SIDE EXTENDING THE FULL WIDTH OF THE DOOR AS PER ANSI A117.1 404.2.9

1 DOOR CLR AT PUBLIC/COMMON AREAS
SCALE: 3/8" = 1'-0"

2 TYP. GRAB- BAR SECTION
SCALE: 6" = 1-0"

3 CLEAR FLOOR SPACES
SCALE: 3/8" = 1'-0"

4 COMMON USE SINGLE BATHROOM
SCALE: 1/2" = 1'-0"

5 COMMON USE LAVATORY
SCALE: 1/2" = 1'-0"

6 COMMON USE ACCESSIBLE WC COMPARTMENT
SCALE: 1/2" = 1'-0"

FIG. 12F PROTRUDING OBJECTS MOUNTED NEAR GRAB BARS.

FIG. 12G RECESSED OBJECTS MOUNTED NEAR GRAB BARS.

7 PROTRUDING OBJECTS
SCALE: 1/4" = 1'-0"

403.5.2 Clear Width at Turn. Where the accessible route makes a 180 degree turn around an element which is less than 48 inches wide, clear width shall be 42 inches minimum approaching the turn, 48 inches minimum at the turn and 42 inches minimum leaving the turn.

EXCEPTION: Where the clear width at the turn is 60 inches minimum compliance with 403.5.2 shall not be required.

8 CLEAR WIDTH AT TURN
SCALE: 3/8" = 1'-0"

9 TYP. MOUNTING HEIGHTS
SCALE: 1/2" = 1'-0"

TACTILE CHARACTERS CENTERED WITHIN 18"X18" CLEAR FLOOR SPACE.

MINIMUM HEIGHT: BASELINE OF LOWEST COPY MOUNTED NO LOWER THAN 48" ABOVE FLOOR

MAXIMUM HEIGHT: BASELINE OF HIGHEST COPY MOUNTED NO HIGHER THAN 60" ABOVE FLOOR

10 TACTILE
SCALE: 3/8" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND IS NOT TO BE REPRODUCED IN WHOLE OR IN PART, OR USED FOR ANY OTHER PROJECT WITHOUT WRITTEN AUTHORIZATION BY DICKINSON ARCHITECTS, P.C. THIS DRAWING IS FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS EXPRESSLY LOANED UNDER THE FOLLOWING:
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:

JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	4/16/21	EA	35% SET
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA017272
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:

ACCESSIBILITY GUIDELINES

DRAWING NO:

T102

1 LIFE SAFETY PLAN
SCALE: 1/8" = 1'-0"

0' 2' 4' 8' 16' 32'
SCALE: 1/8" = 1'-0"

LIFE SAFETY CODE KEY

- SMOKE PARTITION
- 30 MIN RATED FIRE PARTITION
- 1 HOUR RATED FIRE PARTITION
- 2 HOUR RATED FIRE PARTITION
- 2 HOUR RATED FIRE WALL
- PATH OF EGRESS TRAVEL
- END OF COMMON PATH OF TRAVEL
- OCCUPANCY DESIGNATION (IBC) / PRIMARY USE FOR OCCUPANT LOAD (NFPA)
- # ROOM OCCUPANT LOAD
- ABC TYPE FIRE EXTINGUISHER
- K TYPE FIRE EXTINGUISHER
- INCIDENTAL USE AREA/ACCESSORY OCCUPANCY
- KB KNOX BOX
- CPT COMMON PATH OF TRAVEL
- TD TRAVEL DISTANCE TO EXIT
- EGRESS WIDTH
- EGRESS CAPACITY / # OF OCCUPANTS AT EXIT

OCCUPANT LOAD FACTORS (PER NFPA 7.3.1.2)

- (A) ASSEMBLY LESS CONCENTRATED - 15 NET SF
- (B) BUSINESS - 150 SF
- (C) CLASSROOM - 20 NET SF
- (DC) DAY CARE - 35 NET SF
- (K) KITCHEN - 100 SF
- (M) MERCANTILE - 30 SF
- (RT) RUNNING TRACK - 50 SF
- (S) STORAGE - 500 SF
- (V) WORKSHOP/VOCATIONAL - 50 NET SF

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND MAY NOT BE REPRODUCED OR PUBLISHED IN WHOLE OR IN PART, OR ANY OF THE INFORMATION CONTAINED ON THIS DRAWING OR FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS SUBJECT TO RESTITUTION. © 2021 DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	4/16/21	EA	35% SET
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA032370
REGISTERED ARCHITECT
2/10/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
LIFE SAFETY PLAN

DRAWING NO:
LS101

2 - 1-HR HORIZ. SHAFT WALL ASSEMBLY
SCALE: 1 1/2" = 1'-0"

*DETAIL IS TYPICAL FOR FIRE RATING & SOUND RATING

3 - INTERSECTION OF RATED WALLS
SCALE: 1 1/2" = 1'-0"

Design No. U305
July 29, 2021
Bearing Wall Rating — 1 Hr
Finish Rating — See Items 3, 3A, 3D, 3E, 3F, 3G, 3H, 3J and 3L.
STC Rating - 56 (See Item 9)

* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

1. Wood Studs — Nom 2 by 4 in. spaced 16 in. OC max, effectively firestopped.
2. Joints and Nail-Heads — Joints covered with joint compound and paper tape. Joint compound and paper tape may be omitted when square edge boards are used. As an alternate, nom 3/32 in. thick gypsum veneer plaster may be applied to the entire surface of Classified veneer baseboard with the joints reinforced with paper tape. Nailheads exposed or covered with joint compound.
3. Gypsum Board* — 5/8 in. thick paper or vinyl surfaced, with beveled, square, or tapered edges, applied either horizontally or vertically. Gypsum panels nailed 7 in. OC with 6d cement coated nails 1-7/8 in. long, 0.0915 in. shank diam and 15/64 in. diam heads. When used in widths other than 48 in., gypsum panels are to be installed horizontally.

AMERICAN GYPSUM CO — Types AGX-1(finish rating 23 min.), M-Glass (finish rating 23 min.), Type AGX-11 (finish rating 26 min), Type AGX-12 (finish rating 22 min), Type LightRoc (finish rating 23 min.) or Type AG-C

CERTAINTEED GYPSUM INC — Type C, Type X or Type X-1 (finish rating 26 min); Type EGRG or GlasRoc (finish rating 23 min), GlasRoc-2, Type Habito (finish rating 26 min).

CERTAINTEED GYPSUM INC — Type LGFC6A (finish rating 34 min), Type LGFC2A, Type LGFC-C/A, Type LGFC-WD, Type LGLLX (finish rating 21 min), Type CLLX (finish rating 24 min)

GEORGIA-PACIFIC GYPSUM L L C — Type 5 (finish rating 26 min), Type 6 (finish rating 23 min), Type 9 (finish rating 26 min), Type C (finish rating 26 min), Type DGG (finish rating 20 min), Type GPFS1 (finish rating 20 min), Type GPFS2 (finish rating 20 min), Type GPFS6 (finish rating 26 min), Type DS, Type DAP, Type DD (finish rating 20 min), Type DA, Type DAPC, Type LS (finish rating 23 min), Type X, Veneer Plaster Base - Type X, Water Rated - Type X, Sheathing - Type X, Soffit - Type X, Type LWX (finish rating 22 min), Veneer Plaster Base-Type LWX (finish rating 22 min), Water Rated-Type LWX (finish rating 22 min), Sheathing Type-LWX (finish rating 22 min), Soffit-Type LWX (finish rating 22 min), Type DGLW (finish rating 22 min), Water Rated-Type DGLW (finish rating 22 min), Sheathing Type- DGLW (finish rating 22 min), Soffit-Type DGLW (finish rating 22 min), Type LWX (finish rating 22 min), Type LW2X (finish rating 22 min), Veneer Plaster Base - Type LW2X (finish rating 22 min), Water Rated - Type LW2X (finish rating 22 min), Sheathing - Type LW2X (finish rating 22 min), Soffit - Type LW2X (finish rating 22 min), Type DGL2W (finish rating 22 min), Water Rated - Type DGL2W (finish rating 22 min), Sheathing - Type DGL2W (finish rating 22 min)

NATIONAL GYPSUM CO — Type FSK (finish rating 20 min), Type FSK-G (finish rating 20 min), Type FSW (finish rating 20 min), Type FSW-2 (finish rating 24 min), Type FSW-3 (finish rating 20 min), Type FSW-5 (finish rating 22 min), Type FSW-G (finish rating 20 min), Type FSK-C (finish rating 20 min), Type FSW-C (finish rating 20 min), Type FSMR-C, Type FSW-6 (finish rating 20 min), Type FSL (finish rating 24 min), Type FSW-8, Type FSLX (finish rating 21 min), Type RSX (finish rating 26 min).

PABCO BUILDING PRODUCTS L L C, DBA PABCO GYPSUM — Types C, PG-2 (finish rating 20 min), PG-3 (finish rating 20 min), Types PG-3W, PG-5W (finish rating 20 min), Type PG-4 (finish rating 20 min), Type PG-6 (finish rating 23 min), Types PG-3WS, PG-5WS, PGS-WRS (finish rating 20 min), Types PG-5, PG-9 (finish rating 26 min), PG-11 PG-13 (Nails increased to 2 in.), Type PG-C or PGI (finish rating 26 min)

UNITED STATES GYPSUM CO — Type AR (finish rating 24 min), Type C (finish rating 24 min), Type FRX-G (finish rating 29 min), Type IP-AR (finish rating 24 min), Type IPC-AR (finish rating 24 min), Type IP-X1 (finish rating 24 min), Type IP-X2 (finish rating 24 min), Type SHX (finish rating 24 min), Type SCX (finish rating 24 min), Type SGX (finish rating 24 min), Type ULX (finish rating 22 min), Type WRX (finish rating 24 min), Type WRC (finish rating 24 min), Type ULIX (finish rating 20 min)

5. Batts and Blankets* — (Optional — Required when Item 6A is used (RC-1)) — Glass fiber or mineral wool insulation. Placed to completely or partially fill the stud cavities. When Item 6A is used, glass fiber or mineral wool insulation shall be friction-fitted to completely fill the stud cavities.
CERTAINTEED CORP
JOHNS MANVILLE
KNAUF INSULATION LLC
MANSON INSULATION INC
ROCKWOOL — Types Acoustical Fire Batts and Type AFB, min. density 1.69 pcf / 27.0 kg/m^3
ROCK WOOL MANUFACTURING CO — Delta Board

THERMAFIBER INC — Type SAFB, SAFB FF

5C. Batts and Blankets* — Required for use with resilient channels, Item 7, 3 in. thick mineral wool batts, friction-fitted to fill interior of wall.
THERMAFIBER INC — Type SAFB, SAFB FF
5D. Glass Fiber Insulation — (As an alternate to Item 5C) — 3 in. thick glass fiber batts bearing the UL Classification Marking as to Surface Burning and/or Fire Resistance, friction-fitted to fill the interior of the wall. See Batts and Blankets (BKNV or BZJZ) Categories for names of Classified companies.
5E. Batts and Blankets* — (Required for use with Wall and Partition Facings and Accessories, Item 3D) — Glass fiber insulation, nom 3-1/2 in. thick, min. density of 0.80 pcf, with a flame spread of 25 or less and a smoke developed of 50 or less, friction-fitted to completely fill the stud cavities. See Batts and Blankets Category (BKNV) for names of manufacturers.
5F. Fiber, Sprayed* — (Optional, Not Shown — Not for use with Items 6, 6A, 6B, 6C, or 6D) — As an alternate to Batts and Blankets (Item 5) and Item 5A - Spray applied granulated mineral fiber material. The fiber is applied with adhesive, at a minimum density of 4.0 pcf, to completely fill the enclosed cavity in accordance with the application instructions supplied with the product. See Fiber, Sprayed (CCAZ).
AMERICAN ROCKWOOL MANUFACTURING, LLC — Type Rockwool Premium Plus
8. Caulking and Sealants — (Not Shown, Optional) — A bead of acoustical sealant applied around the partition perimeter for sound control.
* Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

*NOTE: SEE CURRENT UL DESIGN FOR FULL PRODUCT INFORMATION AND ALTERNATE ACCEPTABLE MATERIALS

Design No. U415
June 05, 2019

Nonbearing Wall Ratings — 1, 2, 3 or 4 Hr

*** Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.**

1. **Floor, Side and Ceiling Runners —** "J" - shaped runner, min 2-1/2 in. deep (min 4 in. deep when System C is used), with unequal legs of 1 in. and 2 in., fabricated from min 24 MSG (min 20 MSG when Item 4A, 4B, 4C, 4D or 7 are used) galv steel. Runners positioned with short leg toward finished side of wall. Runners attached to structural supports with steel fasteners located not greater than 2 in. from ends and not greater than 24 in. OC. "E" - shaped studs (Item 2A) may be used as side runners in place of "J" - shaped runners.
2. **Steel Studs —** "C-H" - shaped studs, min 2-1/2 in. deep (min 4 in. deep when System C is used), fabricated from min 25 MSG (min 20 MSG when Items 2D, 4A, 4B, 4C, 4D or 7 is used) galv steel. Cut to lengths 3/8 to 1/2 in. less than floor-to-ceiling height and spaced 24 in. or 600 mm OC (max 16 in. OC when Items 4A, 4B, 4C, or 4D are used).

3. **Gypsum Board* —** Gypsum liner panels, nom 1 in. thick, 24 in. or 600 mm (for metric spacing) wide. Panels cut 1 in. less in length than floor to ceiling height. Vertical edges inserted in "H" portion of "C-H" studs or the gap between the two 3/4 in. legs of the "E" studs. Free edge of end panels attached to long leg of vertical "J" - runners with 1-5/8 in. long Type S steel screws spaced not greater than 12 in. OC. When wall height exceeds liner panel length, liner panel may be butted to extend to the full height of the wall. Horizontal joints need not be backed by steel framing. In System I, butt joints in liner panels are staggered min 36 in. Butt joints backed with 6 in. by 22 in. strips of 3/4 in. thick gypsum wallboard (Item 4). Wallboard strips centered over butt joints and secured to liner panels with six 1-1/2 in. long Type G steel screws, three screws along the 22 in. dimension at the top and bottom of the strips.
CGC INC — Type SLX

UNITED STATES GYPSUM CO — Type SLX

USG BORAL DRYWALL SFZ LLC — Type SLX

USG MEXICO S A DE C V — Type SLX

4. **Gypsum Board* —**
System A — 1 Hr
Gypsum panels, with beveled, square or tapered edges, nom 5/8 in. thick, 48 in. or 1200 mm wide, applied vertically or horizontally, attached to studs with 1 in. long Type S steel screws spaced 12 in. when installed vertically or 8 in OC when installed horizontally. Horizontal joints need not be backed by steel framing.
CGC INC — Types AR, C, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, ULX, USGX, WRC, WRX

UNITED STATES GYPSUM CO — Types AR, C, FRX-G, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SGX, SHX, ULIX, ULX, WRC, WRX, USGX. When ULIX is used insulation, Item 6, **Batts and Blankets*** is required and minimum stud depth is 4 in.
5. **Joint Tape and Compound —** (Not Shown)
Systems A, B, C, E, F, G, H, I
Joints on outer layers of gypsum boards (Item 4 and 4A) covered with paper tape and joint compound. Paper tape and joint compound may be omitted when gypsum boards are supplied with square edges. Exposed screw heads covered with joint compound.
6. **Batts and Blankets* —**
Systems A, B, E, F, G, H, I
(Optional) — Mineral wool or glass fiber batts partially or completely filling stud cavity. Any mineral wool or glass fiber batt mineral bearing the UL Classification Marking as to Fire Resistance.
System A With Type ULIX Gypsum Boards
Placed in stud cavities, any min. 3-1/2 in. thick glass fiber insulation bearing the UL Classification Marking as to Surface Burning Characteristics and/or Fire Resistance. See **Batts and Blankets (BKNV or BZJZ) Categories** for names of Classified companies.

*** Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.**

*NOTE: SEE CURRENT UL DESIGN FOR FULL PRODUCT INFORMATION AND ALTERNATE ACCEPTABLE MATERIALS

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C., AND WAS NOT PREPARED FOR USE ON ANY OTHER PROJECT. THE REPRODUCTION, IN WHOLE OR PART, OF ANY DRAWING, INFORMATION, OR DATA CONTAINED HEREIN, FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS PROHIBITED WITHOUT THE WRITTEN CONSENT OF DICKINSON ARCHITECTS, P.C.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA017275
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
UL DETAILS & FIRESTOPPING DETAILS

DRAWING NO:
LS102

1 ARCHITECTURAL SITE PLAN
SCALE: 1" = 20'-0"

GENERAL NOTES:

1. FOR REFERENCE ONLY. SEE CIVIL DRAWINGS UNDER SEPARATE CONTRACT.

N

0 5' 10' 20' 40' 80'
SCALE: 1" = 20'

dickinson
ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C., AND IS NOT TO BE REPRODUCED IN WHOLE OR IN PART, OR TO BE GIVEN TO OTHERS OUTSIDE THEIR ORGANIZATION, OR USED FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS SUBJECT TO STATUTORY PROTECTION.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	4/16/21	EA	35% SET
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA017275
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:
ARCHITECTURAL SITE PLAN

DRAWING NO:
A100

1 DIMENSION FLOOR PLAN
SCALE: 1/8" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND IS NOT TO BE REPRODUCED IN WHOLE OR IN PART, OR USED FOR ANY OTHER PERSON OR PURPOSE, WITHOUT WRITTEN PERMISSION. INFORMATION SHOWN ON THIS DRAWING FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS RESERVED BY THE ARCHITECT.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	4/16/21	EA	35% SET
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA31073
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:
DIMENSION FLOOR PLAN

DRAWING NO:
A101

APPLIANCE SCHEDULE		
⊗	DESCRIPTION	REMARK
A	UNDERCOUNTER ICE MAKER	FBO/IBC
B	UNDERCOUNTER REFRIGERATOR	FBO/IBC
C	REFRIGERATOR	FBO/IBC
D	DRYER	FBO/IBC
E	WASHER	FBO/IBC

WALL LEGEND

- WOOD STUD WALL
- METAL STUD WALL
- BRICK WALL
- WALL TYPES, SEE DWG A601

1 REFERENCE FLOOR PLAN - PHASE 1
SCALE: 1/8" = 1'-0"

0' 2' 4' 8' 16' 32'
SCALE: 1/8" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND MAY NOT BE REPRODUCED OR PUBLISHED IN ANY FORM, IN WHOLE OR IN PART, WITHOUT WRITTEN PERMISSION. ALL DRAWINGS, INFORMATION, DESIGN, SPECIFICATIONS, OR FORMS MAY ETHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS THE PROPERTY OF DICKINSON ARCHITECTS.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS			
REV #	DATE	APRVD BY	REVISION
	4/16/21	EA	35% SET
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. R-041277
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
REFERENCE FLOOR PLAN - PHASE 1

DRAWING NO:
A102

1 PARTIAL FLOOR PLAN - PHASE 2
SCALE: 1/8" = 1'-0"

2 PARTIAL ROOF PLAN - PHASE 2
SCALE: 1/8" = 1'-0"

3 PARTIAL REFLECTED CEILING PLAN - PHASE 2
SCALE: 1/8" = 1'-0"

CEILING LEGEND:

GYPSUM BOARD CEILING

RECESSED FIXTURE

4 PARTIAL NORTH DEMOLITION ELEVATION
SCALE: 1/8" = 1'-0"

5 PARTIAL EAST DEMOLITION ELEVATION
SCALE: 1/8" = 1'-0"

GENERAL DEMOLITION NOTES:

1. GC TO PROTECT ALL ADJACENT SURFACES TO REMAIN FROM DAMAGE DURING CONSTRUCTION. GC TO REPAIR/REPLACE ANY ADJACENT SURFACES DAMAGED DURING CONSTRUCTION TO MATCH ORIGINAL CONDITIONS.
2. GC TO FIELD VERIFY CONDITIONS PRIOR TO START OF CONSTRUCTION.
3. EXISTING CONDITIONS & DEMOLITION NOTES BASED ON FIELD SURVERY. IF GC DISCOVERS EXISTING CONDITIONS VARY FROM THOSE SHOWN, CONTACT OWNER OR ARCHITECT IMMEDIATELY.
4. GC TO PROVIDE TEMPORARY PROTECTION FOR ALL OPENINGS IN EXTERIOR WALLS. PROTECTION SHALL CONSIST OF 6 MIL. PLASTIC.
5. COORDINATE DEMOLITION WITH ELECTRICAL, MECHANICAL, PLUMBING, & STRUCTRURAL DRAWINGS.
6. ALL DEMOLITION WORK SHALL COMPLY WITH THE REQUIREMENTS OF THE 2016 EDITION OF NFPA 241, STANDARD FOR SAFEGUARDING CONSTRUCTION, ALTERATION, & DEMOLITION OPERATIONS.

DEMOLITION NOTES:

A. DEMO PORTION OF WALL & PREP FOR NEW OPENING.

B. DEMO SOFFITS, TRIM, & GUTTERS AS REQUIRED.

C. DEMO EXTERIOR FINISH OF WALL. PREP FOR NEW INTERIOR FINISH PER ASSOCIATED WALL TYPE.

N

0' 2' 4' 8' 16' 32'
SCALE: 1/8" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, INC. AND IS RESTRICTED TO THE USE FOR WHICH IT WAS CAUSED TO BE PRODUCED. ANY REPRODUCTION, INFORMATION, OR DRAWING, OR FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS ASSUMED TO BE FORBIDDEN WITHOUT PERMISSION.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS			
REV #	DATE	APRVD BY	REVISION
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moselley Armstrong
CERTIFICATE NO. RA012272
REGISTERED ARCHITECT
2/10/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:
PARTIAL PLANS & ELEVATIONS - PHASE 2

DRAWING NO:
A102.1

1 ROOF PLAN - PHASE 1
SCALE: 1/8" = 1-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND MAY NOT BE REPRODUCED OR PUBLISHED IN WHOLE OR IN PART, OR ANY OF THE ATTACHED INFORMATION, BY ANYONE OR FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS TRANSFERRED FOR USE ON THIS PROJECT.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	4/16/21	EA	35% SET
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA012775
REGISTERED ARCHITECT
2/10/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:
ROOF PLAN - PHASE 1

DRAWING NO:
A105

1 FIRST FLOOR RCP - PHASE 1
SCALE: 1/8" = 1'-0"

0' 2' 4' 8' 16' 32'
SCALE: 1/8" = 1'-0"

CEILING LEGEND

- ACOUSTICAL CEILING PANEL
- SPECIALTY ACOUSTICAL CEILING PANEL
- GYPSUM BOARD CEILING
- T & G WOOD CEILING
- STAINLESS STEEL CEILING PANEL
- RECESSED FIXTURE
- WALL SCONCE
- DECORATIVE CHANDELIER
- LINEAR FIXTURE
- TRACK LIGHTING
- GYM LIGHTING
- EMERGENCY FIXTURE
- EXIT LIGHT
- MECHANICAL SUPPLY AIR DEVICE
- MECHANICAL RETURN AIR DEVICE
- EXHAUST
- CEILING ACCESS PANEL
- WALL TO DECK/STRUCTURE ABOVE
- SOUND INSULATION ABOVE CEILING

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND IS NOT TO BE REPRODUCED OR PUBLISHED IN WHOLE OR IN PART, OR USED FOR OTHER PURPOSES, INFORMATION, OR DRAWING ON FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C. AND IS SUBJECT TO RESTITUTION. © DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	4/16/21	EA	35% SET
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA017275
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:
FIRST FLOOR RCP - PHASE 1

DRAWING NO:
A106

1 WEST ELEVATION
SCALE: 1/8" = 1'-0"

2 NORTH ELEVATION
SCALE: 1/8" = 1'-0"

3 EAST ELEVATION
SCALE: 1/8" = 1'-0"

4 SOUTH ELEVATION
SCALE: 1/8" = 1'-0"

0' 2' 4' 8' 16' 32'
SCALE: 1/8" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND IS INTENDED FOR THE SPECIFIC PROJECT AND SITE AS NOTED. THE REPRODUCTION, DISTRIBUTION, OR DISCLOSURE OF THE CONTAINED INFORMATION IN ANY FORM MAY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C. AND IS PROHIBITED WITHOUT THE WRITTEN CONSENT.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	4/16/21	EA	35% SET
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA012275
REGISTERED ARCHITECT
2/10/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
BUILDING ELEVATIONS - PHASE 1

DRAWING NO:
A201

1 WEST ELEVATION - PHASE 2
SCALE: 1/8" = 1'-0"

2 NORTH ELEVATION - PHASE 2
SCALE: 1/8" = 1'-0"

3 EAST ELEVATION - PHASE 2
SCALE: 1/8" = 1'-0"

4 SOUTH ELEVATION - PHASE 2
SCALE: 1/8" = 1'-0"

0' 2' 4' 8' 16' 32'
SCALE: 1/8" = 1'-0"

dickinson
ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the
American Institute of
Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND IS NOT TO BE REPRODUCED IN WHOLE OR IN PART WITHOUT WRITTEN PERMISSION. THE INFORMATION, DESIGN, AND SURROUNDING INFORMATION IN THIS DRAWING ARE FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS TO BE RETURNED UPON REQUEST.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C
HICKEY
CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA012775
REGISTERED ARCHITECT
2/10/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:
BUILDING
ELEVATIONS
PHASE 2

DRAWING NO:
A202

1 A102 BUILDING SECTION
SCALE: 1/8" = 1'-0"

2 A102.1 BUILDING SECTION
SCALE: 1/8" = 1'-0"

3 A102 BUILDING SECTION
SCALE: 1/8" = 1'-0"

GENERAL NOTES:

1. SEE STRUCTURAL FOR PRE-ENGINEERED ROOF TRUSSES. MAJORITY OF ROOF FRAMING NOT SHOWN ON ARCHITECTURAL, BUT IS REQUIRED.
2. GC TO COORD. ALL ABOVE-CEILING M/E/P/FP EQUIPMENT W/ ROOF TRUSS DESIGN.

0' 2' 4' 8' 16' 32'
SCALE: 1/8" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND IS NOT TO BE REPRODUCED OR PUBLISHED IN WHOLE OR IN PART, OR USED FOR OTHER PURPOSES, WITHOUT WRITTEN PERMISSION. ALTERING, REPRODUCING, INFORMATION ON DRAWING OR FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C. AND IS PROHIBITED BY THE OWNER OF THE PROJECT.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA012272
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:
BUILDING SECTIONS

DRAWING NO:
A301

1 A102.1 BUILDING SECTION
SCALE: 1/8" = 1'-0"

2 A102 BUILDING SECTION
SCALE: 1/8" = 1'-0"

3 A102 BUILDING SECTION
SCALE: 1/8" = 1'-0"

GENERAL NOTES:

1. SEE STRUCTURAL FOR PRE-ENGINEERED ROOF TRUSSES. MAJORITY OF ROOF FRAMING NOT SHOWN ON ARCHITECTURAL, BUT IS REQUIRED.
2. GC TO COORD. ALL ABOVE-CEILING M/E/P/FP EQUIPMENT W/ ROOF TRUSS DESIGN.

0' 2' 4' 8' 16' 32'
SCALE: 1/8" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND MAY NOT BE REPRODUCED OR PUBLISHED IN WHOLE OR IN PART, NOR MAY THE INFORMATION CONTAINED HEREIN BE DISCLOSED OR FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS SUBJECT TO RESTRICTIONS OF COPYRIGHT.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS			
REV #	DATE	APRVD BY	REVISION
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA013771
REGISTERED ARCHITECT
2/10/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:
BUILDING SECTIONS

DRAWING NO:
A302

1 A102 BUILDING SECTION
SCALE: 1/8" = 1'-0"

2 A102 BUILDING SECTION
SCALE: 1/8" = 1'-0"

GENERAL NOTES:

1. SEE STRUCTURAL FOR PRE-ENGINEERED ROOF TRUSSES. MAJORITY OF ROOF FRAMING NOT SHOWN ON ARCHITECTURAL, BUT IS REQUIRED.
2. GC TO COORD. ALL ABOVE-CEILING M/E/P/FP EQUIPMENT W/ ROOF TRUSS DESIGN.

0' 2' 4' 8' 16' 32'
SCALE: 1/8" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND MAY NOT BE REPRODUCED OR PUBLISHED IN WHOLE OR IN PART, OR USED FOR OTHER SURROUNDING INFORMATION, BY OTHERS, OR FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS TRANSFERRED ONLY FOR USE ON THIS PROJECT.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:

JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO.: RA012272
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:

BUILDING SECTIONS

DRAWING NO:

A303

GENERAL NOTES:

1. SEE STRUCTURAL FOR PRE-ENGINEERED ROOF TRUSSES. MAJORITY OF ROOF FRAMING NOT SHOWN ON ARCHITECTURAL, BUT IS REQUIRED.
2. GC TO COORD. ALL ABOVE-CEILING M/E/P/FP EQUIPMENT W/ ROOF TRUSS DESIGN.

1 A301 WALL SECTION
SCALE: 3/4" = 1'-0"

2 A301 WALL SECTION
SCALE: 3/4" = 1'-0"

3 A301 WALL SECTION
SCALE: 3/4" = 1'-0"

0' 4" 8" 1'-4" 2'-8" 4'
SCALE: 3/4" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND MAY NOT BE REPRODUCED OR PUBLISHED IN ANY WAY WITHOUT WRITTEN PERMISSION. ALTHOUGH INFORMATION ON DRAWING OR FOR MAY - OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS THE PROPERTY OF THE PROJECT OWNER.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA012272
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:
WALL SECTIONS

DRAWING NO:
A310

GENERAL NOTES:

1. SEE STRUCTURAL FOR PRE-ENGINEERED ROOF TRUSSES. MAJORITY OF ROOF FRAMING NOT SHOWN ON ARCHITECTURAL, BUT IS REQUIRED.
2. GC TO COORD. ALL ABOVE-CEILING M/E/P/FP EQUIPMENT W/ ROOF TRUSS DESIGN.

1 A302 WALL SECTION
SCALE: 3/4" = 1'-0"

2 A302 WALL SECTION
SCALE: 3/4" = 1'-0"

3 A102 WALL SECTION
SCALE: 3/4" = 1'-0"

0' 4" 8" 1'-4" 2'-8" 4'
SCALE: 3/4" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C., AND WAS OR WILL BE PREPARED FOR USE ON THIS PROJECT ONLY. IT IS NOT TO BE USED ON OTHER SURROUNDING INFORMATION, OR DRAWING FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS TO BE RETURNED UPON REQUEST.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS			
REV #	DATE	APRVD BY	REVISION
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA013775
REGISTERED ARCHITECT
2/10/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
WALL SECTIONS

DRAWING NO:
A311

GENERAL NOTES:

1. SEE STRUCTURAL FOR PRE-ENGINEERED ROOF TRUSSES. MAJORITY OF ROOF FRAMING NOT SHOWN ON ARCHITECTURAL, BUT IS REQUIRED.
2. GC TO COORD. ALL ABOVE-CEILING M/E/P/FP EQUIPMENT W/ ROOF TRUSS DESIGN.

1 / A302 WALL SECTION
SCALE: 3/4" = 1'-0"

2 / A302 WALL SECTION
SCALE: 3/4" = 1'-0"

0' 4" 8" 1'-4" 2'-8" 4'
SCALE: 3/4" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND MUST BE RETURNED ON REQUEST. IT SHALL NOT BE REPRODUCED, COPIED OR LENT TO THIRD PARTIES WITHOUT WRITTEN PERMISSION. SUPPLYING INFORMATION TO DRAWING OR FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS SUBMITTED UPON THE FOLLOWING TERMS:
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA027277
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
WALL SECTIONS

DRAWING NO:
A312

GENERAL NOTES:

1. SEE STRUCTURAL FOR PRE-ENGINEERED ROOF TRUSSES. MAJORITY OF ROOF FRAMING NOT SHOWN ON ARCHITECTURAL, BUT IS REQUIRED.
2. GC TO COORD. ALL ABOVE-CEILING M/E/P/FP EQUIPMENT W/ ROOF TRUSS DESIGN.

NOTE:
THIS WALL IS EXTERIOR ONLY UNTIL PHASE 2 IS CONSTRUCTED. EXTERIOR FINISHES TO BE REMOVED IN PHASE 2. COORDINATE WITH STRUCTURAL DETAILS.

1 A102 WALL SECTION
SCALE: 3/4" = 1'-0"

NOTE:
THIS WALL IS EXTERIOR ONLY UNTIL PHASE 2 IS CONSTRUCTED. EXTERIOR FINISHES TO BE REMOVED IN PHASE 2.

2 A102 WALL SECTION
SCALE: 3/4" = 1'-0"

0' 4" 8" 1'-4" 2'-8" 4'
SCALE: 3/4" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C., AND NOT TO BE REPRODUCED OR USED FOR ANY OTHER PROJECT WITHOUT WRITTEN PERMISSION. ALL DRAWINGS, SPECIFICATIONS, AND OTHER SUPPORTING INFORMATION, OR DRAWINGS OR FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS THE EXCLUSIVE OWNERSHIP OF DICKINSON ARCHITECTS, P.C.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS			
REV #	DATE	APRVD BY	REVISION
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA013270
REGISTERED ARCHITECT
2/10/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
WALL SECTIONS PHASE 1

DRAWING NO:
A313

1 A310 FOUNDATION DETAIL
SCALE: 1 1/2" = 1'-0"

2 A310 FOUNDATION DETAIL
SCALE: 1 1/2" = 1'-0"

3 A311 FLASHING DETAIL
SCALE: 1 1/2" = 1'-0"

4 A102 ROOF TRANSITION DETAIL
SCALE: 1 1/2" = 1'-0"

5 A302 ROOF/FLASHING DETAIL
SCALE: 1 1/2" = 1'-0"

6 A102 DOUBLE COLUMN BASE DETAIL
SCALE: 3/4" = 1'-0"

7 A102 DOUBLE COLUMN BASE DETAIL
SCALE: 3/4" = 1'-0"

8 - PORTE-COCHERE COLUMN SECTION
SCALE: 3/4" = 1'-0"

NOTE: CONTRACTOR TO SUBMIT NAILING PATTERNS FOR ENGINEER REVIEW.

9 A201 DECORATIVE GABLE TRUSS
SCALE: 1/2" = 1'-0"

10 A310 CANOPY DETAIL
SCALE: 1 1/2" = 1'-0"

11 A201 CANOPY ELEVATION
SCALE: 3/4" = 1'-0"

NOTES:
1. BUILD FROM STAIN GRADE FIR
2. SEE ELEVATIONS FOR SINGLE V. DOUBLE BRACKET LOCATIONS

12 A202 BRACKET 1 DETAIL
SCALE: 1 1/2" = 1'-0"

13 A303 PORCH RAKE DETAIL
SCALE: 3/4" = 1'-0"

0' 6" 1' 2' 4' 8'
SCALE: 1/2" = 1'-0"

0' 4" 8" 1'-4" 2'-8" 4'
SCALE: 3/4" = 1'-0"

0' 2" 4" 8" 1'-4" 2'-8"
SCALE: 1-1/2" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND IS NOT TO BE REPRODUCED OR PUBLISHED IN WHOLE OR IN PART, OR USED FOR OTHERWISE INFORMATION, BY OTHERS, OR FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS SUBJECT TO RESTRICTIONS AND OBJECTIONS.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS			
REV #	DATE	APRVD BY	REVISION
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA013775
REGISTERED ARCHITECT
2/10/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
EXTERIOR DETAILS

DRAWING NO:
A321

1 A105 ENTRY TRUSS SECTION
SCALE: 1/2" = 1'-0"

10 A321 BEAM AND EAVE DETAIL
SCALE: 1" = 1'-0"

NOTES:
1. BUILD FROM STAIN GRADE FIR

6 A201 BRACKET 2 DETAIL
SCALE: 1" = 1'-0"

2 A201 TRUSS ELEVATION
SCALE: 1/4" = 1'-0"

11 A105 BEAM AND EAVE DETAIL
SCALE: 3/4" = 1'-0"

5 A301 ROOF ENDWALL DETAIL
SCALE: 1 1/2" = 1'-0"

3 A302 EAVE DETAIL
SCALE: 1 1/2" = 1'-0"

4 A301 EAVE @ DORMER DETAIL
SCALE: 1 1/2" = 1'-0"

7 A102 TYPICAL CORNER BOARD DETAIL
SCALE: 1 1/2" = 1'-0"

8 A102 ENGAGED COLUMN DETAIL
SCALE: 3/4" = 1'-0"

9 A102 PORCH COLUMN DETAIL
SCALE: 3/4" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND MAY NOT BE REPRODUCED OR PUBLISHED IN WHOLE OR IN PART, OR ANY OF THE INFORMATION CONTAINED HEREIN, OR DRAWING OR FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS SUBJECT TO RESTRICTIONS OF SALE.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS			
REV #	DATE	APRVD BY	REVISION
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA9107
REGISTERED ARCHITECT
2/10/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:
EXTERIOR DETAILS

DRAWING NO:
A322

1 A102.1 FAUX WINDOW DETAIL
SCALE: 1 1/2" = 1'-0"

2 A102 COLUMN WRAP DETAIL
SCALE: 1 1/2" = 1'-0"

3 A105 WALKWAY ROOF SECTION
SCALE: 1/2" = 1'-0"

4 A310 EAVE DETAIL
SCALE: 1 1/2" = 1'-0"

5 A311 RAKE DETAIL
SCALE: 1 1/2" = 1'-0"

6 A311 SOFFIT DETAIL
SCALE: 1 1/2" = 1'-0"

7 A201 BAND BOARD DETAIL
SCALE: 1 1/2" = 1'-0"

8 A105 LOUVER VENT DETAIL
SCALE: 3/4" = 1'-0"

0' 6" 1' 2' 4' 8'
SCALE: 1/2" = 1'-0"

0' 4" 8" 1'-4" 2'-8" 4'
SCALE: 3/4" = 1'-0"

0' 2" 4" 8" 1'-4" 2'-8"
SCALE: 1-1/2" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND IS NOT TO BE REPRODUCED IN WHOLE OR IN PART, OR TO BE GIVEN TO PERSONS OTHER THAN THOSE ENTITLED TO THE PERTINENT INFORMATION, OR USED FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS LOANED UPON THE CONDITIONS HEREIN.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA9107
REGISTERED ARCHITECT
2/10/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
EXTERIOR DETAILS

DRAWING NO:
A323

1 / A302 CEILING DETAIL
SCALE: 1" = 1'-0"

6 / A102 FAUX WINDOW JAMB DETAIL
SCALE: 1 1/2" = 1'-0"

10 / A102 ENLARGED BUILDOUT PLAN
SCALE: 1 1/2" = 1'-0"

15 / A102 FEC PLAN DETAIL
SCALE: 3/4" = 1'-0"

2 / A106 FAUX BEAM DETAIL
SCALE: 1 1/2" = 1'-0"

7 / A303 FAUX WINDOW HEAD/SILL
SCALE: 1 1/2" = 1'-0"

11 / - ELEVATED HEARTH DETAIL
SCALE: 3/4" = 1'-0"

16 / - RECESSED FEC DETAIL
SCALE: 3/4" = 1'-0"

3 / A106 FAUX BEAM DETAIL
SCALE: 1 1/2" = 1'-0"

12 / A106 TYPICAL BULKHEAD DETAIL
SCALE: 1 1/2" = 1'-0"

17 TYPICAL HANDRAIL DETAIL
SCALE: 1 1/2" = 1'-0"

4 / A301 ACCORDION PARTITION HEAD DETAIL
SCALE: 1 1/2" = 1'-0"

13 / A301 CEILING DETAIL
SCALE: 1 1/2" = 1'-0"

5 / A102 ENLARGED FIREPLACE PLAN
SCALE: 3/4" = 1'-0"

9 / A302 DRAPERY ROD DETAIL
SCALE: 1 1/2" = 1'-0"

14 / - ACCESS PANEL DETAIL
SCALE: 1 1/2" = 1'-0"

0' 4" 8" 1'-4" 2'-8" 4'
SCALE: 3/4" = 1'-0"

0' 2" 4" 8" 1'-4" 2'-8"
SCALE: 1-1/2" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND IS NOT TO BE REPRODUCED OR PUBLISHED IN WHOLE OR IN PART, OR USED FOR SURROUNDING INFORMATION ON DRAWING OR FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS TO BE RETURNED UPON REQUEST.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA91071
REGISTERED ARCHITECT
2/10/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:
INTERIOR DETAILS

DRAWING NO:
A331

1 / A102 TOILET 137 & 138 PLAN
SCALE: 1/2" = 1'-0"

3 / - TOILET 137 & 138, TYP.
SCALE: 1/2" = 1'-0"

4 / - TOILET 137 & 138, TYP.
SCALE: 1/2" = 1'-0"

5 / - TOILET 137 & 138, TYP.
SCALE: 1/2" = 1'-0"

6 / - TOILET 137 & 138, TYP.
SCALE: 1/2" = 1'-0"

2 / A102 TOILET 104 & 105 PLAN
SCALE: 1/2" = 1'-0"

7 / - TOILET 104
SCALE: 1/2" = 1'-0"

8 / - TOILET 104
SCALE: 1/2" = 1'-0"

9 / - TOILET 104
SCALE: 1/2" = 1'-0"

10 / - TOILET 104
SCALE: 1/2" = 1'-0"

11 / - TOILET 105
SCALE: 1/2" = 1'-0"

12 / - TOILET 105
SCALE: 1/2" = 1'-0"

13 / - TOILET 105
SCALE: 1/2" = 1'-0"

14 / - TOILET 105
SCALE: 1/2" = 1'-0"

TOILET ACCESSORY SCHEDULE			
-	MANUFACTURER	DESCRIPTION	MODEL
A	WINGITS	MODERN ELEGANCE 36" GRAB BAR	WGB5MESN36
B	WINGITS	MODERN ELEGANCE 42" GRAB BAR	WGB5MESN42
C	WINGITS	MODERN ELEGANCE 18" GRAB BAR	WGB5MESN18
D	WINGITS	MODERN ELEGANCE DOUBLE TOILET PAPER HOLDER	WMEDTPHSN
E	LAMPS PLUS	HELENA ANTIQUE SILVER 25" X 42" WALL MIRROR	47A99
F	BRADLEY CORPORATION	PAPER TOWEL DISPENSER / WASTE BIN	270-000000
G	WINGITS	MODERN ELEGANCE 24" GRAB BAR	WGB5MESN24
H	WINGITS	MODERN ELEGANCE 54" GRAB BAR	WGB5MESN54
J	WINGITS	MODERN ELEGANCE ROBE HOOK	WME5RHSN
K	INPRO CORP	SHOWER CURTAIN W/ TRACK	SEE A801 FOR INFO
L	BRADLEY CORPORATION	NAPKIN DISPOSAL, 1.5 GALLONS, SURFACE-MOUNTED	4722-150000
M	TORK	FOAM SOAP DISPENER W/ INTUITION SENSOR, STAINLESS STEEL	466100
N	BRADLEY CORPORATION	UTILITY SHELF, 4 HOOKS / 3 HOLDERS	9333

TYP. TOILET ACCESSORY MOUNTING HEIGHTS

NOTE: FRP & MOP/BROOM HOLDER TYP. ALL JANITOR CLOSETS

15 / A102 JAN. CLST., TYP.
SCALE: 1/2" = 1'-0"

16 / - JAN. CLST., TYP.
SCALE: 1/2" = 1'-0"

17 / - JAN. CLST., TYP.
SCALE: 1/2" = 1'-0"

0' 6' 1' 2' 4' 8'
SCALE: 1/2" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND IS NOT TO BE REPRODUCED IN WHOLE OR IN PART, OR TO BE GIVEN TO PERSONS OR ENTERPRISES WHO HAVE NOT AGREED TO BE BOUND BY THE FOREGOING INFORMATION. IT IS FURNISHED FOR ANY ESTATE PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS TO BE RETURNED UPON REQUEST.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS			
REV #	DATE	APRVD BY	REVISION
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA012272
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:
ENLARGED TOILET PLANS

DRAWING NO:
A401

1 A102 RESTROOMS 118 & 119
SCALE: 1/2" = 1'-0"

3 TOILET 118
SCALE: 1/2" = 1'-0"

4 TOILET 118
SCALE: 1/2" = 1'-0"

5 TOILET 118
SCALE: 1/2" = 1'-0"

6 TOILET 118
SCALE: 1/2" = 1'-0"

15 TOILET 119
SCALE: 1/2" = 1'-0"

16 TOILET 119
SCALE: 1/2" = 1'-0"

17 TOILET 119
SCALE: 1/2" = 1'-0"

18 TOILET 119
SCALE: 1/2" = 1'-0"

TOILET ACCESSORY SCHEDULE			
-	MANUFACTURER	DESCRIPTION	MODEL
A	WINGITS	MODERN ELEGANCE 36" GRAB BAR	WGB5MEGN36
B	WINGITS	MODERN ELEGANCE 42" GRAB BAR	WGB5MEGN42
C	WINGITS	MODERN ELEGANCE 18" GRAB BAR	WGB5MEGN18
D	WINGITS	MODERN ELEGANCE DOUBLE TOILET PAPER HOLDER	WMEDTPHGN
E	LAMPS PLUS	HELENA ANTIQUE SILVER 25" X 42" WALL MIRROR	47A99
F	BRADLEY CORPORATION	PAPER TOWEL DISPENSER / WASTE BIN	270-000000
G	WINGITS	MODERN ELEGANCE 24" GRAB BAR	WGB5MEGN24
H	WINGITS	MODERN ELEGANCE 54" GRAB BAR	WGB5MEGN54
J	WINGITS	MODERN ELEGANCE ROBE HOOK	WMEGRHGN
K	INPRO CORP	SHOWER CURTAIN W/ TRACK	SEE A801 FOR INFO
L	BRADLEY CORPORATION	NAPKIN DISPOSAL, 1.5 GALLONS, SURFACE-MOUNTED	4722-150000
M	TORK	FOAM SOAP DISPENER W/ INTUITION SENSOR, STAINLESS STEEL	466100
N	BRADLEY CORPORATION	UTILITY SHELF, 4 HOOKS / 3 HOLDERS	9933

TYP. TOILET ACCESSORY MOUNTING HEIGHTS

11 TOILET STALL, TYP.
SCALE: 1/2" = 1'-0"

12 TOILET STALL, TYP.
SCALE: 1/2" = 1'-0"

13 TOILET STALL, TYP.
SCALE: 1/2" = 1'-0"

14 TOILET STALL, TYP.
SCALE: 1/2" = 1'-0"

0' 6" 1' 2' 4' 8'
SCALE: 1/2" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND IS NOT TO BE REPRODUCED OR PUBLISHED IN WHOLE OR IN PART, OR USED FOR OTHERWISE INFORMATION, EXCEPT AS PERMITTED BY LAW. OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS ON THE EXPRESS CONDITION THAT THE PROJECT.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS			
REV #	DATE	APRVD BY	REVISION
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA012275
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
ENLARGED TOILET PLANS

DRAWING NO:
A402

1 / A102 SHOWER 110 & TOILET 111 PLAN
SCALE: 1/2" = 1'-0"

3 / - SHOWER 110
SCALE: 1/2" = 1'-0"

4 / - SHOWER 110
SCALE: 1/2" = 1'-0"

5 / - SHOWER 110
SCALE: 1/2" = 1'-0"

6 / - SHOWER 110
SCALE: 1/2" = 1'-0"

7 / - TOILET 111
SCALE: 1/2" = 1'-0"

8 / - TOILET 111
SCALE: 1/2" = 1'-0"

9 / - TOILET 111
SCALE: 1/2" = 1'-0"

10 / - TOILET 111
SCALE: 1/2" = 1'-0"

16 / - TOILET 107 & 108 TYP.
SCALE: 1/2" = 1'-0"

17 / - TOILET 107 & 108 TYP.
SCALE: 1/2" = 1'-0"

18 / - TOILET 107 & 108 TYP.
SCALE: 1/2" = 1'-0"

19 / - TOILET 107 & 108 TYP.
SCALE: 1/2" = 1'-0"

15 / A102 TOILET 107 & 108 PLAN
SCALE: 1/2" = 1'-0"

2 / A102 TOILET 141 & 142
SCALE: 1/2" = 1'-0"

11 / - TOILET 141 & 142
SCALE: 1/2" = 1'-0"

12 / - TOILET 141 & 142
SCALE: 1/2" = 1'-0"

13 / - TOILET 141 & 142
SCALE: 1/2" = 1'-0"

14 / - TOILET 141 & 142
SCALE: 1/2" = 1'-0"

TOILET ACCESSORY SCHEDULE			
-	MANUFACTURER	DESCRIPTION	MODEL
A	WINGITS	MODERN ELEGANCE 36" GRAB BAR	WGB5MESN36
B	WINGITS	MODERN ELEGANCE 42" GRAB BAR	WGB5MESN42
C	WINGITS	MODERN ELEGANCE 18" GRAB BAR	WGB5MESN18
D	WINGITS	MODERN ELEGANCE DOUBLE TOILET PAPER HOLDER	WMEDTPHSN
E	LAMPS PLUS	HELENA ANTIQUE SILVER 25" X 42" WALL MIRROR	47A99
F	BRADLEY CORPORATION	PAPER TOWEL DISPENSER / WASTE BIN	270-000000
G	WINGITS	MODERN ELEGANCE 24" GRAB BAR	WGB5MESN24
H	WINGITS	MODERN ELEGANCE 54" GRAB BAR	WGB5MESN54
J	WINGITS	MODERN ELEGANCE ROBE HOOK	WMESRHSN
K	INPRO CORP	SHOWER CURTAIN W/ TRACK	SEE A801 FOR INFO
L	BRADLEY CORPORATION	NAPKIN DISPOSAL, 1.5 GALLONS, SURFACE-MOUNTED	4722-150000
M	TORK	FOAM SOAP DISPENER W/ INTUITION SENSOR, STAINLESS STEEL	466100
N	BRADLEY CORPORATION	UTILITY SHELF, 4 HOOKS / 3 HOLDERS	9933

TYP. TOILET ACCESSORY MOUNTING HEIGHTS

0' 6" 1' 2' 4' 8'
SCALE: 1/2" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C., AND WAS OR WILL BE PREPARED FOR USE ON THIS PROJECT ONLY. IT IS NOT TO BE USED ON OTHER PROJECTS OR FOR ADDITIONS TO THIS PROJECT BY OTHERS, OR FURNISHING INFORMATION TO OTHERS FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS THE COMMON LAW COPYRIGHT PROPERTY OF DICKINSON ARCHITECTS, P.C.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS			
REV #	DATE	APRVD BY	REVISION
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA012173
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
ENLARGED TOILET PLANS

DRAWING NO:
A403

1 A102 ENLARGED KITCHEN PLAN
SCALE: 1/4" = 1'-0"

EQUIPMENT SCHEDULE		
Item No	Qty	Equipment Category
1	1	Dry Storage Shelving
2	2	Sink, Hand, Wall Mount
3	1	Ice Maker w/ Bin
4	2	Dish Dolly, Adjustable
5	–	–Spare Number–
6	1	Beverage Counter
7	1	Soda/Ice Dispenser (By Vendor)
8	1	Iced Tea Brewer (USF Beverage)
9	2	Tea Dispenser (USF Beverage)
10	–	–Spare Number–
11	1	Coffee Maker (USF Beverage)
12	1	Hot Food Table
13	1	Work Table
14	1	Pass Thru Shelf
15	–	–Spare Number–
16	1	Refrigerator, Reach-In
17	1	Freezer, Reach-In
18	2	Work Table W/Overshelf
19	1	Exhaust Hood System (By HVAC)
20	–	–Spare Number–
21	1	Range W/Griddle/Broiler
22	1	Double Convection Oven
23	1	Salad/Sandwich Prep Refrigerator
24	1	Holding/Proofing Cabinet
25	–	–Spare Number–
26	1	Work Table
27	1	Wall Shelf
28	1	Mixer, Counter
29	1	Slicer, Food
30	–	–Spare Number–
31	1	Prep Table W/Sinks
32	1	Wall Shelf
33	1	Clean Pot/Pan Shelving
34	1	Sink, Scullery, 3 Compartments
35	–	–Spare Number–
36	1	Wall Mount Shelf W/ Potrack
37	1	Dishtable, Straight, Clean
38	1	Warewasher, Door Type, Low Temp
39	1	Dishtable, Straight, Soiled
40	1	Shelf, Sort, Wall Mount Racks
40	–	–Spare Number–

THIS DRAWING IS NOT MEANT TO SUPPLANT ANY REQUIRED ARCHITECTURAL AND/OR ENGINEERING DRAWINGS. THIS DRAWING REFLECTS DATA ABOUT THE FOOD SERVICE EQUIPMENT IN ACCORDANCE WITH INFORMATION WE HAD WHEN THIS DRAWING WAS MADE. PLEASE REFER TO THE PROPER ARCHITECTURAL AND ENGINEERING DRAWINGS FOR ANY BUILDING OR SITE WORK INFORMATION.

PROJECT: JUD HICKEY CENTER
LOCATION: AUGUSTA, GA
OWNER/AGENT:
DETAILS OF: PRELIMINARY EQUIPMENT PLAN

US FOODS
P.O. BOX 869
LEXINGTON, SC 29071
LEXINGTON, SC – CONWAY, SC – CHARLESTON, SC – SAVANNAH, GA, – AUGUSTA, GA

REVISION	
1	D.F.F. 7-2-21
2	D.F.F. 10-29-21

DRAWN BY: DANNY FRICK
APPROVED BY:
DATE: 6-28-21
PROJECT NUMBER 21-JH-001
SCALE: 1/4"=1'-0"

SHEET
1 OF 1

NOTE: KITCHEN EQUIPMENT INCLUDED FOR REFERENCE ONLY.
SEE CUT SHEETS FROM OWNER FOR ADDITIONAL INFORMATION

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C., AND NOT TO BE REPRODUCED OR PUBLISHED IN WHOLE OR IN PART, OR USED FOR OTHER PURPOSES THAN THE PROJECT SPECIFIED, OR FURNISHED INFORMATION BY OTHERS, OR FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS TO BE RETURNED UPON REQUEST.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS			
REV #	DATE	APRVD BY	REVISION
	2/16/22	EA	ISSUE FOR PERMIT

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA012275
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
ENLARGED KITCHEN PLANS

DRAWING NO:
A410

1 INTERIOR STUD WALL
SCALE: 1 1/2" = 1'-0"

FIRE RATING		
S.T.C. RATING		

2 INTERIOR STUD WALL
SCALE: 1 1/2" = 1'-0"

FIRE RATING		
S.T.C. RATING		

3 INTERIOR STUD WALL
SCALE: 1 1/2" = 1'-0"

FIRE RATING		
S.T.C. RATING		

4 INTERIOR STUD WALL
SCALE: 1 1/2" = 1'-0"

FIRE RATING	UL U305	1 HR
S.T.C. RATING		

NOTE: SEE LIFE SAFETY SHEET FOR RATED WALL LOCATIONS. IF NOT INDICATED AS RATED ON LIFE SAFETY SHEET, FIRE RATING IS NOT REQUIRED AT THAT LOCATION.

5 INTERIOR STUD WALL
SCALE: 1 1/2" = 1'-0"

FIRE RATING		
S.T.C. RATING		

6 INTERIOR STUD WALL
SCALE: 1 1/2" = 1'-0"

FIRE RATING	UL U305	1 HR
S.T.C. RATING		

NOTE: SEE LIFE SAFETY SHEET FOR RATED WALL LOCATIONS. IF NOT INDICATED AS RATED ON LIFE SAFETY SHEET, FIRE RATING IS NOT REQUIRED AT THAT LOCATION.

71 INTERIOR STUD WALL
SCALE: 1 1/2" = 1'-0"

FIRE RATING	UL 415	1 HR
S.T.C. RATING		

GENERAL NOTES:

1. AT WALLS WHERE TILE IS USE AS THE FINISH MATERIAL, WATER RESISTANT GYP. BD. SHALL BE USED AS THE BASE LAYER UNLESS OTHERWISE NOTED. ALL WALLS TO RECEIVE CERAMIC TILE SHALL HAVE STUDS SPACED AT A MAXIMUM OF 16" O.C.
2. PROVIDE RATED WALLS ACCORDING TO THE REQUIREMENTS OF THE RESPECTIVE TEST NUMBER INDICATED.
3. APPLY SEALANT TO WALLS TO MEET THE INDICATED STC RATING.
4. WALL HEIGHT INDICATED "TO STRUCTURE" SHALL BE CARRIED TO UNDERSIDE OF FLOOR/ROOF ASSEMBLY AND SEALED AT TOP.
5. WHERE NON RATED WALLS DO NOT EXTEND TO STRUCTURE, EXTEND STUDS TO STRUCTURE AND BRACE WALLS TO DECK ABOVE @ 48" O.C.
6. ALL MECHANICAL ROOM WALLS TO BE 60 STC.
7. INTERIOR FACE OF EXTERIOR WALLS SHALL RECEIVE 5/8" MOLD/MOISTURE RESISTANT GYP. BOARD.
8. COORDINATE WITH REFLECTED CEILING PLAN FOR PARTITIONS SCHEDULED TO EXTEND TO STRUCTURE.

0' 2" 4" 8" 1'-4" 2'-8"
SCALE: 1-1/2" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C., AND WAS DEVELOPED FOR USE ON THIS PROJECT ONLY. ANY REPRODUCTION OF THIS DRAWING OR THE INFORMATION SHOWN ON THIS DRAWING OR FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS PROHIBITED WITHOUT WRITTEN CONSENT.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA012775
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:
WALL TYPES

DRAWING NO:
A601

DOOR TYPES

DOOR FRAMES

FRAME PROFILES

1 - HEAD DETAIL
SCALE: 1 1/2" = 1'-0"

5 - JAMB DETAIL
SCALE: 1 1/2" = 1'-0"

9 - SILL DETAIL -LVT/TILE
SCALE: 1 1/2" = 1'-0"

2 - JAMB DETAIL
SCALE: 1 1/2" = 1'-0"

6 - HEAD DETAIL
SCALE: 1 1/2" = 1'-0"

10 - SILL DETAIL -LVT/RSF
SCALE: 1 1/2" = 1'-0"

3 - SILL DETAIL
SCALE: 1 1/2" = 1'-0"

7 - JAMB DETAIL
SCALE: 1 1/2" = 1'-0"

11 - SILL DETAIL - LVT/PMC
SCALE: 1 1/2" = 1'-0"

4 - HEAD DETAIL
SCALE: 1 1/2" = 1'-0"

12 - HEAD DETAIL
SCALE: 1 1/2" = 1'-0"

DOOR SCHEDULE

DR #	WIDTH	DOOR SIZE (W x H) HEIGHT	PAIR	DOOR TYPE	DOOR MAT.	DOOR FRAME TYPE	DOOR FRAME MAT.	DOOR FRAME PR	GLAZING	DETAILS HEAD	DETAILS JAMB	DETAILS SILL	F.R.	HDWR	REMARKS
PHASE 1															
101	3'-0"	8'-0"	*	D	AL	-	AL	-	IG-2						1,4
101.1	3'-0"	7'-0"	*	D	AL	-	AL	-	G-1						1,4,5,6
104	3'-0"	7'-0"		A	WD	1	HM	a		4	5	9			2
105	3'-0"	7'-0"		A	WD	1	HM	a		4	5	9			2
107	3'-0"	7'-0"		A	WD	1	HM	a		4	5	9			2
108	3'-0"	7'-0"		A	WD	1	HM	a		4	5	9			2
109	3'-0"	7'-0"		A	WD	1	HM	a		4	5	9			4
109.1	3'-0"	7'-0"		A	WD	1	HM	a		4	5	-			
110	3'-0"	7'-0"		A	WD	1	HM	a		4	5	-			
110.1	3'-0"	7'-0"		A	WD	1	HM	e		4 SIM	5 SIM	9			4
111	3'-0"	7'-0"		A	WD	1	HM	a		4	5	-			
112	3'-0"	7'-0"		A	WD	1	HM	a		4	5	-	45 MIN		
115	3'-0"	7'-0"		A	WD	1	HM	e		4	5	-			2, 4
116	3'-0"	7'-0"		A	WD	1	HM	e		4	5	-			
117	3'-0"	7'-0"		A	WD	1	HM	a		4	5	-			
117.1	3'-0"	7'-0"		A	WD	1	HM	a		4	5	-			
118	3'-0"	7'-0"		A	WD	1	HM	a		4	5	9			2
118.1	3'-0"	7'-0"		A	WD	1	HM	a		4	5	9			2
118.2	3'-0"	7'-0"		E	WD	1	HM	b		4	5	-			
118.3	2'-6"	7'-0"		E	WD	1	HM	b		4	5	-			
118.4	2'-6"	7'-0"		E	WD	1	HM	b		4	5	-			
118.5	2'-6"	7'-0"		E	WD	1	HM	b		4	5	-			
119	3'-0"	7'-0"		A	WD	1	HM	a		4	5	9			2
119.1	3'-0"	7'-0"		A	WD	1	HM	a		4	5	9			2
119.2	3'-0"	7'-0"		E	WD	1	HM	b		4	5	-			
119.3	2'-6"	7'-0"		E	WD	1	HM	b		4	5	-			
122	3'-0"	7'-0"		A	WD	1	HM	a		4	5	-			
123	3'-0"	7'-0"	*	A	WD	1	HM	a		4	5	-			4
123.1	3'-0"	7'-0"	*	C	GHM	1	GHM	c	IG-2	1 SIM	2 SIM	3 SIM			4
124	3'-0"	7'-0"	*	A	WD	1	HM	a		4	5	-			
125	3'-0"	7'-0"		A	WD	1	HM	a		4	5	-			
126	5'-0"	7'-0"		-	-	1	HM	d		4 SIM	5 SIM	-			CASED OPENING
126.1	2'-6"	7'-0"		B	HM	1	HM	b		4 SIM	5 SIM	-	-		3
126.2	2'-6"	7'-0"		B	HM	1	HM	b		4 SIM	5 SIM	-	-		3
127	3'-0"	7'-0"	*	C	GHM	1	GHM	c	IG-3	1 SIM	2 SIM	3 SIM			4,5
127.1	3'-0"	7'-0"	*	C	GHM	1	GHM	c	IG-3	1 SIM	2 SIM	3 SIM			4,5
127.2	3'-0"	7'-0"		F	WD	-	WD	-	S				-		SCREEN DOOR
127.3	3'-0"	7'-0"		F	WD	-	WD	-	S				-		SCREEN DOOR
128	3'-0"	7'-0"	*	B	GHM	1	GHM	a		4 SIM	5 SIM	11			3, 4
128.1	3'-0"	7'-0"		B	GHM	1	GHM	e		6	7	-			
128.2	3'-0"	7'-0"	*	C	GHM	1	GHM	e	G-1	4 SIM	5 SIM	11			3, 4
128.3	6'-11"	4'-0"		-	SS	1	GHM	d		12	13	14	-		3, SERIES 651 COUNTER DOOR
129	3'-0"	7'-0"	*	C	GHM	1	GHM	a	G-1	6	7	-			
129.1	3'-0"	7'-0"	*	C	GHM	1	GHM	c	IG-2	1 SIM	2 SIM	3 SIM			4
130	3'-0"	7'-0"		B	GHM	1	GHM	a		6	7	-			
131	3'-0"	7'-0"		B	GHM	1	GHM	e		6	7	-			
132	3'-0"	7'-0"	*	C	HM	1	HM	e	G-1	4 SIM	5 SIM	15			3,4
132.1	8'-0"	7'-0"		-	-	-	-	-	IG-2	1 SIM	2 SIM	3 SIM			GARAGE DOOR
133	3'-0"	7'-0"		A	WD	1	HM	a		4	5	-			
133.1	3'-0"	7'-0"		A	WD	1	HM	a		4	5	-			
134	3'-0"	7'-0"	*	B	HM	1	HM	a		4	5	-			4
135.1	3'-0"	7'-0"		B	GHM	1	GHM	c		1 SIM	2 SIM	3 SIM			
136	3'-0"	7'-0"	*	D	GHM	1	GHM	c	IG-2	1 SIM	2 SIM	3 SIM			1
136.1	3'-0"	7'-0"	*	D	AL	-	AL	-	IG-2						1
136.2	3'-0"	7'-0"	*	D	AL	-	AL	-	IG-2						1
136.3	3'-0"	7'-0"	*	D	AL	-	AL	-	IG-2						1
136.4	3'-0"	7'-0"	*	D	AL	-	AL	-	IG-2						1
136.5	3'-0"	7'-0"	*	D	AL	-	AL	-	IG-2						1
137	3'-0"	7'-0"		A	WD	1	HM	e		4	5	9			2
138	3'-0"	7'-0"		A	WD	1	HM	e		4	5	9			2
139	3'-0"	7'-0"	*	D	GHM	1	GHM	c	IG-2	1 SIM	2 SIM	3 SIM			4
139.1	3'-0"	7'-0"		A	WD	1	HM	e		4	5	-			4
139.2	3'-0"	7'-0"	*	D	WD	1	HM	e	G-1	4	5	-			4, STAIN GRADE
140	3'-0"	7'-0"		C	HM	1	HM	e	G-1	4	5	-			
140.1	3'-0"	7'-0"		A	WD	1	HM	b		4 SIM	5 SIM	-			3
141	3'-0"	7'-0"		A	WD	1	HM	a		4	5	17			2
142	3'-0"	7'-0"		A	WD	1	HM	a		4	5	17			2
143	3'-0"	7'-0"		A	WD	1	HM	e		4	5	-			
144	3'-0"	7'-0"		A	WD	1	HM	e		4	5	-			
145	3'-0"	7'-0"		A	WD	1	HM	a		4	5	16			4
146	3'-0"	7'-0"		A	WD	1	HM	e		4	5	-			
147	3'-0"	7'-0"		A	WD	1	HM	e		4	5	-			
148	3'-0"	7'-0"		A	WD	1	HM	e		4	5	16			
149	3'-0"	7'-0"		A	WD	1	HM	e		4	5	16			
150	3'-0"	7'-0"		A	WD	1	HM	a		4	5	-			
151	3'-0"	7'-0"		A	WD	1	HM	a		4	5	16			
152	3'-0"	7'-0"		A	WD	1	HM	a		4	5	-			
153	3'-0"	7'-0"		A	WD	1	HM	a		4	5	-			
154	3'-0"	7'-0"		A	WD	1	HM	a		4	5	-			
PHASE 2															
113	3'-0"	7'-0"	*	D	WD	1	HM	e	G-1	4	5	10			2, 4, STAIN GRADE
113.1	3'-0"	7'-0"	*	D	WD	1	HM	e	G-1	4	5	10			2, 4, 5 STAIN GRADE
113.2	3'-0"	7'-0"	*	B	GHM	1	GHM	c	-	1 SIM	2 SIM	3 SIM			4

GENERAL DOOR NOTES

1. ALL STAIRWELL DOORS SHALL HAVE TEMPERATURE RISE RATE OF 450 DEG. F.
2. ALL FIRE-RATED DOORS MUST HAVE FIRE-RATED FRAMES, HARDWARE, CLOSURES AND OTHER RATED ACCESSORIES INCLUDING GLAZING.
3. ALL TOILET DOORS TO RECEIVE SOUND SEALS UNLESS NOTED OTHERWISE.
4. ALL GLAZING TO BE TEMPERED OR FIRE-RATED SAFETY GLAZING - NO WIRE GLAZING.
5. FILL ALL MASONRY FRAMES WITH GROUT UNLESS NOTED OTHERWISE.
6. PROVIDE EXTERIOR THRESHOLD AND WEATHER-STRIPPING AT ALL EXTERIOR DOORS.
7. PROVIDE STRUCTURAL STEEL SUPPORT AT ALL LEAD LINED DOOR OPENINGS WHICH ARE 6'-0" OR GREATER.
8. FIRE DOOR ASSEMBLIES IN EXIT ENCLOSURES AND EXIT PASSAGEWAYS SHALL HAVE A MAXIMUM TRANSMITTED TEMPERATURE END POINT OF NOT MORE THAN 450 DEG. F. ABOVE AMBIENT AT THE END OF MINUTES OF STANDARD FIRE TEST EXPOSURE.
9. FIRE-PROTECTION-RATED GLAZING IN EXCESS OF 100 SQUARE INCHES SHALL BE TEST IN ACCORDANCEWITH NFPA 252 AS COMPONENTS OF THE DOOR ASSEMBLIES AND NOT AS GLASS LIGHTS, AND SHALL HAVE A MAXIMUM TRANSMITTED TEMPERATURE RISE OF 450 DEG. F.

DOOR & FRAME MATERIALS

HM	HOLLOW METAL
WD	WOOD
AL	ALUMINUM
GHM	GALVANIZED HOLLOW METAL
SS	STAINLESS STEEL

GLAZING TYPES

IG-1	INSULATED GLASS UNIT
IG-2	INSULATED GLASS UNIT - TEMPERED
IG-3	INSULATED TEMPERED GLASS UNIT - FROSTED
G-1	MONOLITHIC SAFETY GLAZING
G-2	MONOLITHIC GLAZING
S	SCREEN

REMARKS

1. STOREFRONT, SEE WINDOW DETAILS FOR FRAME INFO & H/J/S DETAILS
2. SOUND SEALS
3. TRIM ON ONE SIDE OF DOOR ONLY
4. ACCESS CONTROL/ELECTRIFIED HARDWARE. COORD. W/ ELECT.
5. PRIVACY FILM ON DOOR GLAZING. SEE INTERIORS.
6. PRIVACY FILM ON STOREFRONT SIDELITES.

0' 1' 2' 4' 8' 16'
SCALE: 1/4" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C., AND IS NOT TO BE REPRODUCED IN WHOLE OR IN PART, OR TO BE GIVEN TO OTHERS WITHOUT WRITTEN PERMISSION. THE INFORMATION HEREIN IS TO BE USED ONLY FOR ANY ESTATE PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS SUBJECT TO REVISION AT ANY TIME.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REV #	DATE	APRVD BY	REVISION
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA031075
REGISTERED ARCHITECT
2/10/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
DOOR SCHEDULE, TYPES, & DETAILS

DRAWING NO:
A701

13 / - JAMB DETAIL
SCALE: 1 1/2" = 1'-0"

14 / - SILL DETAIL
SCALE: 1 1/2" = 1'-0"

15 / - SILL DETAIL -LVT/SC
SCALE: 1 1/2" = 1'-0"

16 / - SILL DETAIL - CPT/LVT
SCALE: 1 1/2" = 1'-0"

17 / - SILL DETAIL - CPT/TILE
SCALE: 1 1/2" = 1'-0"

0' 1' 2' 4' 8' 16'
SCALE: 1/4" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C., AND WAS NOT PREPARED FOR ANY OTHER PURPOSE THAN THE PROJECT SHOWN. THE INFORMATION, DRAWINGS OR FOR MANY ESTATE PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS RESERVED AT THE OWNER'S OPTION.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA017277
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:
DOOR DETAILS

DRAWING NO:
A702

1 HEAD DETAIL
SCALE: 1 1/2" = 1'-0"

7 HEAD DETAIL
SCALE: 1 1/2" = 1'-0"

14 HEAD DETAIL
SCALE: 1 1/2" = 1'-0"

2 JAMB DETAIL
SCALE: 1 1/2" = 1'-0"

8 JAMB DETAIL
SCALE: 1 1/2" = 1'-0"

15 SILL DETAIL
SCALE: 1 1/2" = 1'-0"

3 SILL DETAIL
SCALE: 1 1/2" = 1'-0"

9 SILL DETAIL
SCALE: 1 1/2" = 1'-0"

16 HEAD DETAIL
SCALE: 1 1/2" = 1'-0"

4 HEAD DETAIL
SCALE: 1 1/2" = 1'-0"

10 HEAD DETAIL
SCALE: 1 1/2" = 1'-0"

17 JAMB DETAIL
SCALE: 1 1/2" = 1'-0"

5 JAMB DETAIL
SCALE: 1 1/2" = 1'-0"

11 JAMB DETAIL
SCALE: 1 1/2" = 1'-0"

18 SILL DETAIL
SCALE: 1 1/2" = 1'-0"

6 SILL DETAIL
SCALE: 1 1/2" = 1'-0"

12 SILL DETAIL
SCALE: 1 1/2" = 1'-0"

19 SILL DETAIL
SCALE: 1 1/2" = 1'-0"

WINDOW SCHEDULE

NO.	WINDOW SIZE (W X H) WIDTH	HEIGHT	FRAME MAT.	GLASS TH.	TYPE	THERM.	COLOR	OPERATION	DETAILS HEAD	JAMB	SILL	REMARKS
PHASE 1												
A	2'-11 5/8"	5'-0 7/8"	WD/AL	1"	IG-1	LOW-E	CLEAR	DBL HUNG	4	5	6	ANDERSEN E SERIES
B	2'-11 5/8"	4'-4 7/8"	WD/AL	1"	IG-1	LOW-E	CLEAR	DBL HUNG	1	2	3	ANDERSEN E SERIES
B2	2'-11 5/8"	4'-4 7/8"	WD/AL	1"	IG-1	LOW-E	CLEAR	DBL HUNG	1	2	3	ANDERSEN E SERIES
C	3'-6"	4'-0"	HM	1/4"	G-2	-	CLEAR	FIXED	16	17	18	HM BORROWED LITE
D	17'-4"	7'-2"	HM	1/4"	G-1/G-2	-	CLEAR	FIXED	16	17	19	HM BORROWED LITE
E	18'-5"	8'-2"	AL	1"	IG-1/IG-2	LOW-E	CLEAR	FIXED	7	8	9	KAWNEER TRIFAB VG451
F	9'-7"	8'-0"	AL	1/4"	G-1/G-2	-	CLEAR	FIXED	10	11	12	KAWNEER TRIFAB VG451
G	8'-5"	7'-2"	AL	1"	IG-1/IG-2	LOW-E	CLEAR	FIXED	7	8	9	KAWNEER TRIFAB VG451
H	18'-0 3/4"	7'-2"	AL	1"	IG-1/IG-2	LOW-E	CLEAR	FIXED	7	8	9	KAWNEER TRIFAB VG451
J	9'-5 5/8"	7'-2"	AL	1"	IG-1/IG-2	LOW-E	CLEAR	FIXED	7	8	9	KAWNEER TRIFAB VG451
K	14'-8 1/2"	7'-2"	AL	1"	IG-1/IG-2	LOW-E	CLEAR	FIXED	7	8	9	KAWNEER TRIFAB VG451
L	8'-9 7/8"	7'-2"	AL	1"	IG-1/IG-2	LOW-E	CLEAR	FIXED	7	8	9	KAWNEER TRIFAB VG451
M	10'-11"	7'-2"	AL	1"	IG-1/IG-2	LOW-E	CLEAR	FIXED	7	8	9	KAWNEER TRIFAB VG451
N	17'-0"	7'-2"	AL	1"	IG-1/IG-2	LOW-E	CLEAR	FIXED	7	8	9	KAWNEER TRIFAB VG451
P	12'-6"	7'-2"	AL	1"	IG-1/IG-2	LOW-E	CLEAR	FIXED	7	8	9	KAWNEER TRIFAB VG451
Q	4'-10 1/4"	7'-2"	AL	1"	IG-1/IG-2	LOW-E	CLEAR	FIXED	7	8	9	KAWNEER TRIFAB VG451
R	10'-0"	5'-0"	HM	1/4"	G-1/G-2	-	CLEAR	FIXED	16	17	18	HM BORROWED LITE
S	9'-9 13/16"	7'-2"	AL	1/4"	G-1	-	CLEAR	FIXED	10	11	12	KAWNEER TRIFAB VG451
PHASE 2												
T	3'-0"	3'-0"	WD/AL	1"	IG-1	LOW-E	CLEAR	FIXED	4 SIM	5 SIM	6 SIM	ANDERSEN E SERIES
V	11'-0"	3'-0"	AL	1"	IG-1/IG-2	LOW-E	CLEAR	FIXED	7	8	15	KAWNEER TRIFAB VG451

GLAZING TYPES

IG-1 INSULATED GLASS UNIT
IG-2 INSULATED GLASS UNIT - TEMPERED
IG-3 INSULATED TEMPERED GLASS UNIT - FROSTED
G-1 MONOLITHIC SAFETY GLAZING
G-2 MONOLITHIC GLAZING
S SCREEN

ABBREV.:

HM HOLLOW METAL
WD WOOD
AL ALUMINUM

REMARKS:

1. CONTRACTOR TO FIELD VERIFY ALL OPENING DIMENSIONS
2. SEE INT. ELEVATIONS FOR STOREFRONT SAFETY RAIL LOCATIONS.

FRAME TYPES

SCALE: 1/4" = 1'-0"

SCALE: 1-1/2" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND MAY NOT BE REPRODUCED OR PUBLISHED IN WHOLE OR IN PART, OR ANY INFORMATION CONTAINING INFORMATION PROPRIETARY TO DICKINSON ARCHITECTS, P.C. OR FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS SUBJECT TO RESTRICTIONS OF SALE.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:

JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA013237
REGISTERED ARCHITECT
2/10/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:

WINDOW SCHEDULE, TYPES, & DETAILS

DRAWING NO:

A710

MATERIAL DESIGN BASIS

PAINT

PNT-1 WALL PAINT - FIELD
MANUF.: SHERWIN WILLIAMS
COLOR: SW 7006 EXTRA WHITE
TOP COAT: PROMAR 200 ZERO VOC
FINISH: EGGSHELL
LOCATIONS: SEE INT. ELEVATIONS

PNT-2 WALL PAINT - FIELD
MANUF.: SHERWIN WILLIAMS
COLOR: SW 7043 WORLDLY GRAY
TOP COAT: PROMAR 200 ZERO VOC
FINISH: EGGSHELL
LOCATIONS: SEE INT. ELEVATIONS

PNT-3 WALL PAINT - ACCENT
MANUF.: BENJAMIN MOORE
COLOR: HC-154 HALE NAVY
TOP COAT: ULTRA SPEC 500 INTERIOR
FINISH: SATIN
LOCATIONS: SEE INT. ELEVATIONS

PNT-4 WALL PAINT - ACCENT
MANUF.: SHERWIN WILLIAMS
COLOR: SW 6219 RAIN
TOP COAT: PROMAR 200 ZERO VOC
FINISH: SATIN
LOCATION: SEE INT. ELEVATIONS

PNT-5 WALL PAINT - ACCENT
MANUF.: SHERWIN WILLIAMS
COLOR: SW 6219 RAIN
TOP COAT: PROMAR 200 ZERO VOC
FINISH: EGGSHELL
LOCATION: SEE INT. ELEVATIONS

PNT-6 MILLWORK PAINT
MANUF.: SHERWIN WILLIAMS
COLOR: SW 7006 EXTRA WHITE
TOP COAT: PROMAR 200 ZERO VOC
FINISH: SEMI-GLOSS
LOCATION: SEE MILLWORK DETAILS & ELEVATIONS

PNT-7 MILLWORK PAINT
MANUF.: BENJAMIN MOORE
COLOR: HC-145 VAN COURTLAND BLUE
TOP COAT: ULTRA SPEC 500 INTERIOR
FINISH: SEMI-GLOSS
LOCATION: SEE MILLWORK DETAILS & ELEVATIONS

PNT-8 CEILING PAINT
MANUF.: SHERWIN WILLIAMS
COLOR: SW 7006 EXTRA WHITE
TOP COAT: PROMAR 200 ZERO VOC
FINISH: FLAT
LOCATION: CEILINGS ONLY

PNT-9 DOOR FRAME PAINT - TYPICAL
MANUF.: SHERWIN WILLIAMS
COLOR: SW 7006 EXTRA WHITE
FINISH: SEMI-GLOSS
LOCATION: DOOR FRAME
NOTES: ONE COAT ALKYD PRIMER, TWO COATS ALKYD ENAMEL. FACTORY PRIMER IS ACCEPTABLE WITH NO VISUAL RUST.

STAIN

ST-1 MANUF.: -
COLOR: STAIN TO MATCH WILSONART 7992 -38 PINNACLE WALNUT
SHEEN: MATTE
LOCATION: RECEPTION WOOD BEAMS

CARPET

CPT-1 MANUFACTURER: TARKETT
STYLE: TWILL
COLOR: COTTON + IRON
PRODUCT #: 11527 57202
SIZE: 18" X 36"
INSTALL PATTERN: ASHLAR

LUXURY VINYL TILE

LVT-1 MANUFACTURER: COBALT SURFACES
COLLECTION: KATANGA
PRODUCT #: KPS-821
COLOR: DOE
SIZE: 7" x 48"
WEAR LAYER : 20 MIL
THICKNESS: 5MM
FINISH: COBALT GUARD
INSTALLTION METHOD: GLUE DOWN
INSTALL PATTERN: SEE FINISH PLAN
NOTE: TO BE INSTALLED WITH MANUFACTURERS RECOMMENDED ADHESIVE

SEALED CONCRETE

SC-1 MANUF.: -
PRODUCT: SEALED CONCRETE

WOOD BASE

WB-1 MANUFACTURER: GARDEN STATE LUMBER
ITEM #: GSB412
COLOR: PNT-6, UNLESS NOTED OTHERWISE ON INT. ELEV.

WB-2 MANUFACTURER: GARDEN STATE LUMBER
ITEM #: WM618
COLOR: PNT-6, UNLESS NOTED OTHERWISE ON INT. ELEV.

WOOD CROWN

WC-1 MANUFACTURER: GARDEN STATE LUMBER
ITEM #: GSC512
COLOR: SEE INT. ELEV.

RUBBE BASE

RB-1 MANUFACTURER: JOHNSONITE
PROFILE: PERCEPTIONS RECESS TOE
HEIGHT: 4.25"
COLOR: 80 FAWN
NOTES: ROLLED GOODS

POLYURETHANE MODIFIED CEMENT

PMC-1 MANUFACTURER: SHERWIN WILLIAMS
PRODUCT: FASTOP S
COLOR: LIGHT GRAY
TOPCOAT: 3746
NOTES: INTEGRAL 4" FLASH COVE

RUBBER SPORTS FLOOR

RSF-1 *
MANUFACTURER: ECORE
PRODUCT: FOREST RX
COLOR: 9822 TOASTED OAK

RSF-2 *
MANUFACTURER: ECORE
PRODUCT: FOREST RX
COLOR: 2990 OILED OAK

FIBERGLASS REINFORCED PLASTIC (FRP) PANELS

FRP-1 MANUFACTURER: CRANE COMPOSITES
PRODUCTI SEQUENTIA .075"
CLASS C BEADED
COLOR: WHITE
NOTES: APPLY TO 2 WALLS SURROUNDING MOP SINKS

WALL PROTECTION

WP-1 MANUFACTURER: ALTRO
PRODUCT: PURAGUARD
COLOR: WHITE
ITEM #: W139
SIZE: 4' X 9' PANELS
MATERIAL: EXTRUDED SEMI-RIGID PVCu PANEL
THICKNESS: .08"
INSTALLATION: WELDED

VINYL WALLCOVERING

VWC-1

NOT USED

VWC-2 MANUFACTURER: MDC INTERIOR SOLUTIONS
PATTERN: HORIZON LINE
COLOR: CLEAR SKIES
ITEM #: W2HL01/4142
WEIGHT/TYPE: TYPE II 20 OZ. VINYL
BACKING: OSNABURG
WIDTH: 54"
PATTERN MATCH: RANDOM REVERSIBLE
NOTE: TO BE INSTALLED WITH MANUFACTURERS RECOMMENDED ADHESIVE; GLASS INSTALLED ON TOP OF WALLCOVERING

VWC-3

NOT USED

VWC-4 MANUFACTURER: MOMENTUM
PATTERN: ALEGRE
COLOR: DA CAPO
ITEM #: A203-194
WEIGHT/TYPE: TYPE II 20 OZ. VINYL
BACKING: OSNABURG
WIDTH: 54"
PATTERN MATCH: REVERSE HANG, RANDOM MATCH
NOTE: TO BE INSTALLED WITH MANUFACTURERS RECOMMENDED ADHESIVE

VWC-5 MANUFACTURER: MOMENTUM
PATTERN: HERRINGBONE ROW
COLOR: FROST
ITEM #: T2-HR-04
WEIGHT/TYPE: TYPE II 20 OZ. VINYL
BACKING: OSNABURG
WIDTH: 54"
PATTERN MATCH: REVERSE, RANDOM MATCH
NOTE: TO BE INSTALLED WITH MANUFACTURERS RECOMMENDED ADHESIVE

QUARTZ

QTZ-1 MANUFACTURER: WILSONART
COLOR: LORRAINE
ITEM #: Q1012
THICKNESS: 3CM

WOOD COUNTERTOP

WCT-1 MANUFACTURER: -
BUTCHER BLOCK COUNTERTOP
COLOR: STAIN TO MATCH FORMICA 5887-58 MILLENNIUM OAK

PLASTIC LAMINATE

PLAM-1 MANUFACTURER: WILSONART
COLOR: MANGALORE MANGO
ITEM #: 7984-38
FINISH: FINE VELVET FINISH

HAND RAILS

HR-1 MANUFACTURER: INPRO
SERIES: 900 W/ STAINLESS STEEL END CAPS AND BRACKETS
COLOR: 0278 SAND DUNE

CERAMIC TILE

CT-1 WALL TILE
MANUFACTURER: TRINITY TILE
SERIES: DAHLIA
SIZE: 3" X 10"
COLOR: CLOUD
FINISH: GLOSS
GROUT FOR CT-1
MANUFACTURER: MAPEI
PRODUCT: KERAPOXY CQ
COLOR: 93 WARM GRAY
INSTALLATION: VERTICAL RUNNING BOND

PORCELAIN TILE

PT-1 FLOOR TILE
MANUFACTURER: GARDEN STATE TILE
PRODUCT: ARDOSIA
SIZE: 12" X 24"
TEXTURE: MATTE
COLOR: OXFORD WHITE

GROUT FOR PT-1
MANUFACTURER: MAPEI
PRODUCT: KERAPOXY CQ
COLOR: 93 WARM GRAY
INSTALLATION: HORIZONTAL RUNNING BOND

PT-2 FLOOR TILE
MANUFACTURER: GARDEN STATE TILE
PRODUCT: ARDOSIA
SIZE: 2" X 2" MOSAIC
TEXTURE: MATTE
COLOR: OXFORD WHITE

GROUT FOR PT-2
MANUFACTURER: MAPEI
PRODUCT: KERAPOXY CQ
COLOR: 93 WARM GRAY

PB-1 TILE BASE
MANUFACTURER: GARDEN STATE TILE
PRODUCT: ARDOSIA
SIZE: 3" X 24"
TEXTURE: MATTE
COLOR: OXFROD WHITE

GROUT FOR PB-1
MANUFACTURER: MAPEI
PRODUCT: KERAPOXY CQ
COLOR: 93 WARM GRAY

ACOUSTICAL CEILING PANELS

ACP-1 MANUFACTURER: USG
PRODUCT: MARS CLIMAPLUS PERFORMANCE
ITEM NO. : 86185
SIZE: 2' X 2' X3/4"
NRC: .70
COLOR: FLAT WHITE 050
GRID: DONN DX/DXL SUSPENSION SYSTEM
GRID COLOR: FLAT WHITE 050

ACP-2 MANUFACTURER: USG
PRODUCT: SHEETROCK BRAND LAY-IN CEILING
ITEM NO. : 3260
SIZE: 2' X 2' X 1/2"
EDGE: SQUARE
COLOR: FLAT WHITE 050
GRID: DONN DX/DXL SUSPENSION SYSTEM
GRID COLOR: FLAT WHITE 050

ACP-3 MANUFACTURER: MBI PRODUCTS
PRODUCT: CLOUDLITE BAFFLES
SIZE: 2' X 10' X 2'
EDGE: SQUARE
MATERIAL: PVC
COLOR: WHITE
INSTALLATION: INSTALL ON HANGERS W/ GROMMETS IN FLAP, COORD. FINAL LAYOUT WITH MECHANICAL. BOTTOM OF PANELS SHOULD NOT HANG BELOW TRUSSES.

TRANSITION STRIP

TS-1 TRANSITION FROM WALL TO WALL TILE
MANUFACTURER: SCHLUTER
PRODUCT PROFILE: JOLLY
FINISH: SATIN ANODIZED ALUMINUM

TS-2 EDGE TRANSITION FROM TILE TO TILE
MANUFACTURER: SCHLUTER
PRODUCT PROFILE: QUADEC
COLOR: SATIN ANODIZED ALUMINUM

TS-3 TRANSITION FROM LVT TO PT/SC/PMC
MANUFACTURER: SCHLUTER
PRODUCT PROFILE: RENO-U
COLOR: SATIN ANODIZED ALUMINUM

TS-4 TRANSITION FROM LVT TO CPT
MANUFACTURER: TARKETT
PRODUCT: CD-XX
COLOR: 80 FAWN

TS-5 TRANSITION FROM CPT TO PT
MANUFACTURER: SCHLUTER
PRODUCT: RENO-TK
COLOR: SATIN ANODIZED ALUMINUM

CABINETRY HARDWARE

HDW-1 MANUFACTURER: EMTEK
PRODUCT NAME: TRIBECA PULL
SIZE: 4" CENTER
FINISH: POLISHED CHROME
ITEM #: 86429

HDW-2 MANUFACTURER: EMTEK
PRODUCT NAME: BAR PULL
SIZE: 4" CENTER
FINISH: SATIN NICKEL
ITEM #: 86360

HDW-3 MANUFACTURER: EMTEK
PRODUCT NAME: BAR PULL
SIZE: 4" CENTER
FINISH: MATTE BLACK
ITEM #: 86360

HDW-4 MANUFACTURER: REJUVENATION
PRODUCT NAME: ARCHED SHELF BRACKETS
SIZE: 10" CENTER
FINISH: POLISHED NICKEL
ITEM #: C2958
NOTES: RECEPTION ADA COUNTER BRACKETS

SPECIALTY FINISH

SF-1 WALL MURAL @ CORRIDOR
PAINTED MURAL BY LOCAL ARTIST
ARTIST AND DESIGNER TO WORK TOGETHER ON FINAL DESIGN
CONTRACTOR NOTES: PRIME WALL ONLY; ARTWORK PROVIDED BY OWNER

SF-2 WALL MURAL @ PAC
VINYL WALL MURAL OR VINYL GRAPHICS APPLIED TO WALL. ARTIST/DESIGNER TO WORK TOGETHER ON FINAL DESIGN.
CONTRACTOR NOTES: PRIME & PAINT WALL PNT-1; ARTWORK PROVIDED BY OWNER

SF-3 SPECIAL WALL FINISH
PLYWOOD

SF-4 PEGBOARD @ WORKSHOP
MANUF.: DIAMOND LIFE GEAR
PRODUCT: PEGBOARD HB
SIZE: 4' X 8' PANELS
FINISH: PAINTABLE FINISH, PNT-1
NOTES: INSTALL PER MANUFACTURER'S INSTRUCTIONS. PROVIDE BLOCKING AS REQUIRED BY MANUF.

SF-5 SLAT WALL @ MARKETPLACE / HOME HUB
MANUF.: DIAMOND LIFE GEAR
PRODUCT: SLATWALL MX
SIZE: 4' X 8' PANELS
FINISH: WHITE
NOTES: INSTALL PER MANUFACTURER'S INSTRUCTIONS. PROVIDE BLOCKING AS REQUIRED BY MANUF.

SF-6 MIRROR @ FITNESS EQUIPMENT
MANUF.: -
PRODUCT: MIRROR, TEMPERED
HEIGHT: 7 AFF

SF-7 WINDOW FILM
MANUF.: 3M
PRODUCT #: 7100126667
PATTERN: STRAIGHT WASHI
COLOR: WHITE
NOTES: INSTALL ON WINDOWS IN OFFICES 146, 147, 148, 149 AND ON DOORS 101.1, 113.1, 113.2, 127, 127.1, & 134

CURTAINS

CURT-1 PRIVACY CURTAIN
MANUF.: INPRO
PRODUCT: PRIVACY CURTAIN
TRACK: FORMTRAC
FABRIC TYPE: PLATINUM
FABRIC PATTERN: BLISSFUL
FABRIC COLOR: ASTER
MESH: 12"; SNOW

CURT-2 SHOWER CURTAIN
MANUF.: INPRO
PRODUCT: SHOWER CURTAIN
TRACK: NANOTRAC
FABRIC TYPE: SHIELD BY PANAZ
FABRIC PATTERN: ABLOOM
FABRIC COLOR: EUCALYPTUS

CURT-3 ROOM DIVIDER CURTAIN
MANUF.: INPRO
PRODUCT: ROOM DIVIDER
TRACK: ARCHITECTURAL DRAPERY ROD W/ BATON AND CORD DRAW
FABRIC TYPE: DRAPERY FABRIC
FABRIC PATTERN: WHIMSY
FABRIC COLOR: HOP

INTERIOR ABBREVIATIONS

ACP	ACOUSTICAL CEILING PANEL
BR	BRICK
BP	BRICK PAVER
CT	CERAMIC TILE
CB	CERAMIC BASE
CMU	CONCRETE MASONRY UNIT
CPT	CARPET
CPT-W	CARPET WALK OFF
EP	EPOXY
EXP	EXPOSED
FCB	FIBER CEMENT BOARD
GYP	GYPSUM BOARD
GL	GLASS
GT	GLASS TILE
GRT	GROUT
HDW	HARDWARE
LVT	LUXURY VINYL TILE
LMC	LINEAR METAL CEILING
MRGB	MOISTURE RESISTANT GYPSUM BOARD
MB	MILLWORK BASE
MV	MASONRY VENEER
PMC	POLYURETHANE MODIFIED CEMENT
PT	PORCELAIN TILE
PB	PORCELAIN BASE
PLAM	PLASTIC LAMINATE
PC	POURED CONCRETE
PNT	PAINT
RB	RUBBER BASE
RSF	RUBBER SPORTS FLOOR
RUB	RUBBER FLOOR
SC	SEALED CONCRETE
SS	SOLID SURFACE
STS	STAINLESS STEEL
ST	STAIN
SF	SPECIALTY FINISH
TBR	THIN BRICK
TS	TRANSITION STRIP
VWC	VINYL WALL COVERING
WCT	WOOD COUNTERTOP
WSCT	WAINSCOT PANELING
WV	WOOD VENEER
WB	WOOD BASE
WC	WOOD CROWN
VCG	VINYL CORNER GUARDS

NOTES FOR PHASE 2

(*) SIGNIFIES FINISHES USED IN PHASE 2

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND MAY NOT BE REPRODUCED OR PUBLISHED IN ANY WAY WITHOUT WRITTEN PERMISSION. ALL INFORMATION, INCLUDING BUT NOT LIMITED TO THE IDEAS, DESIGNS, PLANS, SPECIFICATIONS, OR OTHER INSTRUMENTS OF SERVICE PROVIDED BY DICKINSON ARCHITECTS, P.C., AND IS RESTRICTED TO THE NAMED PROJECT.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. R24012775
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
INTERIOR FINISH SCHEDULE

DRAWING NO:
A801

1 FINISH FLOOR PLAN
SCALE: 1/8" = 1'-0"

NOTE: ALL FLOORING TRANSITIONS TO BE CENTERED UNDER DOOR IN THE CLOSED POSITION, UNLESS NOTED OTHERWISE.

2 SILL DETAIL - TYP.
SCALE: 1 1/2" = 1'-0"

APPLIANCE SCHEDULE		
-	DESCRIPTION	REMARK
A	UNDERCOUNTER ICE MAKER	FBO/IBC
B	UNDERCOUNTER REFRIGERATOR	FBO/IBC
C	REFRIGERATOR	FBO/IBC
D	DRYER	FBO/IBC
E	WASHER	FBO/IBC

INTERIOR ABBREVIATIONS

ACP	ACOUSTICAL CEILING PANEL
BR	BRICK
BP	BRICK PAVER
CT	CERAMIC TILE
CB	CERAMIC BASE
CMU	CONCRETE MASONRY UNIT
CPT	CARPET
CPT-W	CARPET WALK OFF
EP	EPOXY
EXP	EXPOSED
FCB	FIBER CEMENT BOARD
GYP	GYPSUM BOARD
GL	GLASS
GT	GLASS TILE
GRT	GROUT
HDW	HARDWARE
LVT	LUXURY VINYL TILE
LMC	LINEAR METAL CEILING
MRGB	MOISTURE RESISTANT GYPSUM BOARD
MB	MILLWORK BASE
MV	MASONRY VENEER
PMC	POLYURETHANE MODIFIED CEMENT
PT	PORCELAIN TILE
PB	PORCELAIN BASE
PLAM	PLASTIC LAMINATE
PC	POURED CONCRETE
PNT	PAINT
RB	RUBBER BASE
RSF	RUBBER SPORTS FLOOR
RUB	RUBBER FLOOR
SC	SEALED CONCRETE
SS	SOLID SURFACE
STS	STAINLESS STEEL
ST	STAIN
SF	SPECIALTY FINISH
TBR	THIN BRICK
TS	TRANSITION STRIP
VWC	VINYL WALL COVERING
WCT	WOOD COUNTERTOP
WSCT	WAINSCOT PANELING
WV	WOOD VENEER
WB	WOOD BASE
WC	WOOD CROWN
VCG	VINYL CORNER GUARDS

FINISH SYMBOL LEGEND

LVT-1
PT-1
RSF-1
RSF-2
PMC-1
SC-1
CPT-1

FINISH SYMBOL LEGEND

CEILING FINISH
WALL FINISH
BASE FINISH
FLOOR FINISH

0' 2' 4' 8' 16' 32'
SCALE: 1/8" = 1'-0"

0' 2' 4' 8' 1'-4' 2'-8'
SCALE: 1-1/2" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND IS INTENDED FOR THE SPECIFIC PROJECT AND SITE SHOWN HEREON. THE INFORMATION, INFORMATION, OR DRAWING FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS PROHIBITED WITHOUT THE WRITTEN CONSENT OF DICKINSON ARCHITECTS, P.C.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS			
REV #	DATE	APRVD BY	REVISION
	4/16/21	EA	35% SET
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA012775
REGISTERED ARCHITECT
2/10/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:
FIRST FLOOR FINISH PLAN

DRAWING NO:
A810

1 LOBBY
SCALE: 1/4" = 1'-0"

2 LOBBY
SCALE: 1/4" = 1'-0"

3 LOBBY
SCALE: 1/4" = 1'-0"

4 LOBBY
SCALE: 1/4" = 1'-0"

5 MARKETPLACE
SCALE: 1/4" = 1'-0"

6 MARKETPLACE
SCALE: 1/4" = 1'-0"

7 MARKETPLACE
SCALE: 1/4" = 1'-0"

8 MARKETPLACE
SCALE: 1/4" = 1'-0"

9 VOLUNTEER HUB
SCALE: 1/4" = 1'-0"

10 VOLUNTEER HUB
SCALE: 1/4" = 1'-0"

11 NURSES OFFICE/SENSORY ROOM
SCALE: 1/4" = 1'-0"

12 NURSES OFFICE/SENSORY ROOM
SCALE: 1/4" = 1'-0"

13 NURSES OFFICE/SENSORY ROOM
SCALE: 1/4" = 1'-0"

14 NURSES OFFICE/SENSORY ROOM
SCALE: 1/4" = 1'-0"

15 SALON
SCALE: 1/4" = 1'-0"

16 SALON
SCALE: 1/4" = 1'-0"

17 SALON
SCALE: 1/4" = 1'-0"

18 SALON
SCALE: 1/4" = 1'-0"

19 ART STUDIO
SCALE: 1/4" = 1'-0"

20 ART STUDIO
SCALE: 1/4" = 1'-0"

21 ART STUDIO
SCALE: 1/4" = 1'-0"

22 ART STUDIO
SCALE: 1/4" = 1'-0"

23 HOME HUB
SCALE: 1/4" = 1'-0"

24 HOME HUB
SCALE: 1/4" = 1'-0"

25 HOME HUB
SCALE: 1/4" = 1'-0"

26 HOME HUB
SCALE: 1/4" = 1'-0"

27 COMPUTER LAB
SCALE: 1/4" = 1'-0"

28 CORR. 121.3
SCALE: 1/4" = 1'-0"

29 CORR. 121.3
SCALE: 1/4" = 1'-0"

30 SPA
SCALE: 1/4" = 1'-0"

31 SPA
SCALE: 1/4" = 1'-0"

32 SPA
SCALE: 1/4" = 1'-0"

33 SPA
SCALE: 1/4" = 1'-0"

0' 1' 2' 4' 8' 16'
SCALE: 1/4" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND IS NOT TO BE REPRODUCED OR PUBLISHED IN ANY WAY, EXCEPT AS REQUIRED FOR ISSUING PERMITS. ANY OTHER USE OF THE DRAWING OR THE INFORMATION IS PROHIBITED FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS A VIOLATION OF THE COPYRIGHT LAW.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA012775
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:
INTERIOR ELEVATIONS

DRAWING NO:
A821

1 LAUNDRY
SCALE: 1/4" = 1'-0"

2 LAUNDRY
SCALE: 1/4" = 1'-0"

3 LAUNDRY
SCALE: 1/4" = 1'-0"

4 DINING ROOM
SCALE: 1/4" = 1'-0"

5 DINING ROOM
SCALE: 1/4" = 1'-0"

6 DINING ROOM
SCALE: 1/4" = 1'-0"

7 DINING ROOM
SCALE: 1/4" = 1'-0"

8 WORKSHOP
SCALE: 1/4" = 1'-0"

9 WORKSHOP
SCALE: 1/4" = 1'-0"

10 WORKSHOP
SCALE: 1/4" = 1'-0"

11 WORKSHOP
SCALE: 1/4" = 1'-0"

12 BRAIN HEALTH CENTER
SCALE: 1/4" = 1'-0"

13 BRAIN HEALTH CENTER
SCALE: 1/4" = 1'-0"

14 BRAIN HEALTH CENTER
SCALE: 1/4" = 1'-0"

15 BRAIN HEALTH CENTER
SCALE: 1/4" = 1'-0"

16 SIDE ENTRANCE
SCALE: 1/4" = 1'-0"

17 SIDE ENTRANCE
SCALE: 1/4" = 1'-0"

18 SIDE ENTRANCE
SCALE: 1/4" = 1'-0"

19 SIDE ENTRANCE
SCALE: 1/4" = 1'-0"

20 CORRIDOR 121.2
SCALE: 1/4" = 1'-0"

21 CORRIDOR 121.2
SCALE: 1/4" = 1'-0"

0' 1' 2' 4' 8' 16'
SCALE: 1/4" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND IS INTENDED FOR USE ON THIS PROJECT ONLY. ANY REPRODUCTION OF THIS DRAWING OR THE INFORMATION SHOWN HEREON FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS PROHIBITED WITHOUT WRITTEN CONSENT.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA012372
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
INTERIOR ELEVATIONS

DRAWING NO:
A822

1 PHYSICAL ACTIVITY CENTER (PHASE 2)
SCALE: 1/4" = 1'-0"

2 PHYSICAL ACTIVITY CENTER (PHASE 2)
SCALE: 1/4" = 1'-0"

3 PHYSICAL ACTIVITY CENTER (PHASE 2)
SCALE: 1/4" = 1'-0"

4 PHYSICAL ACTIVITY CENTER (PHASE 2)
SCALE: 1/4" = 1'-0"

5 BREAK ROOM
SCALE: 1/4" = 1'-0"

6 BREAK ROOM
SCALE: 1/4" = 1'-0"

7 BREAK ROOM
SCALE: 1/4" = 1'-0"

8 BREAK ROOM
SCALE: 1/4" = 1'-0"

9 COPY ROOM
SCALE: 1/4" = 1'-0"

10 COPY ROOM
SCALE: 1/4" = 1'-0"

11 COPY ROOM
SCALE: 1/4" = 1'-0"

12 COPY ROOM
SCALE: 1/4" = 1'-0"

13 FILE ROOM
SCALE: 1/4" = 1'-0"

0' 1' 2' 4' 8' 16'
SCALE: 1/4" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C., AND IS NOT TO BE REPRODUCED OR USED FOR ANY OTHER PURPOSE THAN THE PROJECT SPECIFIED HEREIN WITHOUT WRITTEN PERMISSION. ALL ERRORS, OMISSIONS, OR CONFLICTING INFORMATION SHOULD BE REPORTED TO THE ARCHITECT. DO NOT SCALE DRAWINGS OR FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS TRANSFERRED TO THE OWNER FOR USE ON THE PROJECT.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	11/17/21	EA	65% SET
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA013217
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
INTERIOR ELEVATIONS

DRAWING NO:
A823

1 CORR. 109.1
SCALE: 1/4" = 1'-0"

2 CORR 113.2
SCALE: 1/4" = 1'-0"

3 CORR 113.2
SCALE: 1/4" = 1'-0"

4 CORR 126.1
SCALE: 1/4" = 1'-0"

5 CORR. 134
SCALE: 1/4" = 1'-0"

6 CORR. 134
SCALE: 1/4" = 1'-0"

7 OPEN OFFICE
SCALE: 1/4" = 1'-0"

8 OPEN OFFICE
SCALE: 1/4" = 1'-0"

9 OPEN OFFICE
SCALE: 1/4" = 1'-0"

10 OPEN OFFICE
SCALE: 1/4" = 1'-0"

11 OFFICE, TYP.
SCALE: 1/4" = 1'-0"

12 OFFICE, TYP.
SCALE: 1/4" = 1'-0"

13 OFFICE, TYP.
SCALE: 1/4" = 1'-0"

14 OFFICE, TYP.
SCALE: 1/4" = 1'-0"

15 EXECUTIVE DIRECTOR
SCALE: 1/4" = 1'-0"

16 EXECUTIVE DIRECTOR
SCALE: 1/4" = 1'-0"

17 EXECUTIVE DIRECTOR
SCALE: 1/4" = 1'-0"

18 EXECUTIVE DIRECTOR
SCALE: 1/4" = 1'-0"

19 CONFERENCE ROOM
SCALE: 1/4" = 1'-0"

20 CONFERENCE ROOM
SCALE: 1/4" = 1'-0"

21 CONFERENCE ROOM
SCALE: 1/4" = 1'-0"

22 CONFERENCE ROOM
SCALE: 1/4" = 1'-0"

0' 1' 2' 4' 8' 16'
SCALE: 1/4" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C., AND IS NOT TO BE REPRODUCED OR PUBLISHED IN WHOLE OR IN PART, OR USED FOR OTHERWISE UNFORESEEN INFORMATION, BY OTHERS, OR FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS SUBJECT TO SPECIAL AGREEMENT.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA013775
REGISTERED ARCHITECT
2/10/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
INTERIOR ELEVATIONS

DRAWING NO:
A824

1 MILLWORK PLAN
SCALE: 1/8" = 1'-0"

0' 2' 4' 8' 16' 32'
SCALE: 1/8" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C., AND WAS NOT PREPARED FOR ANY PURPOSE OTHER THAN THE PROJECT SHOWN. THE ATTACHED INFORMATION, DRAWINGS, OR FORMS MAY ATTAIN PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS RESERVED BY DICKINSON ARCHITECTS, P.C.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	2/16/22	EA	ISSUE FOR PERMIT
1	9/9/22	EA	OWNER REVISIONS

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA012272
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:
MILLWORK PLAN

DRAWING NO:
A850

1 A850 RECEPTION DESK PLAN
SCALE: 1/2" = 1'-0"

2 - RECEPTION DESK
SCALE: 1/2" = 1'-0"

3 - RECEPTION DESK
SCALE: 1/2" = 1'-0"

4 - RECEPTION DESK
SCALE: 1/2" = 1'-0"

5 - RECEPTION DESK
SCALE: 1/2" = 1'-0"

21 - VOLUNTEER HUB MILLWORK
SCALE: 1/2" = 1'-0"

6 - RECEPTION DESK DETAIL
SCALE: 1" = 1'-0"

7 - RECEPTION DESK DETAIL
SCALE: 1" = 1'-0"

17 - SIDE ENTRANCE PANELING
SCALE: 1/2" = 1'-0"

8 A850 MARKETPLACE MILLWORK PLAN
SCALE: 1/2" = 1'-0"

9 - MARKETPLACE MILLWORK
SCALE: 1/2" = 1'-0"

10 - MARKETPLACE MILLWORK
SCALE: 1/2" = 1'-0"

NOTE: OPPOSITE WALL IS MIRROR IMAGE. COORD. W/ OWNER PROVIDED APPLIANCES PRIOR TO FABRICATION/INSTALLATION.

20 - LAUNDRY MILLWORK
SCALE: 1/2" = 1'-0"

15 - RECEPTION WALL PANELING DETAIL
SCALE: 1" = 1'-0"

16 - PANELING DETAIL @ SIDE ENTRANCE
SCALE: 1" = 1'-0"

11 - MARKETPLACE ISLAND
SCALE: 1/2" = 1'-0"

12 - MARKETPLACE ISLAND
SCALE: 1/2" = 1'-0"

13 - MARKETPLACE ISLAND
SCALE: 1/2" = 1'-0"

14 A821 RECEPTION WALL PANELING
SCALE: 1/2" = 1'-0"

MILLWORK KEY

BC# - BASE CABINET
UC# - UPPER CABINET
TC# - TALL CABINET

MILLWORK NOTES

1. " SEE ELEVATIONS FOR BACKSPLASH HEIGHTS
2. COORDINATE ALL APPLIANCES WITH OWNER PRIOR TO MILLWORK FABRICATION

0' 6" 1' 2' 4' 8'
SCALE: 1/2" = 1'-0"

0' 3" 6" 1' 2' 4'
SCALE: 1" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND IS NOT TO BE REPRODUCED IN WHOLE OR IN PART, OR TO BE GIVEN TO OTHERS WITHOUT WRITTEN PERMISSION. ANY REPRODUCED INFORMATION IS RELEASED ON THE MAY - STATE PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS TO BE RETURNED UPON REQUEST.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS			
REV #	DATE	APRVD BY	REVISION
	2/16/22	EA	ISSUE FOR PERMIT

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA012272
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
MILLWORK DETAILS

DRAWING NO:
A851

1 - NURSES OFFICE MILLWORK
SCALE: 1/2" = 1'-0"

5 - HOME HUB MILLWORK
SCALE: 1/2" = 1'-0"

6 - HOME HUB STORAGE CABINETS / SLAT WALL
SCALE: 1/2" = 1'-0"

2 - ART STUDIO MILLWORK
SCALE: 1/2" = 1'-0"

7 - CORKBOARD DETAIL
SCALE: 1" = 1'-0"

8 - COMPUTER LAB COUNTER
SCALE: 1/2" = 1'-0"

9 - COMPUTER LAB MILLWORK
SCALE: 1/2" = 1'-0"

3 - ART STUDIO MILLWORK
SCALE: 1/2" = 1'-0"

NOTE: COORD. W/ OWNER PROVIDED APPLIANCES PRIOR TO FABRICATION/INSTALLATION.

10 - WORKSHOP MILLWORK
SCALE: 1/2" = 1'-0"

4 - ART STUDIO SHELVING
SCALE: 1/2" = 1'-0"

12 - FLOATING SHELF DETAIL
SCALE: 1 1/2" = 1'-0"

11 - WORKSHOP STORAGE
SCALE: 1/2" = 1'-0"

MILLWORK KEY

BC# - BASE CABINET
UC# - UPPER CABINET
TC# - TALL CABINET

MILLWORK NOTES

1. ** SEE ELEVATIONS FOR BACKSPLASH HEIGHTS
2. COORDINATE ALL APPLIANCES WITH OWNER PRIOR TO MILLWORK FABRICATION

0' 6" 1' 2' 4' 8'
SCALE: 1/2" = 1'-0"

0' 3" 6" 1' 2' 4'
SCALE: 1" = 1'-0"

0' 2" 4" 8" 1'-4" 2'-8"
SCALE: 1-1/2" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND MAY NOT BE REPRODUCED OR DISTRIBUTED IN WHOLE OR IN PART, OR ANY OF THE ENCLOSED INFORMATION, BY ANYONE FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS SUBJECT TO RETURN UPON REQUEST.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS

REV #	DATE	APRVD BY	REVISION
	2/16/22	EA	ISSUE FOR PERMIT

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. R24012775
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME: 1893

DRAWING TITLE:
MILLWORK DETAILS

DRAWING NO:
A852

1 A850 DINING ROOM MILLWORK
SCALE: 1/2" = 1'-0"

2 - DINING ROOM MILLWORK
SCALE: 1/2" = 1'-0"

3 - DINING ROOM MILLWORK
SCALE: 1/2" = 1'-0"

4 - MANTLE DETAIL
SCALE: 1 1/2" = 1'-0"

5 - BACKSPLASH DETAIL @ DINING ROOM WINDOWS
SCALE: 1 1/2" = 1'-0"

12 - BRAIN HEALTH CENTER MILLWORK
SCALE: 1/2" = 1'-0"

** COORDINATE APPLIANCES WITH OWNER BEFORE MILLWORK FABRICATION

13 - BREAK ROOM MILLWORK
SCALE: 1/2" = 1'-0"

6 - COPY ROOM MILLWORK
SCALE: 1/2" = 1'-0"

7 - COPY ROOM MILLWORK
SCALE: 1/2" = 1'-0"

8 - FILE ROOM MILLWORK
SCALE: 1/2" = 1'-0"

9 - HAND WASHING STATION
SCALE: 1/2" = 1'-0"

10 - HAND WASHING STATION @ SIDE ENTRANCE
SCALE: 1/2" = 1'-0"

11 - HAND WASHING STATION @ SALON
SCALE: 1/2" = 1'-0"

MILLWORK KEY

BC# - BASE CABINET
UC# - UPPER CABINET
TC# - TALL CABINET

MILLWORK NOTES

1. ** SEE ELEVATIONS FOR BACKSPLASH HEIGHTS
2. COORDINATE ALL APPLIANCES WITH OWNER PRIOR TO MILLWORK FABRICATION

0' 6" 1' 2' 4' 8'
SCALE: 1/2" = 1'-0"

0' 2" 4" 8" 1'-4" 2'-8"
SCALE: 1-1/2" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C., AND IS NOT TO BE REPRODUCED IN WHOLE OR IN PART, OR USED FOR ANY OTHER PURPOSE THAN THE PURPOSE FOR WHICH IT WAS PROVIDED BY THE OWNER OR FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS SUBMITTED ON THE CONDITION THAT THE
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS			
REV #	DATE	APRVD BY	REVISION
	2/16/22	EA	ISSUE FOR PERMIT

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA013775
REGISTERED ARCHITECT
2/10/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:
MILLWORK DETAILS

DRAWING NO:
A853

1 BC1
SCALE: 1" = 1'-0"

2 BC2
SCALE: 1" = 1'-0"

3 BC3
SCALE: 1" = 1'-0"

4 BC4
SCALE: 1" = 1'-0"

5 BC5
SCALE: 1" = 1'-0"

6 BC6
SCALE: 1" = 1'-0"

7 BC7
SCALE: 1" = 1'-0"

8 BC8
SCALE: 1" = 1'-0"

9 BC9
SCALE: 1" = 1'-0"

10 BC10
SCALE: 1" = 1'-0"

11 BC11
SCALE: 1" = 1'-0"

NOTE: ALL CABINETS OVER 30" TO HAVE QTY (2) ADJUSTABLE SHELVES EACH.

12 UC1
SCALE: 1" = 1'-0"

NOTE: ALL CABINETS OVER 30" TO HAVE QTY (2) ADJUSTABLE SHELVES EACH.

13 UC2
SCALE: 1" = 1'-0"

NOTE: ALL CABINETS OVER 30" TO HAVE QTY (2) ADJUSTABLE SHELVES EACH.

14 UC3
SCALE: 1" = 1'-0"

15 TC1
SCALE: 1" = 1'-0"

16 TC2
SCALE: 1" = 1'-0"

17 FLOATING COUNTER DETAIL
SCALE: 1 1/2" = 1'-0"

MILLWORK NOTES

1. " SEE ELEVATIONS FOR BACKSPLASH HEIGHTS
2. COORDINATE ALL APPLIANCES WITH OWNER PRIOR TO MILLWORK FABRICATION

MILLWORK KEY

BC# - BASE CABINET
UC# - UPPER CABINET
TC# - TALL CABINET

0' 3" 6" 1' 2' 4'
SCALE: 1" = 1'-0"

0' 2" 4" 8" 1'-4" 2'-8"
SCALE: 1-1/2" = 1'-0"

dickinson ARCHITECTS
Architecture|Interior Design|Planning
771 Broad Street Suite 200
Augusta, Georgia 30901
(706) 722-7488
mail@dickinsonarchitects.com
www.dickinsonarchitects.com

Member of the American Institute of Architects

THIS DRAWING IS THE PROPERTY OF DICKINSON ARCHITECTS, P.C. AND IS NOT TO BE REPRODUCED OR PUBLISHED IN WHOLE OR IN PART, OR USED FOR OTHER PURPOSES, WITHOUT WRITTEN PERMISSION. ALL DRAWINGS AND OTHER INSTRUMENTS OF SERVICE ARE THE PROPERTY OF THE ARCHITECT AND MAY NOT BE USED FOR ANY OTHER PURPOSE DETRIMENTAL TO THE INTERESTS OF DICKINSON ARCHITECTS, P.C., AND IS SUBJECT TO RETURN UPON REQUEST.
© DICKINSON ARCHITECTS, P.C.

PROJECT TITLE:
JUD C HICKEY CENTER

REVISIONS			
REV #	DATE	APRVD BY	REVISION
	2/16/22	EA	ISSUE FOR PERMIT

STATE OF GEORGIA
Erin Moseley Armstrong
CERTIFICATE NO. RA013717
REGISTERED ARCHITECT
2/16/22

DA PROJECT NUMBER & NAME:
1893

DRAWING TITLE:
MILLWORK DETAILS

DRAWING NO:
A854