

UNCLASSIFIED\FOR OFFICIAL USE ONLY**Bid Inquiry Contractor Report
All Inquiries**

Project: MOODY PERSONNEL RECOVERY HANGAR/HMU **Review:** Personnel Recovery Hangar -BIDDER INQUIRY (00002)

(sorted by CommentID)

Displaying 260 inquiries.

Id	Discipline	Sheet	Detail	Spec
8664377	Contracting			FAR 52.236-27
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Please confirm the site visit date of 6/30/20 and the due date/time for registration.				
Item c says that visitors were supposed to have provided their information 4 days prior (6/19) to the release of the solicitation (6/23).				
On: Jun 24 2020.				
Government Response. . Amendment 0001 is forthcoming. It is anticipated to change the site visit date to 14-Jul-2020 at 0930hrs with a deadline for providing requested info of 6-July-20. Please follow posted solicitation amendments if there is any discrepancy with a ProjNet response. On: Jun 24 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8667077	Architectural			086045
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Paragraph 2.4.2 incorrectly provides requirements for the translucent panel as follows:				
a. No translucent panel can provide 90% LT - Is the intent 30% LT?				
b. No translucent panel manufacturer has a 12" system. Is the intent between 2.5" and 4"?				
c. Translucent Polycarbonate systems do not require a grid and therefore not needed.				
On: Jun 25 2020.				
Government Response. . a. Yes, the Light transmission shall be 30% b. Assembled panel thickness shall be 2.75" c. Provide framing pattern (grid) as indicated on sheet A-622 On: Jun 26 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8667520	Architectural	IN601	Schedules	
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Several Questions regarding the Interior Finish Legend on IN601:				
1) Legend lists both PNT-1 and PNT-2 as specification 09 67 23.13, however this specification has not been provided. Please clarify the correct specifications for these finishes.				
2) Legend lists ACT-2 as specification 09 51 23, however this specification has not been provided. Please advise.				
3) Legend lists WB-1 as specification 12 21 00, however this specification has not been provided. Please advise.				
On: Jun 25 2020.				
Government Response. . 1. Correct specification section should be 09 67 23.15 Fuel Resistive Resinous Flooring, 3-coat system. 2. Incorrect specification listed for ACT-2. The correct Section is 09 51 00. 3. Spec section will be provided. On: Jun 26 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8667524	Architectural	IN601	Finish schedule	

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

IN 601, Finish Schedule, Room 101 Hanger, Notes PNT-1 extending 10' AFFL on walls. Please clarify the following items:
 1) Will the walls receive the same 3 coat system with slip resistant grit finish?
 2) Confirm the demising wall along 2 line will be unfinished above 10'.

On: Jun 25 2020.

Government Response. . 1. The slip resistant grit will not need to be on the wall.
 2. Remaining demising wall will need to be painted (PNT-3). On: Jun 26 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8674062	Architectural	A-622		086045
----------------	---------------	-------	--	--------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Per Inquiry 8667077, you stated the required panel thickness was 2.75". Panel thickness does not correlate to performance and there is nothing special about a 2.75" thick panel. It is only the thickness of one manufacturer. Performance is the significant issue and not thickness. Per your desire to use the framing as shown on A-622, the system appears to be a storefront glass system. You cannot insert a 2.75" panel into a storefront system. Also, multiwall polycarbonate should never be used in a system designed for glass. The glass system has a bite of 1/2" which is far too shallow for multiwall. The advantage of a multiwall system is that no intermediate framing is required with a tongue and groove panel. Only the head, sill and jamb framing is needed which reduces cost but provides for a high performing glazing system. What is the intent?

On: Jun 30 2020.

Government Response. . Panel thickness is to be between 2.5" and 4" as required to meet the performance requirements. Different manufacturers have different standards. The intent is NOT to have a storefront glass system, the intent is to create a design pattern to break up the large panel area, Thus, even though the intermediate framing may not be required, it is the intent to have the grid pattern in the panels which may be accomplished with a Panel Grid Core. This is a high performance translucent building wall system to be bid as such, not as a storefront framing/glass system. On: Jul 01 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8674390	Mechanical			23 09 00
----------------	------------	--	--	----------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

We would like to know who is prefer HVAC Control Contractor for Moody Air Force Base. Can you please provide who does all of the HVAC Control System for the base so we can get an HVAC control price.

On: Jun 30 2020.

Government Response. . The Moody AFB HVAC controls is Siemens. No specific contractor is intended. What is required is 100% compatibility with the existing Moody Siemens system. A firm by the name of Apogee has current experience on Moody AFB, but any HVAC controls contractor who works with and knows the Siemen system should be sought for pricing On: Jul 01 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8676267	Other			N/A
----------------	-------	--	--	-----

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

REGARDING FAR CLAUSE 52.228-1 BID GUARANTEE - The front end documents do not specify, but is there a form we are required to use for the bid bond, such as Standard Form 24?

On: Jun 30 2020.

Government Response. . The bid bond is the most commonly submitted type and the SF24 is the form used for bid bonds, if that method is used. The SF24 used must be the current version that is not expired. Expiration date is listed at the bottom of the form.

	The bidder chooses what type of bid guarantee it wants to submit with the bid that complies with 52.228-1. On: Jul 01 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8677503	Specifications		00 21 13
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Reference Section 00 21 13 Instruction To Bidders, para 2.c.- W.G. Yates and Sons is a closely held corporation and out financial information is confidential. Could the financial information requested in the referenced paragraph be provided under separate cover?			
On: Jul 01 2020.			
	Government Response. . All bids are submitted electronically and only Contracting personnel will be the recipient of all bid material submitted. Financial statement information is protected from disclosure by the Contracting Officer. Please submit bids per the solicitation requirements. On: Jul 02 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8677504	Specifications		142423
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Reference Division 142423, paras 1.3.2 and 2.6.2- Please confirm that "factory training" referenced in these paragraphs refers to company provided training provided to his licensed installers or maintenance personnel and not another maintenance company or base maintenance personnel.			
On: Jul 01 2020.			
	Government Response. . The factory training refers to elevator company training provided to their installers and maintenance providers. On: Jul 08 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8685257	Equipment	IF101 thru IF102	12 50 00.13
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Spec section 12 50 00.13 states to purchase and install furniture and indicates an FF&E attachment. There is no attachment included with the documents. Sheet IF101C note C. indicates furniture on plan for reference only. Is the FF&E to be included or are these items be furnished & installed by others?			
On: Jul 06 2020.			
	Government Response. . FF&E is by others On: Jul 06 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8689980	Other		Solictiation
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
In the Davis-Bacon Wage Determination, there is not a classification for Asbestos Worker / Heat and Frost Insulator. Please provide this classification so that we may properly bid the work?			
On: Jul 08 2020.			
	Government Response. . Since the wage determination (WD) for Lowndes County does not have an Asbestos Worker / Heat and Frost Insulator listed, bidders can use a national average at \$18.32 per hour, or an average of skills similar (no laborers or operators) on the WD which comes to about \$16.40 per hour and \$3.70 in fringe benefits (total \$20.10 per hour). Another way to estimate the labor cost is to use local union rates for the project location (if available). Do not consider apprentice rates unless the contractor has a bona fide currently registered		

apprenticeship program. When and after the contract is awarded, the awardee MUST submit a SF-1444 with the requested rates so every rate on the certified payroll matches the WD with additions (SF-1444). On: Jul 10 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8690008	Architectural	A-601		
----------------	---------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

The door schedule on A-601 shows doors 109, 109A, 114A, 114E, 114F, 116, 124A, and 124D to be "Door Type BB," However the door sizes are shown to be a single leaf door. The doors located on the floor plans A-101C and A-101D show these doors to be double leaf doors. Please advise.

On: Jul 08 2020.

Government Response. . Doors 109, 109A, 114A, 114E, 114F, 116, 124A and 124D are double leaf doors with each leaf 3'-0" wide for a total door width of 6'-0" On: Jul 14 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8690009	Architectural	A-601		
----------------	---------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

The door schedule on A-601 list a door 109B. This door can not be located on the floor plan. Is this door required for this project? Please advise.

On: Jul 08 2020.

Government Response. . Door 109B is indicated on sheet A-101D between Corr 109 and Corr 109B. This door is also a pair of doors with each leaf at 3'-0" wide for a total door opening width of 6'-0". On: Jul 14 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8690013	Architectural	A-601		
----------------	---------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

The door schedule on A-601 shows stairwell doors 1SC, 1SD, and 2SC to be 60 minute rated wood doors. Is this correct or should they be hollow metal doors? Please advise.

On: Jul 08 2020.

Government Response. . Doors 1SC, 1SD and 2SC should be 60 min rated wood doors as indicated. On: Jul 14 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8690015	Architectural	A-601		
----------------	---------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

The door schedule on A-601 shows door 118D to be "Door Type B," However there is no glass type listed. Please advise what glass type should be assigned at this door.

On: Jul 08 2020.

Government Response. . Door 118D should be a "Door Type A" with no glazing. On: Jul 14 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8690017	Architectural	A-401		
----------------	---------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

On drawing A-401, The accessory tags located on the enlarged plans are not consistent with the accessory schedule located on the same page. Please clarify if these are supposed to match or if there are some items that need to be added to the schedule.

On: Jul 08 2020.

Government Response. . The Toilet Accessory Schedule on sheet A-401 and the accessory tags on the Large Scale Plans do not match and need clarifying. Revised Sheet A-401 to be issued for clarification. On: Jul 14 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8690019	Architectural	A-401		
----------------	---------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

On drawing A-401, toilet accessories A104 and A105 Mirrors and A114 Mop and Broom holders are not labeled or drawn. Please provide locations of these items if they are required.

On: Jul 08 2020.

Government Response. . Accessory A104 occurs in Toilet 122, Accessory A105 occurs in Women 113, Accessory A114 occurs in Jan 132 and Jan 219 On: Jul 14 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8690023	Architectural	A-401		
----------------	---------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

On drawing A-401, A107 (Paper Towel Dispenser) and A110 (Soap Dispensers) are only shown at TLT 122 and the sink just outside of this room. Are other PT Dispensers and Soap Dispensers required at the other restrooms? Please advise.

On: Jul 08 2020.

Government Response. . Paper Towel Dispenser occurs in all 5 toilet spaces. Soap Dispensers occur in all 5 toilet spaces. Revised Sheet A-401 to be issued for additional clarification. On: Jul 14 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8690026	Architectural	A-401		
----------------	---------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

On drawing A-401, There are three separate accessories tagged A12. The items appear to be some sort of combination paper towel dispenser and waste receptacle unit, similar to the items tagged A113. Please clarify that these units are intended to be for correct pricing.

On: Jul 08 2020.

Government Response. . The items listed in the Description column of the Toilet Accessory Schedule are correct items to be used in the project. The accessory tags on the Large Scale Plans are not consistent with the Toilet Accessory Schedule. Revised Sheet A-401 to be issued for clarification On: Jul 14 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8690030	Architectural			10 28 13
----------------	---------------	--	--	----------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Specification section 10 28 13 Toilet Accessories list some additional accessories that are not shown on the plans, I.E. Facial Tissue Dispensers, Towel Pins, Toilet Seat Cover Dispensers. Are these items required for this project. If so please provide locations

On: Jul 08 2020.

	Government Response. . Facial tissue dispensers, Towel Pins and Toilet seat Covers are not required. On: Jul 14 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8690129	General		00 21 13
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Reference 00 21 13 - Instructions to Bidders / NOTICE TO BIDDERS, Part 2.b. concerning bid guarantee. Is the original bid guarantee due at the address provided prior to the proposal due date and time?			
On: Jul 08 2020.			
	Government Response. . Yes, per the paragraph, "An electronic copy of the bid guarantee must be submitted with the electronic bid submission. Also, the original bid guarantee shall be mailed to: U.S. Army Corps of Engineers, Savannah District CECT-SAS-E (Dan Helmig) 100 W. Oglethorpe Ave. Savannah, GA 31401"		
The original bid guarantee must be received by the bid opening date and time. On: Jul 08 2020			
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8690177	General		00 21 13
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Reference 00 21 13 - Instructions to Bidders / NOTICE TO BIDDERS, Part 2.c. concerning financial statement. Part 2.c. states to provide a current financial statement electronically with the proposal. Part 3 in this same section states "The Offeror's bid shall not contain classified data." We would classify the company's financial statement as classified data. Please clarify how this is to be handled. Can financial data be provided at a later date under separate cover if still needed and the offeror is in contention for an award?			
On: Jul 08 2020.			
	Government Response. . For this solicitation, classified data is information that has been classified for national security by the US Government and requires a US Government security clearance to access. Company financial statements are not US Government classified data, even if the company deems them to include sensitive or protective business data. Please see response to Inquiry ID: 8677503 and submit bids per the solicitation requirements. On: Jul 08 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8690548	General		01 50 00
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Reference spec section 01 50 00, Part 3.3.2 and 3.3.3. If temporary electricity, potable water and natural gas will be made available without charge, is metering still required as mentioned in part 3.3.3?			
On: Jul 08 2020.			
	Government Response. . Metering will NOT be required On: Jul 10 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8690561	Commissioning		01 91 00.15
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Reference 01 91 00.15 Part 3.1. Considering this is a fully designed project, is part 3.1 Design Phase applicable?			

On: Jul 08 2020.			
	Government Response. . Paragraph 3.1 is a standard UFGS paragraph, and not applicable to a contractor for this Design-Bid Build project. On: Jul 14 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8691863	Contracting		00 70 00
Comment Classification: Unclassified\\For Official Use Only (U\\FOUO)			
Please confirm that FAR 52.219-4 Notice of Price Evaluation Preference for HUBZone Small Business Concerns is incorporated and applicable to this solicitation.			
On: Jul 08 2020.			
	Government Response. . Confirmed that this clause is present and applicable in the solicitation. On: Jul 08 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8692942	Equipment		14 24 23
Comment Classification: Unclassified\\For Official Use Only (U\\FOUO)			
Does CLASS I Elevator Mechanic Certification by Georgia Department of Insurance suffice requirements detailed in Specs per Section 14 24 23 Paragraph 1.3.1.1 a. b.?			
On: Jul 09 2020.			
	Government Response. . Per endorsement letter from the elevator manufacturer, an elevator technician certified by the Georgia State Office of Insurance and Safety Fire Commissioner with a minimum of three years experience will suffice. On: Jul 14 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8693948	General		Spec Section 00
Comment Classification: Unclassified\\For Official Use Only (U\\FOUO)			
Please provide the Davis Bacon Wage Rates for the project.			
On: Jul 09 2020.			
	Government Response. . The wage determination applicable to this project is listed in the solicitation on page 58 of 844 of file 20B3002vol1.pdf on beta.sam.gov. On: Jul 09 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8693975	Architectural		08 71 00
Comment Classification: Unclassified\\For Official Use Only (U\\FOUO)			
Can the Schlage door hardware be substituted with Assa Abloy door hardware?			
On: Jul 09 2020.			
	Government Response. . Equal substitutions are allowed except for cylinders and cores and keying which must match Base Standard - interchangeable core system manufactured by Best Lock Co. On: Jul 14 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8694156	Civil		General
Comment Classification: Unclassified\\For Official Use Only (U\\FOUO)			

Please provide depth for concrete dumpster pad.				
On: Jul 09 2020.				
Government Response. . The depth of the concrete dumpster pad is 8". On: Jul 14 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8694161	Civil	CG103-104		
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Please specify type of material needed for 15" Header pipe. Sheets CG103 & CG104				
On: Jul 09 2020.				
Government Response. . The type of material needed for 15" header pipe shown on sheets CG101 and CG104 is PVC. On: Jul 14 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8694164	Civil	CU201		
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Please clarify who is responsible for purchase and installation of Fire Tank shown on CU201.				
On: Jul 09 2020.				
Government Response. . The contractor is responsible for purchase and installation of Fire Tank shown on CU201. On: Jul 16 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8694167	Civil	CU201		
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Please clarify who is responsible for all piping connecting the pumphouse to the Fire Water Tank shown on sheet CU201.				
On: Jul 09 2020.				
Government Response. . The Contractor is responsible for all piping connecting the pumphouse to the Fire Water Tank shown on sheet CU201. On: Jul 14 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8694171	Plumbing	P502	Detail 1	
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Please provide pipe size and type for "Tank Overflow to Storm" Sheet P502 Detail 1 (Rainwater Cistern Tank Detail).				
On: Jul 09 2020.				
Government Response. . Provide same size and material of incoming downspout. Provide downspout boot at connection to underground overflow piping. On: Jul 14 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8694205	Contracting			RFI Submission Date
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
On Page 8 of 53 of the RFP, it states that technical inquiries and questions are due 10 days prior to bid date. Amendment 1 moved the proposal due date to 8/6 due to a delayed site visit.				

ProjNet, however, still indicates the system will be open from Jun 23 2020 - Jul 13 2020, which is before the organized site visit on July 14.

Please confirm that questions will be accepted until 10 days prior to bid submission to allow for questions that arise from the site visit.

On: Jul 09 2020.

Government Response. . Confirmed that questions are accepted until 10 days prior to bid opening date per the solicitation instructions. On: Jul 09 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8697544	Civil			General
----------------	-------	--	--	---------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Please specify height of Chain link Security Fence.

On: Jul 10 2020.

Government Response. . Fence fabric should be 6' height per specs. section 32 31 13.53 2.1.1 On: Jul 16 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8697546	Civil	CG103		
----------------	-------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Per sheet CG103. Please provide detail showing Concrete Lined Swale.

On: Jul 10 2020.

Government Response. . Refer to GDOT Detail D-10, use 1' Depth. On: Jul 16 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8697548	Fire Protection/Life Safety	FX520		
----------------	-----------------------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Sheet FX520 Detail 5 shows concrete encasement. Is this only referring to the pipe penetration through the concrete slab for the tank? Please clarify?

On: Jul 10 2020.

Government Response. . Per General Note 2 on sheet FX320, all buried piping between the tank and the pump building shall be concrete encased. On: Jul 16 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8697552	Civil	CG104 / 201		
----------------	-------	-------------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Sheet CG104 list Rainwater Tank Overflow as 15" PVC. Sheet CG201 list it as 10" PVC. Please Clarify.

On: Jul 10 2020.

Government Response. . Use 15" PVC Throughout On: Jul 16 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8697553	Civil			General
Comment Classification: Unclassified\For Official Use Only (U\FOUO) Please specify thickness of concrete pad for Rainwater Tank. On: Jul 10 2020.				
Government Response. . Refer to Typical Exterior Equipment Pad Detail 7/S-501 on Sheet S-501 On: Jul 16 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8697554	Civil	C301		
Comment Classification: Unclassified\For Official Use Only (U\FOUO) Sheet C-301 Detail 5. Which apron is this referring to? On: Jul 10 2020.				
Government Response. . Please disregard this detail On: Jul 16 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8697556	Utilities Engineering			General
Comment Classification: Unclassified\For Official Use Only (U\FOUO) Is contractor responsible for installation of 3" Natural Gas installation and Meter? On: Jul 10 2020.				
Government Response. . Contractor is responsible for all natural gas piping and equipment downstream of the gas meter as shown on detail. On: Jul 16 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8697557	Civil			General
Comment Classification: Unclassified\For Official Use Only (U\FOUO) Please provide detail for sidewalk. On: Jul 10 2020.				
Government Response. . Refer to GDOT Detail A3. On: Jul 16 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8697558	Civil			General
Comment Classification: Unclassified\For Official Use Only (U\FOUO) Please provide detail of paving design for "Concrete Addition to Loading Dock". On: Jul 10 2020.				
Government Response. . Refer to detail 13 / C501. Concrete thickness is 8". On: Jul 16 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8697561	Civil			CS502

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**
 Sheet CS502. Is the 2' concrete mow strip required on both sides of the security fence?
 On: Jul 10 2020.

Government Response. . Mow strip is required on one or both sides where turf is present. On: Jul 16 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8697563	Civil			General
----------------	-------	--	--	---------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**
 Please provide Heavy Duty Paving Detail.
 On: Jul 10 2020.

Government Response. . Heavy duty pavement detail will be added to dwg. CS503 in Amendment 02 forthcoming. On: Jul 16 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8697564	Civil			General
----------------	-------	--	--	---------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**
 Is Temp. Fencing required along the entire limits of construction or only where shown on plans?
 On: Jul 10 2020.

Government Response. . Place temporary fencing where shown . on the drawings. On: Jul 16 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8702291	Mechanical	MH102D	Note C	
----------------	------------	--------	--------	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**
 Sheet MH102D note C states "Exposed duct shall be double wall, finish selected by Architect" Does this include the exposed low pressure duct that is in the conditioned space? If it does, can this duct be converted to spiral with the grilles mounted in the spiral duct. That would give the system a better look than trying to make small rectangular duct double wall.
 On: Jul 14 2020.

Government Response. . Yes this applies to all exposed duct. Yes the low pressure rectangular duct can be converted to spiral duct. On: Jul 21 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8702293	Architectural	M401, A201-202		
----------------	---------------	----------------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**
 Sheet M-401, Keynote 23.022 and 23 says to refer to Architectural for louver details.
 Sheet A-201 & 202 shown the louvers with sizes and louver designation (L1 or L2), cannot find a louver schedule.
 The louvers appear to be in the Architectural scope and not in the mechanical scope. Can the government provide a mechanical louver schedule for the contractor to price?
 On: Jul 14 2020.

Government Response. . Please see sheet A-622 for the Louver Schedule On: Jul 16 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8702303	Civil	CU201		
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>There are notes saying "By Others", pointing to the Building 677 Pumphouse and the Fire Tank. Are these 2 structures part of this RFP?</p> <p>On: Jul 14 2020.</p>				
	<p>Government Response. . Refer to the architectural and fire protection plans for additional information. On: Jul 16 2020</p>			
	<p>Current Request Status: Request Closed</p>			
<p>Information for this report is procurement sensitive.</p>				
8702308	Security	TY Drawings		
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Would you please tell us what security equipment/products are currently in use on the base? Since this appears to be a new construction Hangar, we assume that it would need to match existing camera and access control systems of the base or buildings around it. If not, is this an open spec?</p> <p>On: Jul 14 2020.</p>				
	<p>Government Response. . See Specification 28 10 05 para 2.5 that requires ONVIF conformance. Will clarify Sheet T-001 Symbols Legend. On: Jul 21 2020</p>			
	<p>Current Request Status: Request Closed</p>			
<p>Information for this report is procurement sensitive.</p>				
8702309	Security	TY Drawings		
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Video Surveillance Cameras --The camera icons on the drawings do not show any association with the camera details. Please confirm what type of cameras are required.</p> <p>On: Jul 14 2020.</p>				
	<p>Government Response. . Cameras that can be mounted in ACT-type ceiling should be mounted as detailed, and cameras that must be wall mounted should be as detailed. On: Jul 21 2020</p>			
	<p>Current Request Status: Request Closed</p>			
<p>Information for this report is procurement sensitive.</p>				
8702310	Security	TY Drawings		
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Intrusion Detection System: The security (intrusion, cameras, access) are all under the same Spec section. We noticed the intrusion is Vindicator. Is this hard spec'd or will another Intrusion system be acceptable?</p> <p>On: Jul 14 2020.</p>				
	<p>Government Response. . See Specification 28 10 05 Para. 2.1 On: Jul 21 2020</p>			
	<p>Current Request Status: Request Closed</p>			
<p>Information for this report is procurement sensitive.</p>				
8702888	Architectural	IF-101C		
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Are all lockers and entrance mats provided under the FFE package or will they be the responsibility of the contractor?</p> <p>On: Jul 14 2020.</p>				
	<p>Government Response. . Lockers & locker benches to be provided by contractor. EFM-1, RG-1 and RG-2 to be by contractor. On: Jul 16 2020</p>			

Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8702898	Architectural			Fire Extinguishers
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>There's no specification for fire extinguishers nor are they located on the plans. Please advise if the contractor is to provide or if they are provided by the owner.</p> <p>On: Jul 14 2020.</p>				
<p>Government Response. . No portable contractor-provided fire extinguishers are required as this is an alarmed/sprinkled building, and the hangar bay will have user-furnished portable equipment as required On: Jul 22 2020</p>				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8702904	Communications	T-602 - Detail 3		
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Drawing Sheet T-602/Detail 3 – indicates Cat6 U/FTP cable to be installed from the Comm room patch panels to the workstations outlet locations. However, Specification 271000 Building Telecommunications Cabling System indicates Category 6 UTP cable. Please confirm the cable type required. Category 6 U/FTP or Category 6 UTP?</p> <p>On: Jul 14 2020.</p>				
<p>Government Response. . Category 6 UTP is required. See Sheet T-602/Detail 3 and 4 for clarification. On: Jul 22 2020</p>				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8702906	Communications	T-Drawings		
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>T-Series drawings – Some drawings indicate "Provide and install 12-strand Singlemode". However, drawing sheet T-201 0 details indicate that the fiber optic enclosures are NIC (not in contract). Is the outside plant and inside plant fiber optic cable to be included in our pricing and scope of work?</p> <p>On: Jul 14 2020.</p>				
<p>Government Response. . Outside plant and inside plant cabling is to be included in the bid. See T-series drawings for additional information. See specifications divisions 27, 28, and 33 for additional information. Sheet T-201 will be revised to remove NIC from elevations for the fiber patch panel. Security fiber patch panel is required to be provided by Contractor. Coversheet Security Legend and Security riser diagram will be revised for clarity to indicate cabling and conduit for CCTV cameras is required to be provided by Contractor in next amendment. On: Jul 23 2020</p>				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8702907	Communications	T Drawings & TY Drawings		
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>T-Series and TY-Series drawings – Legend T-001 indicates outlet for CCTV camera location. However, the description is for 1" conduit and pull string only. Is cabling for the CCTV cameras to be included in our pricing and scope? If so, please provide the requirements for CCTV camera cable type. Also, is the communications contractor or security contractor responsible for furnishing and installing the CCTV camera cabling?</p> <p>On: Jul 14 2020.</p>				
<p>Government Response. . Specifications speak to cabling to be provided for CCTV camera. Symbols Legend will</p>				

	be clarified in forthcoming amendment On: Jul 22 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8702910	Communications	T-201 & T-401	
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Are racks or cabinets required the in the comm rooms? If cabinets are required, please provide the size dimensions.			
On: Jul 14 2020.			
	Government Response. . Cabinets are required. See specification 27 10 00 Para. 2.4.2. On: Jul 22 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8702913	Communications	T-201 & T-401	
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Is the communications contractor or the security contractor responsible for furnishing and installing the security racks/cabinets?			
On: Jul 14 2020.			
	Government Response. . The successful bidder of Div 27 owes equipment cabinets for communications system. The successful bidder of Div 28 owes equipment cabinets for security system. Coordination between Div 27 and Div 28 is required by Specification 28 10 05 Para. 2.13. On: Jul 22 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8703031	Communications	T-601	2
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Plate T-601 shows new manhole CM17. TS102 shows it as existing. Is manhole CM17 new or existing?			
On: Jul 14 2020.			
	Government Response. . CM17 manhole is new as per sheet T-601. On: Jul 23 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8703037	Electrical	ESD101	
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
There is an existing 30' CCTV pole around 65' Southeast of the existing highmast pole P05, installed on a precast base. It is fed from the 120V panel being relocated with the P05 rack. Does this pole need to be relocated and a new base provided/installed? Does the relocated CCTV pole need the 120V ckt reconnected to it? Is a quazite box required to serve a pull point for the branch ckt?			
On: Jul 14 2020.			
	Government Response. . As best we can tell, this inquiry appears to be un-related to this solicitation. We can't find anything on the drawings noting this CCTV pole. If you can clarify this further, please enter a new inquiry On: Jul 16 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8703040	Electrical	ES101 & ES102	
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Confirm that the lateral feeds for teh padmount should not be #2 15kV EPR with #2 ground. Drawings show #2/0.			

On: Jul 14 2020.

Government Response. . Provide service laterals feeds for the padmounts phase(hots), neutral and grounds as #2/0 15KV EPR. On: Jul 16 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8703055	Architectural	IN601	Interior Finish Legend	09 67 23.15
----------------	---------------	-------	------------------------	-------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Spec Section 09 67 23.15, Paragraph 2.2 specifies the flooring to have a thickness ranging from 13 to 20 mils. The Interior Finish Legend, PNT-1: Resinous Flooring states for the resinous flooring to be Stonhard GS: Stonkote GS4; Stonseal GS6 System. The system specified in the specifications is at a bare minimum 1/8" thick and for hangars it is recommended to be 3/16"-1/4" thick. Please specify which system is to be followed: the specification performance requirement or the basis of design on the drawings.

On: Jul 14 2020.

Government Response. . Follow the basis of design on the drawings for the correct mil layers based on the Stonhard GS finishes. On: Jul 16 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8703099	Architectural			01 91 00.15
----------------	---------------	--	--	-------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Spec Section 01 91 00.15: Appendix B - Basis of Design and Appendix C - Design Phase Commissioning Plan are blank past the page headers. Please specify if there will be documents added by amendment or if these pages are to remain blank.

On: Jul 14 2020.

Government Response. . The Basis of Design and FIO Design Phase Commissioning Plan will not be provided in this section. Section 01 91 00.15 10 will be revised in future amendment so that these attachments will not be indicated. On: Jul 22 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8703135	Architectural			DD Form 1423 (page 120 of 844)
----------------	---------------	--	--	--------------------------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

On page 120 of 844, there is a back page of DD Form 1423, which is instructions to complete the form, but no front page and it is not listed in the attachments to Section 00 73 00. Please provide the front page of DD Form 1423.

On: Jul 14 2020.

Government Response. . This will be corrected in Amendment #3 On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8703150	Architectural			01 00 00
----------------	---------------	--	--	----------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Section 01 00 00, Item 11. Please provide the Davis Bacon Wage Rate for plumbers, as it is not listed.

On: Jul 14 2020.

Government Response. . The bidder must estimate the plumber rate(s) based on industry standard and/or the

	prevailing wages in the area. Perhaps a local plumbers union for journeyman wage rates for an accurate bid estimate. On: Jul 17 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8704899	Civil		Reference Drawings - RA-1
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Are the Benson tanks still in building 655 and are they empty and clean?			
On: Jul 15 2020.			
	Government Response. . Bldg 655 is completely empty On: Jul 16 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8704907	Civil		Reference Drawings - RC-1
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Do you have drawings, showing dimensions, on the two tanks outside and are they clean?			
On: Jul 15 2020.			
	Government Response. . Available drawings of the tanks and pumphouse will be added by forthcoming amendment as a For Information Only supplemental file On: Jul 23 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8704910	Civil		Reference Drawings - RC-1
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Is there an asbestos and lead report for the buildings to be demolished?			
On: Jul 15 2020.			
	Government Response. . A report was accomplished and no lead paint or asbestos was identified requiring abatement On: Jul 24 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8704914	Civil		Reference Drawings - RC-1
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Are there any HVAC units in the two buildings being demolished and if so will the Freon removal be by the contractor or the by the base?			
On: Jul 15 2020.			
	Government Response. . There are no HVAC units at either building On: Jul 16 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8704916	Civil		Reference Drawings - RC-1
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Will all salvage belong to the demolition contractor?			
On: Jul 15 2020.			
	Government Response. . yes, all salvage will belong to the contractor On: Jul 23 2020		
	Current Request Status: Request Closed		

Information for this report is procurement sensitive.

8704918	Civil			RFP
----------------	-------	--	--	-----

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**
 When is the anticipated start date for this project?
 On: Jul 15 2020.

Government Response. . No precise date is available. Assuming the bids received on 6-Aug result in an awardable project, the contract award could be on/about 30-Aug. Notice to Proceed would then be coordinated upon receipt and approval of contractor performance and payment bonds On: Jul 16 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8704936	Electrical	E-516, E-517, E-702		
----------------	------------	---------------------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**
 Would you please provide a specification for the pole for type "J" fixture? Sheet E-516, E-517 and E-702 has no information for the pole.
 On: Jul 15 2020.

Government Response. . Refer to specification 26 56 00 for pole requirements. Mounting height of the lighting fixture is 15ft. On: Jul 22 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8705503	Sustainability			Division 07
----------------	----------------	--	--	-------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**
 Is air barrier testing required for this project?
 On: Jul 15 2020.

Government Response. . Air barrier testing is not required to meet LEED v2009, however the air barrier system will require visual inspection and sign-off to comply with UFC requirements. Note: due to the large doors and overhead coiling doors an air pressure test is not possible. On: Jul 22 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8705738	General	Reference 00 21 13	Instructions to Bidders	Part 2(c)
----------------	---------	--------------------	-------------------------	-----------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**
 Reference 00 21 13 - Instructions to Bidders / NOTICE TO BIDDERS, Part 2(c) where it states "Current Financial Statement (e.g. the last three years financial statement, Annual Reports, Dun and Bradstreet ratings and/or number, etc.) Provide a list of all current contracts held, total dollar value, award date, anticipated completion, performance and payment bond amount." If the offeror is a Joint Venture (JV), how should this requirement be applied? Do you only want the requested information for the JV, or from each individual firm that make up the JV?
 On: Jul 15 2020.

Government Response. . If the JV has been in existence for 3 or more years, provide financial statements for the JV. If JV has not been in existence for 3 years, provide financial statements for both entities that comprise the JV along with any financial statements for the years that the JV has been in existence. On: Jul 16 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8705767	Architectural			Metal Wall Panels
----------------	---------------	--	--	-------------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Please provide a specification for Metal Wall Panels.

On: Jul 15 2020.

Government Response. . See specification section 13 34 19 METAL BUILDING SYSTEMS for Metal Panels On: Jul 22 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8705768	Electrical	CD101		
----------------	------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

The existing water tanks have Cathodic protection on them. The new drawings do not reference reinstalling this system once they have been relocated. Please verify this requirement.

On: Jul 15 2020.

Government Response. . No new cathodic protection is not required. The existing water tanks will not be relocated. See fire protection drawings for new fire water tank & system. On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8705772	Electrical	EP101A and EP101B		
----------------	------------	-------------------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

The drawings reference 400HZ frequency converters 1,2,3 and 4 but we have not seen Cat # for the preferred unit or Cat # for the appropriate receptacle. Please provide this information if available.

On: Jul 15 2020.

Government Response. . To be coordinated with building user post-award. Budget for typical On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8706953	Structural	S-001	Special Inspections - Note 2	01 45 35 - Special Inspections
----------------	------------	-------	------------------------------	--------------------------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Note 2 states, "OWNER, OR ARCHITECT/STRUCTURAL ENGINEER OF RECORD ACTING AS THE OWNER'S AGENT, SHALL DIRECTLY EMPLOY AND PAY FOR SERVICES OF THE SPECIAL INSPECTORS TO PERFORM REQUIRED SPECIAL INSPECTIONS."

Please confirm that the contractor is NOT required to provide Special Inspection services for any scope of work on this project.

On: Jul 16 2020.

Government Response. . Contractor is responsible for providing special inspection services as called for on designated features for this project. On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8707080	Civil	C-301		32 13 14.13
----------------	-------	-------	--	-------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Please provide Spec Section 32 13 14.13 for Airfield PCC Pavement or confirm if 32 12 15.13 applicable. Drawing details on Vol #1 - Sheet C-301 reference PCC Pavement to 32 13 14.13, not provided within Specifications.

On: Jul 16 2020.

Government Response. . Specification Section 32 13 15.13 will be provided for Airfield PCC Pavement as part of

	next amendment #3 On: Jul 23 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8707089	Contracting	SOW	01 00 00
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
<p>Please confirm Small Business Plan for this project. The stated targets add up to 53.5% exceeding the 50% overall. Small Business – 50%</p> <p>Small Disadvantaged Business – 17%</p> <p>Women Owned Small Business – 18%</p> <p>HUBZone Small Business – 10%</p> <p>Veteran-Owned Small Business – 8.5%</p> <p>Service-Disabled Veteran-Owned Small Business – 4%</p> <p>On: Jul 16 2020.</p>			
<p>Government Response. . Per Section 00 21 13 Notice to Bidders under item 2 (on page 6 of 53), the apparent low bidder (if not a small business), upon request by the Contracting Officer after the bid opening but before award, shall submit a subcontracting plan pursuant to 52.219-9 Alt I.</p> <p>Many small businesses are categorized under multiple socioeconomic categories instead of only one category. Therefore, the socioeconomic category targets do not add up to the same target percentage as the Small Business target. On: Jul 16 2020</p>			
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8707095	Architectural	IN401, IN501, IN502	06 20 00
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
<p>Please reference sheets IN401, IN501, IN502 and specification section 06 20 00.</p> <p>Regarding the construction of the cabinets, the documents appear to require 'face frames'. These are very expensive and highly uncommon for commercial use. 'Full overlay' is the more common construction. Please advise which type of cabinets should be priced.</p> <p>Regarding finishes, the drawings call for interiors (aka semi-exposed surfaces) stained to match the exterior of the cabinets. This is very expensive and highly uncommon. White melamine with a particle board core is most common. However, a more common 'high end' approach is to use wood veneer on a plywood core with a clear natural finish. Please advise which material should be priced for the cabinet interiors.</p> <p>On: Jul 16 2020.</p>			
<p>Government Response. . Bid as shown On: Jul 23 2020</p>			
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8707142	Communications		27 & 28
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
<p>Will the CCTV/IDS/ACS systems for Personnel Recovery 4-Bay Hanger/HMU tie into an existing system or will this be stand-alone design build system?</p> <p>If the CCTV/IDS/ACS system for Personnel Recovery 4-Bay Hanger/HMU tie into existing system can we get existing manufacture of the theses systems and what building on site will we need to tie into?</p> <p>On: Jul 16 2020.</p>			

	Government Response. . The security system for HMU will tie into the existing facility systems. The Installation's contractor for these systems is Advantor On: Jul 23 2020			
	Current Request Status: Request Closed			
Information for this report is procurement sensitive.				
8707718	Architectural	A-201 & 202 M-401		
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Sheet M-401, Keynote 23.022 and 23 says to refer to Architectural for louver details.				
Sheet A-201 & 202 shown the louvers with sizes and louver designation (L1 or L2), cannot find a louver schedule.				
The louvers appear to be in the Architectural scope and not in the mechanical scope. Are we to quote these as an alternate?				
On: Jul 16 2020.				
	Government Response. . Exterior Louvers are covered in the architecture scope and mechanical connects to them. Louver schedule is on sheet A-622. Louver are in the main bid and not an alternate. On: Jul 22 2020			
	Current Request Status: Request Closed			
Information for this report is procurement sensitive.				
8708597	Architectural	A-100 series, A-201, A-202, A-622, M-100		
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Reference Drawings A-100 series, A-201, A-202, A-622, M-100 series				
Architectural drawings call out louvers as note 8.02. Mechanical drawings call out exhaust and OA louvers as notes 23.022 and 23.023 respectively and refers to architectural drawings for details. Please confirm the following:				
a. Louvers per note 8.02 and louvers per notes 23.022/23.023 are not the same louvers.				
b. Drawing A-622 louver schedule only applies to architectural louvers shown on A-100 series, A-201 and A-202. Please provide schedule for mechanical louvers referenced by notes 23.022 and 23.023 on M-100 series drawings.				
On: Jul 16 2020.				
	Government Response. . Mechanical refers to architectural for the louvers. Louvers are in the architectural scope and mechanical connects to them. The louver schedule on sheet A-622 covers all the exterior louvers that are required for mechanical to connect to. On: Jul 22 2020			
	Current Request Status: Request Closed			
Information for this report is procurement sensitive.				
8708999	Architectural	C-205		10 14 53; 2.1
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Spec section 10 14 53, Paragraph 2.1 lists 5 different types of sign post. There is only one type of traffic sign shown on C-205. Which type of post is required?				
On: Jul 16 2020.				
	Government Response. . The Restricted Area Boundary Warning Signs are painted on the pavement and not a traffic sign mounted on a sign post. See Detail 3 on Sheet C-200 On: Jul 23 2020			
	Current Request Status: Request Closed			
Information for this report is procurement sensitive.				

8709007	Architectural			10 14 53; Paragraphs 2.6 and 2.7
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Spec section 10 14 53, Paragraphs 2.6 and 2.7 list delineators Please specify the location of the delineators.</p> <p>On: Jul 16 2020.</p>				
<p>Government Response. . There are no delineators on the project. On: Jul 23 2020</p>				
<p>Current Request Status: Request Closed</p>				
<p>Information for this report is procurement sensitive.</p>				
8709064	Architectural	IN-601 Note D		
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>IN-601 Note D calls for window blinds on "all office exterior windows". Please confirm this applies to windows looking into the hangar area, such as Corridor 202, Ready Briefing Rm 108, CTK Work Area 114 as well as rooms not labeled "office", such as Break Rm 121, GHMRE 201, HMU OIC & NCOIC 210 and HMU Super 209.</p> <p>On: Jul 16 2020.</p>				
<p>Government Response. . Window blinds to be placed in following rooms: 209, 210, 212, 213, 220, 221, 222, 201. On: Jul 22 2020</p>				
<p>Current Request Status: Request Closed</p>				
<p>Information for this report is procurement sensitive.</p>				
8709081	Architectural			12 50 00.13; Paragraph 2.2
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Please provide the FF&E Package Attachment as noted in Paragraph 2.2.</p> <p>On: Jul 16 2020.</p>				
<p>Government Response. . FF&E is not part of the bid for this project On: Jul 23 2020</p>				
<p>Government Response. . FF&E is not part of the bid for this project On: Jul 23 2020</p>				
<p>Current Request Status: Request Closed</p>				
<p>Information for this report is procurement sensitive.</p>				
8710770	Architectural			06 61 16
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Please provide section and detail sheets for the following:</p> <ul style="list-style-type: none"> - Men's Toilet – Rm's 111 and 204 - Women's Toilet – Rm's 113 and 205 <p>On: Jul 17 2020.</p>				
<p>Government Response. . Provide solid surface counter with integral sinks and counter-mounted faucet. Counter to be ABA compliant. Clarification detail to follow in forthcoming amendment. On: Jul 23 2020</p>				
<p>Current Request Status: Request Closed</p>				
<p>Information for this report is procurement sensitive.</p>				
8710807	Architectural	IF101C		Government Responses 8685257 & 8702888
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>The ProjNet Government Response 8685257 states that FF&E is by others (not in the contractor's scope). Sheet IF101C is the Furniture schedule, which includes Lockers (LK1, LK2, LK3) and Locker Benches (CH5, CH6). ProjNet Response 8702888 states that the Lockers and Locker Benches are to be provided by the contractor. This response also states that "EFM-1" is to be provided by the contractor, as well as the 2 Entrance Mats.</p>				

Please clarify what is to provided by the contractor, and please provide the Specifications for those items. What is "EFM-1"?

On: Jul 17 2020.

Government Response. . Lockers & locker benches to be provided by contractor. EFM-1, RG-1 and RG-2 to be by contractor.

EFM-1 (Entry walk-off Matt) information can be found on sheet IN601, location of mat can be found on IN101C. On: Jul 22 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8710819	Architectural	A-402 - Detail 3 & 4		
----------------	---------------	----------------------	--	--

Comment Classification: **Unclassified\\For Official Use Only (U\\FOUO)**

Please provide more information on the configuration of the Draft Curtain.

On: Jul 17 2020.

Government Response. . The draft curtain is created by the depth of the metal building steel beams, however to complete the draft curtain, the opening between the top of the structure and the roof panel above must be closed off where the purlins occur. The purlin space needs to be closed off as indicated per details 3 and 4 on A-402. These locations are indicated on sheets A-102A and A-102B per keynote 5.02 On: Jul 22 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8712044	Civil	G-006		
----------------	-------	-------	--	--

Comment Classification: **Unclassified\\For Official Use Only (U\\FOUO)**

Concerning temporary construction fencing, it is only noted on the east side of the site. Is temporary fencing required on the NW, W and S portions of the construction site?

On: Jul 17 2020.

Government Response. . Construction fence is required to separate the construction from the airfield operations area. On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8712054	Civil	G-006, CS-501, CS-502		
----------------	-------	-----------------------	--	--

Comment Classification: **Unclassified\\For Official Use Only (U\\FOUO)**

On G-006, the note for temporary construction fencing refers us to sheets CS-501 and CS-502. CS-501 and 502 give details of the new permanent security fencing. Is the temporary construction fence to be constructed per these details?

On: Jul 17 2020.

Government Response. . Temporary construction fence should meet the details shown on CS-501 and 502 with the exception, concrete is not required around the fence posts. On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8712089	Civil	CU202		
----------------	-------	-------	--	--

Comment Classification: **Unclassified\\For Official Use Only (U\\FOUO)**

Is the contractor responsible for installing the new site gas line to the building or the local utility provider? If the contractor, please provide a specification.

On: Jul 17 2020.				
Government Response. . Yes, Will provide specification 33 11 23 Natural Gas and Liquid Petroleum Piping in next amendment #3 On: Jul 23 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8712100	Civil	C-200	3	
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Refer to detail 3/C-200 regarding the Restricted Area Boundary Warning Sign. What is the sign mounted to?				
On: Jul 17 2020.				
Government Response. . The Restricted Area Boundary Warning Signs are painted on the pavement and not a traffic sign mounted on a sign post. See Detail 3 on Sheet C-200 On: Jul 23 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8712112	Civil	C-205		
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Refer to sheet C-205 and detail 3/C-200 regarding the Restricted Area Boundary Warning Sign. The note points to a square box on the drawing and notes (Typ.). Are the other "boxes" along this line and in this area supposed to designate this same sign / detail also? Are there a total of nine (9) required?				
On: Jul 17 2020.				
Government Response. . Painted signs shall be installed at the spacing indicated at the approximate "boxes" shown on the drawings. On: Jul 23 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8712127	Civil	C-301	1, 2, 3, 4 & 5	32 13 14.13
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Details 1 thru 5 on sheet C-301 refer to PCC Pavement in specification section 32 13 14.13. There is no such spec section in the bid documents provided. Please provide.				
On: Jul 17 2020.				
Government Response. . Specification Section 32 13 14.13 will be provided as part of the next amendment #3 On: Jul 23 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8712138	Civil	C-301	1, 4 & 5	
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Details 1, 4 & 5 on sheet C-301 refer to a subdrain in specification section 33 46 16. There is no such spec section in the bid documents provided. Please provide.				
On: Jul 17 2020.				
Government Response. . Specification Section 33 46 16 will be provided as part of the next amendment #3 On: Jul 23 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8712145	Civil			33 40 00

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

There does not appear to be a specification provided for the storm drainage system. Usually it is 33 40 00. Will a specification be provided?

On: Jul 17 2020.

Government Response. . Specification 33 40 00 Storm Drainage Utility is already provided in the bid package
On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8712195	Civil	C-301	5	32 11 33
----------------	-------	-------	---	----------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Detail 5 on sheet C-301 calls for 12" "Cement" Stabilized Subbase at spec section 32 11 33. The specifications provided do not include this section, but includes a section for Lime-Modified Subgrade. Please clarify what, if any is needed?

On: Jul 17 2020.

Government Response. . Specification Section 32 11 33 will be provided as part of the next amendment #3
On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8712233	Architectural	A-610		
----------------	---------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Please provide the glass lite size for door types B, BB and E.

On: Jul 17 2020.

Government Response. . Glass lite size for door type E shall be 24" wide by 34" high. Glass lite size for door types B and BB shall be 4" wide by 25" high. On: Jul 22 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8712304	Architectural	A-401		
----------------	---------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Please provide elevations, section cuts and finishes for the restroom vanities.

On: Jul 17 2020.

Government Response. . Provide solid surface counter with integral sinks and counter-mounted faucet. Counter to be ABA compliant. Clarification detail to follow in future addendum. On: Jul 22 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8712495	Architectural	IN601		
----------------	---------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Drawing IN601 calls for WB-1 to be 1" Hunter Douglas mini blinds, however there is no specification section related to window blinds. Please advise if this scope of work is GC responsibility or Owners.

On: Jul 17 2020.

Government Response. . Spec spec 12 21 00 is to be issued in amendment #2 submission. This scope is Contractor responsibility
On: Jul 22 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8712629	Mechanical			General
----------------	------------	--	--	---------

Comment Classification: **Unclassified\\For Official Use Only (U\\FOUO)**

Mechanical – Would the government consider the return duct for the terminal unit to be converted to oval spiral due to the size of the duct work versus the rectangular duct work as shown?

On: Jul 17 2020.

Government Response. . Yes oval spiral duct for the return to terminal units would be acceptable. Equivalent sizes shall be provided. On: Jul 22 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8712632	Commissioning			General
----------------	---------------	--	--	---------

Comment Classification: **Unclassified\\For Official Use Only (U\\FOUO)**

Please confirm the commissioning will be 1st tier and provided by the general contractor as outlined in spec section 01 91 00.15 paragraph 1.1 Summary?

On: Jul 17 2020.

Government Response. . Spec 01 91 00.15 will be amended to clarify On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8712639	Structural	S001		23 05 48.19
----------------	------------	------	--	-------------

Comment Classification: **Unclassified\\For Official Use Only (U\\FOUO)**

• Spec section 23 05 48.19 calls for Seismic bracing on this project. Sheet S-001 calls for Seismic class B on this project. Class B normally does not require bracing. On previous projects at MAFB, Seismic bracing was not required. In accordance with the IBC and ASCE codes, seismic is not required for the Seismic Design Category of "B" which is the seismic design category on the structural drawing S-001.

Please confirm if Seismic bracing is required on this project for all trades?

On: Jul 17 2020.

Government Response. . No seismic bracing is required. On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8713351	General	-	-	-
----------------	---------	---	---	---

Comment Classification: **Unclassified\\For Official Use Only (U\\FOUO)**

Details 1/401, 2/401, and 3/401 illustrate the layout and notes associated with restrooms. This information does not provide the profile, size or materials associated with the vanities in each of the restrooms. Can you please provide a profile with dimensions and materials required for all restroom vanities/countertops?

On: Jul 19 2020.

Government Response. . Provide solid surface counter with integral sinks and counter-mounted faucet. Counter to be ABA compliant. Clarification detail to follow in future amended drawing(s)/schedules. On: Jul 22 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8713352	General	-	-	-
----------------	---------	---	---	---

Comment Classification: **Unclassified\\For Official Use Only (U\\FOUO)**

The reflective ceiling plans (A-801A, A-801-B, A-801-C, A-801-D and A-802-C) do not identify a finish for the exposed ceiling areas. On drawing IN601, the Finish Schedule does not show any paint on the ceiling for Hangar 101, CTK Work Area 114, Weapons Work Area 118, DASH 21 - 124, and Engine Backshop 128. Please confirm these ceiling surfaces and exposed

piping, conduit, and ductwork are not required to be painted.

On: Jul 19 2020.

Government Response. . Open to structure ceilings to be Painted PNT-3. On: Jul 22 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8714308	Structural			05 12 00 1.3
----------------	------------	--	--	--------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Specification 05 12 00 1.3 requires a structural steel fabrication and erection to be performed by AISC Certified Fab Plants and Erectors.

Would you allow non-AISC-Certified contractors to perform the fabrication & installation of stairs, steel gratings, bollards, ladders and railings?

On: Jul 20 2020.

Government Response. . AISC Quality Certification applies only to structural steel buidling elements covered under Section 05 12 00. Steel elements that are covered in the other Division 05 specification sections do not require AISC Quality Certification. On: Jul 22 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8714675	General			13 34 19
----------------	---------	--	--	----------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

The PEMB specification 13 34 19 calls for aluminum skin insulated panels. We would prefer to use steel skin panels, especially since a weather tight warranty is involved. Are steel skins acceptable in lieu of aluminum skins?

On: Jul 20 2020.

Government Response. . For this initial Bid, use the aluminum skin wall panels as specified. The awardee, if desired, may elect to propose a substitution with a desired reason/benefits for substitution request. On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8714913	Civil	CS102		
----------------	-------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Does the proposed turn-around on Sijan Street receive a 24" concrete curb and gutter around it? It's hard to determine from the drawings.

On: Jul 20 2020.

Government Response. . No curb and gutter is required at the end of Sijan Street On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8715026	Civil	CS102		
----------------	-------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Are the "AGE - Dedicated Parking Spaces" denoted on the paving with painted striping? If so, is there a pattern? Is there any signage that needs to be provided at these locations?

On: Jul 20 2020.

Government Response. . This shown for information only. No striping or signage is required. On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8715133	Fire Protection/Life Safety	FX113		33 16 15
----------------	-----------------------------	-------	--	----------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Reference water storage tank. Drawing FX113 states it is to have a capacity of 150,000 gallons. Specification 33 16 15 states 188,000 gallons. Which is correct?

On: Jul 20 2020.

Government Response. . The water storage tank should be provided per specification section 36 16 15 which matches the dimensions given on FX120 and FX320. FIO, the tank was designed based on a commercially available bolted steel tank with a total volume of 188,000 gallons in order to meet the minimum required usable fire water storage volume of 150,000 gallons. On: Jul 22 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8715197	Civil	CS502		
----------------	-------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Light Duty Asphalt Paving is detailed on this sheet, but not Heavy Duty. Please provide a detail for Heavy Duty Asphalt Paving.

On: Jul 20 2020.

Government Response. . See Section 1 on on C-301 for heavy duty section. On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8715215	Structural	A-112		
----------------	------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

What is the thickness and reinforcing of the dumpster enclosure slab?

On: Jul 20 2020.

Government Response. . Use 10" slab, see Concrete note 10 on S001 for slab reinforcement On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8715314	Civil	C-301	5	
----------------	-------	-------	---	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Where does detail 5/C-301 apply? The Proposed Concrete Access Apron on CS102 states to see detail 3 sheet C-301. Is this a typo and it should be detail 5?

On: Jul 20 2020.

Government Response. . Detail 5/C-301 applies to the "infill" area/extension of the existing airfield parking apron near the location of the towway connection On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8715382	Structural	CS-101		
----------------	------------	--------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Please provide more detail for the "Low Wall" shown at the SW corner of B645.

On: Jul 20 2020.

Government Response. . The existing retaining wall (low wall), dock leveler, dock leveler pad, stairs, railings,

	trench drain and concrete pad in front of the retaining wall to remain. On: Jul 27 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8715402	Structural	CS-101	
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Please provide more detail for the "Loading Dock" that we are supposed to be making an 'addition to' at the south end of B645.			
On: Jul 20 2020.			
	Government Response. . Grades in these area to be adjusted to match exiting slab evelations and the new building and pavement elevations. Additional information to be provided in forthcoming amendment On: Jul 27 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8715489	Civil	L	33 00 00
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
What landscaping, if any is required?			
On: Jul 20 2020.			
	Government Response. . Grassing is per Sheets CG 507 & 508 Ds3, Bermuda Common On: Jul 23 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8715504	Civil	CG-501	
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Is the Detention Pond Concrete Spillway to receive any type of reinforcing steel?			
On: Jul 20 2020.			
	Government Response. . The spillway does not require reinforcing steel On: Jul 23 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8715588	Civil	C-301	
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Please provide better details for the subdrain system. How deep? How wide of a trench is required?			
On: Jul 20 2020.			
	Government Response. . Subdrain inverts and structure rim elevations for the subdrain system are shown on CG111. Width of trench shall be in accordance with Section 33 46 16 of the specifications. On: Jul 23 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8715634	Civil	CG-103 and CG-104	
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Please provide more detail for the 15" Storm Header Pipe connected to downspouts. What type of piping is it? PVC? HDPE? How is it connected to the downspouts?			
On: Jul 20 2020.			
	Government Response. . Refer to A-202 for downspout note. Also see P-502 amendment #2 which includes connection notes and details. On: Jul 22 2020		

Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8715635	Plumbing	CG104 and P502		
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
How does the Rainwater Tank connect to the roof downspouts? Please provide further details.				
On: Jul 20 2020.				
Government Response. . Refer to A-202 for downspout note. Also see P-502 amendment #2 which includes connection notes and details. On: Jul 23 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8715830	Fire Protection/Life Safety	CU201		
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Notes for both the fire water tank and the pumphouse say "by others". Is the water tank and pumphouse part of this contract?				
On: Jul 20 2020.				
Government Response. . The fire water tank and pumphouse is part of this project. Refer to individual discipline sheets in set for additional information on the fire water tank and pumphouse. On: Jul 23 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8715928	Structural	S-001		
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Refer to High Mast Lighting Foundations, Note #1. Please confirm that the contractor is responsible for obtaining an additional soil boring for the EOR to evaluate and confirm their design for the foundation.				
On: Jul 20 2020.				
Government Response. . Soil boring and applicable evaluation is required by the GC at high mast lighting location. On: Jul 28 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8716085	Architectural			07 41 63 and 13 34 19
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Specification section 07 41 63 Fabricated Roof Panel Assemblies, Section 1.8 indicates metal roof panel manufacturer's warranty is required for 30 years after the Government accepts the roof work. Specification Section 13 34 19 Special Construction, Section 1.10.2 – Roof System Weather-tightness Warranty- indicates manufacturer to supply no-dollar-limit warranty for 20 years from date of acceptance by the government. Typically, for metal buildings, we see the roof warranty as defined in Specification Section 13 34 19. Please advise as to what specification is to be followed regarding roofing warranty.				
On: Jul 20 2020.				
Government Response. . The 20 year Fabricated Roof Panel Warranty is correct On: Jul 23 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8716093	Architectural			12 50 00.13

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Please provide the "FF&E Package Attachment" that is noted in Spec Section 12 50 00.13, Paragraphs 2.2 and 2.3.

On: Jul 20 2020.

Government Response. . FF&E is NOT part of this project's bid On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8716944	Structural	S-101C, S101D		
----------------	------------	---------------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Please reference drawings S-101C & D, which show keynote S8 near CL A/4. There is no definition for this keynote. Please clarify keynote S8.

On: Jul 21 2020.

Government Response. . Keynote SB8 is "TOP OF FOOTING ELEVATION IS -6'-0"" On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8716945	Structural	S-111		
----------------	------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Reference the Fire Pump building foundation plan on S-111. There are columns shown along CL 1 & 3/B that do not have any defined foundation (footing / pier) information. Please clarify.

On: Jul 21 2020.

Government Response. . Section 8/S-301 applies at CL1 & 3/B. On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8716947	Structural	A-411		
----------------	------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Reference drawing A-411, which details Stair #1. There is no reference to Stair #2. Please confirm that Stair #2 is opposite / identical to Stair #1.

On: Jul 21 2020.

Government Response. . Yes Stair No 1 and Stair No 2 are identical, just opposite hand. On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8716953	Architectural	A-101D		
----------------	---------------	--------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Reference drawing A-101D, which shows the screen wall for the chiller and references A-112. The screen wall has the same detail as the Dumpster Enclosure, which has no Structural reference. Please clarify the required foundation for the Chiller Screen Wall.

On: Jul 21 2020.

Government Response. . The Section 1/A-112 is for the chiller screen wall as well as then dumpster screen wall. See sheet A-101D for the section cut on the screen wall. Both have the same foundation. On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8716959	Structural	S-101E		
----------------	------------	--------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Reference drawing S-101E, specifically room 110 – Secure Storage and room 116 – Weapons Vault. Detail 1/S-310 is indicated to show the condition where the concrete cap for those rooms ties into the masonry wall. There is no corresponding detail to show that condition for the 2nd floor room 214 – Flight Vault. Please provide a detail showing the condition where the concrete ceiling slab ties back into the walls for room 214.

On: Jul 21 2020.

Government Response. . Section 1/S-310 also applies to room 214, with the top of slab elevation indicated in keynote SF10 On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8717686	Civil			32 11 23.23
----------------	-------	--	--	-------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Paragraph 1.1.1 mentions "contract unit prices". The bid form does not have unit prices. Please specify if contract unit prices are to be used and that the bid form will be modified.

On: Jul 21 2020.

Government Response. . No bid form modification will be provided. Unit prices do not apply On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8717713	Civil			32 12 15.13
----------------	-------	--	--	-------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Throughout the specification, it mentions the method of measurement and payment of the asphalt pavement, along with a unit price. The bid form does not have unit prices. Please specify if contract unit prices are to be used and that the bid form will be modified.

On: Jul 21 2020.

Government Response. . Unit prices are NOT applicable to this bid On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8718024	Structural	S-001		
----------------	------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Refer to Sheet S-001, Foundations Note #1. Please provided referenced Geotechnical Engineering Report dated February 2019.

On: Jul 21 2020.

Government Response. . We will provide the Geotech report in a forthcoming amendment to the IFB package On: Jul 29 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8718234	Architectural			Lockers
----------------	---------------	--	--	---------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Per RFI 8702888 response, The lockers are a part of GC scope. The locker counts are different looking at A-101D and IF101D. Please advise which counts to proceed with pricing. Also please provide specification section related to lockers. GC

needs to know what type of construction for each locker.

On: Jul 21 2020.

Government Response. . Locker count is correct for room 128 on sheet A-101D, 10 full height lockers. IF101D and FF&E package to be updated in future amendment. On: Jul 22 2020

Government Response. . The text below appends or clarifies ALL previous replies. Revised sheet IF101D is forthcoming in Amendment #3 On: Jul 30 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8718237	Architectural			10 21 13
----------------	---------------	--	--	----------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Spec Section 10 21 13 – Toilet Compartments list multiple materials for partition construction. Paragraphs in section 2.2 list out metal sheet where as materials called out in section 2.3 list solid phenolic. Finishes paragraph 2.8.1 calls for solid plastic partitions. Please advise what material toilet partitions and urinal screens should be priced as.

On: Jul 21 2020.

Government Response. . Toilet partitions to be solid phenolic plastic. On: Jul 22 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8718240	Architectural	A-621		
----------------	---------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Drawing A-621 shows the exterior Aluminum Window to be tagged W3, Drawings A-622 shows the interior rated HM frame window to be W3. The details shown on A-622 show the W3 frame to be HM. Please clarify which type of window is intended to be W3.

On: Jul 21 2020.

Government Response. . The window Type W3 on sheet A-621 only applies to exterior windows and is aluminum as indicated by the details. The window type W3 on sheet A-622 only applies to Interior windows and is HM as the details mindicate. On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8718244	Architectural	A-402		
----------------	---------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Drawing A-402 calls for steel ladder with Fall Arrest System. Please provides specification section related to fall protection system.

On: Jul 21 2020.

Government Response. . Per note on sheet A-402, Enlarged plan 1, the Fall Arrest system shall comply with OSHA regulations to meet the requirements of 29 CFR 1910.28 On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8718248	Architectural			41 22 13.14
----------------	---------------	--	--	-------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Spec Section 41 22 13.14 states a top-running 5 ton bridge crane with a span of 148 feet and mentions crane rail. 148' span for a top-running crane is pretty unusual. Please advise if patented track utilizing multiple runways and an undermount crane would be an acceptable option for this project, like many military jobs.

On: Jul 21 2020.				
Government Response. . Provide top running crane as designed On: Jul 28 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8719235	Architectural	A-610		
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Please clarify Door No. 109B on the Door Schedule. Nothing is shown in the information columns.				
On: Jul 21 2020.				
Government Response. . Please refer to Amendment 02 forthcoming On: Jul 23 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8719237	Architectural	A-111		
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Is Door 102P (the OH coiling door) to be insulated? Note #3 does not specify.				
On: Jul 21 2020.				
Government Response. . Please see keynote 8.04 which calls for the door to be Insulated On: Jul 23 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8719240	Architectural	A-622		
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Are there any W4 non-rated HM window frames in this job? None can be located on the drawings right off hand.				
On: Jul 21 2020.				
Government Response. . Please see sheet A-101D, Office 129 which has a W4 On: Jul 23 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8719794	Architectural			07 41 63 and 07 61 15
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Specification Section 07 41 63 - Fabricated Roof Panels Assemblies- Item 2.5.1- C-2 indicates the roof panel to have a 1 1/2" high rib at 12" O.C. with small stiffening ribs. Panel width 38" with 36" coverage.				
Specification Section 07 61 15 –Aluminum Standing Seam Roofing- Item 2.2.1.5 indicates roof panels to be 12" wide with a minimum of 2" high vertical legs and two .37" stiffening ribs at 4" O.C. between legs.				
Please advise specification to utilize for roof panels.				
On: Jul 22 2020.				
Government Response. . Specification section 07 41 63 applies to the Fabricated Roof Panels (Insulated) referenced by keynote 7.02 in the drawings. Specification section 07 61 15 only applies to the exterior, uninsulated roof outside vestibule 102. On: Jul 23 2020				
Current Request Status: Request Closed				

Information for this report is procurement sensitive.

8719878	Fire Protection/Life Safety			21 30 00, 2.8
----------------	-----------------------------	--	--	---------------

Comment Classification: **Unclassified\\For Official Use Only (U\\FOUO)**

1. The fire pump specifications call for a 450hp motor on the pumps however in order to make the requirement for pressure & volume and to meet the newest UL 448 requirements the horse power will likely be closer to 600hp. We are unaware of any manufacturer that can power a motor of that size on 3/60/480v. The manufactures are all telling us it will need to be a high voltage motor at 3/60/4160v. That adds another issue as it relates to a soft start controller? Can you clarify this issue or please provide an acceptable make and model?

On: Jul 22 2020.

Government Response. . The design pressure & flow selection was 200psi & 2500gpm. The design fire pump selection was based on 450 HP motor. Multiple vendors are available to meet this design scenario. The basis of design used is AC Fire Pump series 9100, 1785 RPM, 450 motor HP, 480Volt, 3Phase. The contractor shall be responsible for providing a vendor that meets the design pressure & flow demand and utilities the electrical services shown. On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8720277	Structural	S-501		
----------------	------------	-------	--	--

Comment Classification: **Unclassified\\For Official Use Only (U\\FOUO)**

Please reference detail S-501. Please provide the dimensions of the column blockouts for the C1 columns.

On: Jul 22 2020.

Government Response. . Column blockouts may be diamond or circular at contractor's option and of sufficient size to maintain minimum 3" of concrete cover over baseplates and anchor bolts. On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8720278	Structural	S-101C		
----------------	------------	--------	--	--

Comment Classification: **Unclassified\\For Official Use Only (U\\FOUO)**

Please reference drawing S-101C. There are a number of footings along CL 3 (at CL's B, C, D, E, F, G, and H) that have no pier designations but do have what appears to be C1 type steel columns, which would require blockouts. Please clarify what is required at those locations.

On: Jul 22 2020.

Government Response. . The columns in question are to be provided by PEMB to support 2nd floor framing. Columns should be supported directly on footing as shown in Detail 1/S-501 On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8720280	Structural	S-301	8 & 9/S-301	
----------------	------------	-------	-------------	--

Comment Classification: **Unclassified\\For Official Use Only (U\\FOUO)**

Please reference detail 8/S-301. Underneath the width dimensions, (X 2'-0") is shown. This situation also occurs at detail 9/S-301. Please clarify what is meant by these notes.

On: Jul 22 2020.

Government Response. . The (x 2'-0") indicates the width of the extended thickened slab under the wind column. On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8720283	Structural	S-001		
----------------	------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Please reference S-001. Foundations Note #4 states "To minimize weathering, the last 6" of excavation for all footings shall be made immediately prior to placement of footings." Given that the final 6" of fine grading excavation needs to occur prior to reinforcement being placed into the footing , followed by inspection, then concrete placement, please define exactly what immediately prior to placement of footings means in terms of time. Please also consider waiving this requirement.

On: Jul 22 2020.

Government Response. . The time between excavation and placement of concrete should be such that the bearing capacity of the soil below the foundations is not compromised by weathering. Suitability of soil below foundation is to be verified by special inspections. On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8720285	Structural	A-101C		
----------------	------------	--------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Please reference A-101C. It appears that there is a concrete slab/pad at the entry canopy (roughly CL 3/A0). There are no details top show this condition in the structural drawings. Please provide details showing the dimensions of concrete required at the Entry Canopy.

On: Jul 22 2020.

Government Response. . The dashed line shown on A-101C represents the outline of the entrance canopy above. See CS101 and CS102 for exterior slabs. On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8720287	Structural	S-101C		
----------------	------------	--------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Please reference S-101C. There are a three walls that have as SB6 or SB7 designation, indicating a thickened slab condition under CMU walls. However there are a number of CMU walls indicated (mostly east of CL E) that have no such designation. Additionally, S-101D also has CMU walls that have no such indication either. Please clarify which CMU walls, load bearing and non-load bearing, require a thickened slab.

On: Jul 22 2020.

Government Response. . Provide thickened slab below all interior CMU partitions as noted in Detail 4/S-501. Thickened slab shall be widened per Note 4 at load-bearing CMU where no other foundation is indicated. Load bearing CMU includes all CMU walls required for support of mezzanine framing, 2nd floor framing, concrete caps, and stair framing that are indicated on the structural framing plans. On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8720366	Architectural			133419
----------------	---------------	--	--	--------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Reference Section 13 34 19 Metal Building System- Paragraph 1.10 Warranty requires a 20 year no dollar limit warranty on ".....metal building systems." All metal building manufacturers will warrant the finish and weather tightness of the metal roofing and siding panels for 20 years, as referenced in the next two paragraphs, but not the metal building frame, which they will warrant for 5 years. Please clarify that the 20 years no dollar limit warranty only applies to roof and wall panels.

On: Jul 22 2020.

Government Response. . The 20 year warranty is for the weathertightness of roof and wall panels, not the

	building structure system to which the 5 year warranty applies. On: Jul 23 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8720368	Architectural		133419
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Reference Section 13 34 19 Metal Building System-Reference Paragraph 3.13.3 Contractors Five (5) Year No Penal Sum Warranty- This warranty is fine with metal building manufacturers but conflicts with paragraph 1.10. of same section, please clarify.			
On: Jul 22 2020.			
	Government Response. . The 20 year warranty is for the weathertightness of roof and wall panels, not the building structure system to which the 5 year warranty applies. On: Jul 23 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8720860	Architectural	IN-601	12 21 00
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Refer to Finish Schedule on IN-601. WB-1 for Window Blinds refers us to spec section 12 21 00. There is not section 12 21 00 provided in the documents. Please provide this spec section.			
On: Jul 22 2020.			
	Government Response. . Spec section 12 21 00 will be available in amendment #02. On: Jul 23 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8720870	Architectural	IN-601	09 67 23.13
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
PNT-2 on the Finish Schedule refers us to spec section 09 67 23.13. This spec section is for Resinous Floors. Should the reference spec section for PNT-2 be 09 90 00?			
On: Jul 22 2020.			
	Government Response. . Spec section has been updated to 09 90 00, new IN601 sheet is included in amendment 02 forthcoming. On: Jul 23 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8720879	Architectural	IN-601	
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
WB-1 Window Blinds is listed on the finish schedule. Please provide locations for the window blinds.			
On: Jul 22 2020.			
	Government Response. . Blindes to be placed on all office windows as per note D, IN601. Window blinds to be placed in following rooms: 209, 210, 212, 213, 220, 221, 222, 201. On: Jul 23 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8720980	Architectural	A;101	

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Please provide a specification for the lockers shown.

On: Jul 22 2020.

Government Response. . Locker specification will be issued in Amendment #3 On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8721290	General			Division 01
----------------	---------	--	--	-------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Will the Cybersecurity Maturity Model Certification (CMMC) be required for this project?

On: Jul 22 2020.

Government Response. . Cybersecurity Maturity Model Certification On: Jul 31 2020

Government Response. . This new text supercedes ALL previous replies. No, it will not On: Jul 31 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8721395	General			SF-1442; 13.A.
----------------	---------	--	--	----------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

We respectfully request a one week extension of the due date for the project to Thursday, August 13.

On: Jul 22 2020.

Government Response. . Any changes to the bid opening date/time will be addressed by amendment to the solicitation. On: Jul 24 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8721544	Architectural			Wage Rates
----------------	---------------	--	--	------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Please provide wage rate for pipe insulators.

On: Jul 22 2020.

Government Response. . See beta.sam.gov for wage rates On: Jul 24 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8722081	Contracting			Solictiation
----------------	-------------	--	--	--------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Is the fire pump house to be considered part of CLIN 0001 or CLIN 0002?

On: Jul 23 2020.

Government Response. . Fire pumphouse system is to be bid on CLIN 002 On: Jul 23 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8722200	Structural	A-311, A-312 & A-314		
----------------	------------	----------------------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Architectural details 1/A-311, 1/A-312, and 1/A-314 all show continuous rigid perimeter insulation. None of the slab condition details on S-301 and S-302 show under slab insulation. Please clarify whether under slab insulation is required and the locations where it is installed.

On: Jul 23 2020.

Government Response. . Perimeter Insulation is required per architectural details. See also specification section 07 21 13 paragraph 3.5 On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8722204	Structural	S-501		
----------------	------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Please reference detail 5/S-501, which indicates a 4" granular full. Is this material to be as specified per section 32 11 23 – AGGREGATE BASE COURSE? Please clarify what this material is and confirm that this is the only base material required under slab on grade.

On: Jul 23 2020.

Government Response. . Granular Fill under slab-on-grade is covered under Section 31 00 00 and is classified as Capillary Water Barrier. On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8722221	Architectural	A-111		
----------------	---------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Finish Schedule not provided for Pump Building. Please confirm finishes finish equal to Mech Rm #123 per IN601-Finish Schedule.

On: Jul 23 2020.

Government Response. . Finish schedule will be provided for pump room on A-111 in amendment 3 submission. On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8722417	Structural	S-302, S-501 & S-502		
----------------	------------	----------------------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Please reference details 2/S-302 and 4/S-501, both of which refer to 4/S-502 for CMU wall reinforcement. Detail 4/S-502 shows form deck attachment. Please confirm the correct reference detail for CMU wall reinforcement should be 4/S-503.

On: Jul 23 2020.

Government Response. . Reference should be 4/S-503 On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8723290	Mechanical	MH102D	Note C	
----------------	------------	--------	--------	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Reference Government Response 8702291, spiral duct was approved in lieu of rectangular double wall duct. Please confirm alternate duct is required to be double wall spiral duct.

On: Jul 23 2020.

Government Response. . Confirmed this alternate duct should also be double wall. On: Jul 28 2020

Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8723481	Civil			General
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Is the site intended to balance?				
On: Jul 23 2020.				
Government Response. . No. It is not intended to balance On: Jul 28 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8723483	Civil			General
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Is there a borrow pit onsite that can used by the contractor for fill or spoils?				
On: Jul 23 2020.				
Government Response. . No borrow pit is available on Moody AFB On: Jul 24 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8723484	General			General
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Are there any work hour restrictions?				
On: Jul 23 2020.				
Government Response. . Normal 8-hour day, 0700-1630 hrs. 5 days/week. On: Jul 23 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8723488	Civil			General
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Please provide details (PVC or DIP) for the 15" header pipe?				
On: Jul 23 2020.				
Government Response. . A detail will be provided in the next amendment #3 On: Jul 28 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8724445	Architectural			11 34 19
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
In Spec Section 11 34 19, Under Part 2.4 Section, 2.4.3 – Foam-Insulation Core Wall Panels. The Paragraph calls for factory formed wall panels with either polyisocyanurate or polyurethane foam. But in Section 2.4.4, second paragraph, it calls for rock wool fiber insulation. All details and sections on the plans call for foam insulation. Which type of insulation is correct?				
On: Jul 24 2020.				
Government Response. . Foam Insulation is required On: Jul 28 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8724447	Architectural			11 34 19

<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>In Spec Section 11 34 19, Under Section 1.10.2 Roof System Warranty, The roof warranty is already specified in Spec Section 07 41 63 and is different from this roof warranty. Please advise.</p> <p>On: Jul 24 2020.</p>				
<p>Government Response. . Roof Panel Warranty shall be 20 years On: Jul 28 2020</p>				
<p>Current Request Status: Request Closed</p>				
<p align="center">Information for this report is procurement sensitive.</p>				
8724450	Architectural			07 41 63 & 07 61 15
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>There are two spec section for the roof system. Looking at the details and sections, it seems that spec section 07 41 63 applies for this project. Are both roof systems used on this project? If so please indicate the location or area of roof to receive standing seam roofs. Please Advise</p> <p>On: Jul 24 2020.</p>				
<p>Government Response. . Both sections apply to this project. The only place that the standing seam roof occurs is at the exterior entrance canopy outside vestibule 102 which is uninsulated. All other roofs shall be the Fabricated Roof Panel Assemblies On: Jul 28 2020</p>				
<p>Current Request Status: Request Closed</p>				
<p align="center">Information for this report is procurement sensitive.</p>				
8724836	Contracting	Page49 of 844		Contract Clause 252.203-7004
<p>Comment Classification: UNCLASSIFIED (U)</p> <p>RE: Volume I of the Specifications: Art. (2):</p> <p>Can your team provide confirmation of available funding for this project?</p> <p>On: Jul 24 2020.</p>				
<p>Government Response. . the programmed funds are available. The validated low bidder price information will be provided to the USAF for funding action. On: Jul 24 2020</p>				
<p>Current Request Status: Request Closed</p>				
<p align="center">Information for this report is procurement sensitive.</p>				
8725285	Specifications	Civil		
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Is cathodic protection systems required on this project? If so, please provide a specification and locations.</p> <p>On: Jul 24 2020.</p>				
<p>Government Response. . A sacrificial anode cathodic protection system for the tank(s) shall be provided by the tank manufacturer per specification section 33 16 15 paragraph 2.3.4. On: Jul 28 2020</p>				
<p>Current Request Status: Request Closed</p>				
<p align="center">Information for this report is procurement sensitive.</p>				
8725837	Antiterrorism-Force Protection			08 60 45 and 08 51 13
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Spec section 08 60 45 for Translucent Panels calls for them to meet a Blast Load criteria. Do the aluminum windows and storefront require any such Blast Loading design / installation?</p>				

On: Jul 24 2020.				
Government Response. . Translucent panels, aluminum windows and storefronts do not require blast loading design/installation. On: Jul 28 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8725938	Architectural			12 50 00.13
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Please confirm that even though we have a specification for FF&E, that per RFI response 8716093 FF&E is NIC.				
On: Jul 24 2020.				
Government Response. . Lockers will be part of Contractor scope; spec section 10 51 13 has been submitted in amendment 3. On: Jul 28 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8726075	General			Amendment 0002
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
We are unable to upload the revised drawings issued in Amendment 0002:				
Volume 1: A-401, A-610, CG201, CS503, IN101B and IN601				
Volume 2: P-502, T-001, T-201, T-502 and T-602				
Please reissue these drawings.				
On: Jul 24 2020.				
Government Response. . Please see 2 files uploaded to the solicitation notice at beta.sam.gov. W912HN-20-B-3002_AMD2_VOLUME1.pdf and W912HN-20-B-3002_AMD2_VOLUME2.pdf On: Jul 24 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8726079	General			Site Visit
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Please provide the sign-in sheet from the site visit.				
On: Jul 24 2020.				
Government Response. . Please see W912HN-20-B-3002_Pre-Bid Visit.pdf file uploaded to the solicitation notice on beta.sam.gov. On: Jul 27 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8727459	Construction Management	N/A	N/A	Form 1442, 13,D
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Form 1442, 13, D states offer to be held for up to 150 calendar days. 1. Are the funds not available for this project? 2. With the crisis at hand, we are seeing material pricing issues and would like to request this be reduced to 60 calendar days.				
On: Jul 26 2020.				
Government Response. . Please see Projnet Inquiry# 8724836 response. We have considered the request to reduce the number of days from 150 to 60 and it will remain unchanged. On: Jul 28 2020				

Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8727460	Sustainability			01 33 29, 1.4.6, f, 1-5
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
<p>Section 01 33 29, 1.4.6, f,1-5 – states contractor is responsible for the fees to be paid to LEED for the certification & plaque on the wall. Please provide the copy of the of the registration which typically shows the cost that will need to be paid to LEED Green Building Council, otherwise please provide an allowance we should carry to pay Green Building Council for the certification.</p> <p>On: Jul 26 2020.</p>				
<p>Government Response. . The project has already been registered with USGBC by the client on May 25, 2016 . The LEED Design review has also been completed. All fees (registration and design phase review) to this point have been paid. When the contractor submits the remaining construction phase credits a fee of \$1,018.80 will be due to USGBC before the final review will commence.</p> <p>The plaques and certificates are at the client's discretion to select. Several styles and price ranges are available from GreenPlaque.com.</p> <p>The final copy of the Design Review is provided for clarity. To date 40 points have been earned towards the final silver certification.</p> <p>Once the contract is awarded the contractor's sustainability representation will be granted access to the LEED Online system for documentation. On: Jul 29 2020</p>				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8727461	Construction Management	n/a	n/a	01 45 3.4.3
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
<p>Section 01 45 00, 3.4.3 states the contractor is to directly employ a specialized person or firm for QC for civil, electrical, environmental, mechanical, structural, submittals, TAB, testing, as well as commissioning and to be onsite during performance of specified work. 1. Please consider allowing these QC personnel to be part of the subcontractor's team. The project will flow much smoother having the subs perform these requirements to these standards. 2. Confirm the CQC manger can perform these tasks if qualified as implied in the last sentence. 3. For building commissioning does this mean we are to have another firm oversee the Commissioning firm as well? 4. Please consider allowing the environmental QC to have say 5 years of experience as the other key trades do not require degree personnel. 5. Please consider removing the requirements for the TAB QC to be hired by the GC or at lease having the certifications. 6. Please consider allowing these QC responsibilities to be performed by the sub with the oversight of the QC manager, the site and project is not that large or complicated to require this many layer of quality control activities.</p> <p>On: Jul 26 2020.</p>				
<p>Government Response. . 1. As indicated in the referenced paragraph, these personnel are to be directly employed by the Contractor.</p> <p>2. Confirmed - as long as he is determined by the Contracting Officer to be qualified.</p> <p>3. Per Section 01 91 00.15, Total Building Commissioning, the Commissioning Firm must be a first tier subcontractor of the General or Prime Contractor.</p> <p>4. Five years experience would be acceptable subject to review and approval by the Contracting Officer.</p> <p>5. The TAB QC may have other duties but must be directly employed by the Contractor and must have requisite certifications.</p> <p>6. Reference response to item 1 above. On: Jul 30 2020</p>				

Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8727462	CAD-BIM	n/a	n/a	01 78 00, 3.1
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Section 01 78 00, 3.1 – As built CAD drawings. Do the CAD as built drawings have to be prepared by a registered architect or engineer?</p> <p>On: Jul 26 2020.</p>				
<p>Government Response. . The final as-built drawings are to be prepared in accordance SAS CAD Standards by an appropriate person with understanding of the same to assure a correctly formatted set of drawings is submitted On: Jul 28 2020</p>				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8727463	Design Team Leader	n/a	n/a	04 20 00, Masonry 2.4.1.3
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Section 04 20 00, Masonry 2.4.1.3 Colored Mortar states to provide colored mortar to match Moody AFB standard color mortar. 1. Please provide this color for mortar. 2. Is the split face CMU to be gray or colored? If colored, please provide the color/manufacture as well.</p> <p>On: Jul 26 2020.</p>				
<p>Government Response. . Please see the Exterior Color Schedule on sheet A-201 for the colors of the split face CMU and also paragraph 2.2.2.4. Mortar color shall match the split face CMU. On: Jul 28 2020</p>				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8727471	Interior Design	n/a	n/a	12 50 00.13 section 2.3
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Division 12 50 00.13 section 2.3 refers to the FF&E attachment in conjunction with the drawings and specifications for the furniture. Is this an additional document that should be provided?</p> <p>On: Jul 26 2020.</p>				
<p>Government Response. . FF&E is not in this bid. Lockers, however, are a CF-CI item. Note Amendment #3 forthcoming On: Jul 28 2020</p>				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8727962	Electrical	E-514	Panel LA5	
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>This is to expand on Projnet RFI#8703037. See Circuit #8 of Panel LA5 on Plate E-514 of bid documents. This is the existing 240V panel being relocated under this project. This circuit feeds a 30' square CCTV pole on a precast base. The pole was installed at the same time as the new highmast poles ~2017. Will this pole be relocated by Gov't? Is it to remain? Shall Contractors relocate it under this contract? If it is being relocated under this contract by Contractors, where should it be moved to?</p> <p>On: Jul 27 2020.</p>				

	Government Response. . The CCTV pole will be noted in Amendment #4 to relocated to a position to be determined no greater than 100ft from the current location On: Jul 31 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8728650	Environmental		01 57 19
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Spec section 01 57 19 Temporary Environmental controls SD-01 Preconstruction Submittals - Is the contractor required to apply for and pay for a storm water notice of intent NPDES for this project?			
On: Jul 27 2020.			
	Government Response. . No, the contractor not responsible for this notice On: Aug 03 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8728651	Structural	2/S-501	03 30 00
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Please reference specification section 03 30 00 – CAST-IN-PLACE CONCRETE. Paragraph 3.11.1.1 states that the Maximum Allowable Construction Joint Spacing in slabs on ground are not to exceed 1,200 square feet. Per detail 2/S-501, the condition for a Construction Joint is indicative of a formed edge / bulkhead, which require smooth dowels. More importantly, this would seem to indicate that slab-on-grade placements also cannot be in excess of 1,200. For the overall area of building requiring SOG, this would equate to roughly 43 separate slab placements. Please clarify the spec requirement for Construction Joints spacing and/or the typical detail for Construction Joints.			
On: Jul 27 2020.			
	Government Response. . Slab on Grade placement must meet the area requirement in the specification and follow the construction joint detail 2/S-501. On: Jul 28 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8728653	Construction Management		General
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Please confirm that a separate Superintendent, a Separate QC manager and a separate SSHO are required for this project. One role cannot work dual hats.			
On: Jul 27 2020.			
	Government Response. . The requirements of section 01 35 26 will not be changed. Separate stand-alone duties for these roles/positions On: Jul 31 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8728730	General		01 57 19
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Spec section 01 57 19 paragraph 3.17.1 application : The specs say that the contractor is to apply pesticides using a state certified pesticide applicator in accordance with EPA label restrictions and recommendations. Can the government provide a list or link for the contractor to contact state certified applicators?			
On: Jul 27 2020.			
	Government Response. . We do not maintain this sort of information. Check with your potential applicators on their own licensing credentials On: Jul 29 2020		
	Current Request Status: Request Closed		

Information for this report is procurement sensitive.

8728735	Mechanical			Spec Sections 25 all inclusive
----------------	------------	--	--	--------------------------------

Comment Classification: **Unclassified\\For Official Use Only (U\\FOUO)**

Spec Sections 25 all inclusive - Cyber security for Hydraulic Passenger Elevators, for Fire and Life Safety Systems, for BACnet Direct Digital Control Systems for HVAC, for interior distribution systems, for switchboards, for power systems and metering, for lighting systems and for UNMS front end Integration – these requirements add a lot of cost to the project. It is customary for the GC to reach out to the DDC controls contractor to cover these items and a lot times the DDC controls contractors are just starting to get acclimated to these new requirements. Can the government provide a contact for the companies that can provide the required Cyber Security for this project so competitive pricing can be obtained?

On: Jul 27 2020.

Government Response. . Both Gov't and industry are going through learning process. We don not maintain a list of companies as noted in this inquiry On: Jul 30 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8728740	Environmental			Spec Section 31 31 16.13
----------------	---------------	--	--	--------------------------

Comment Classification: **Unclassified\\For Official Use Only (U\\FOUO)**

Spec Section 31 31 16.13 Chemical Termite Control – paragraph 2.2.1 Termiticides tell the contractor to provide termiticides currently registered by the EPA or approved for such use by the appropriate agency of the host county. Does the base have a specific approved chemical termite product that is approved and can be priced correctly upfront?

On: Jul 27 2020.

Government Response. . The base does not specify an approved termite control product. On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8728745	Environmental			Spec Section 31 31 16.13
----------------	---------------	--	--	--------------------------

Comment Classification: **Unclassified\\For Official Use Only (U\\FOUO)**

Spec Section 31 31 16.13 Chemical Termite Control – paragraph 1.7 Warranty letter c. requires the reinspection of the building 180 days after retreatment. Can this requirement be waived to help save costs?

On: Jul 27 2020.

Government Response. . No, this requirement cannot be waived. This is typically just a visual inspection On: Jul 29 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8728747	Electrical			General
----------------	------------	--	--	---------

Comment Classification: **Unclassified\\For Official Use Only (U\\FOUO)**

Does this project require 3rd party Electrical Testing?

On: Jul 27 2020.

Government Response. . No 3d party electrical testing is required. However, Refer to applicable specs for requirements related to areas such as commissioning and LEED On: Jul 29 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8728847	Electrical	EP101A and EP101B		
----------------	------------	-------------------	--	--

Comment Classification: **Unclassified\\For Official Use Only (U\\FOUO)**

Please clarify the extent to which Note 5 Sheets EP101A and EP101B apply. Does this note apply to only Class 1 Division 1 and Division 2 locations within the Hangar or is this Note applicable to the Hangar space as a whole?

On: Jul 27 2020.

Government Response. . This requirement is noted in the UFCs and applies to the the Hangar space as a whole even though equipment is mounted above the C1D1 and C1D2 areas is located on the interior. On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8728849	Commissioning			Spec Section 01 91 00.15
----------------	---------------	--	--	--------------------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Spec Section 01 91 00.15 paragraph 1.3 Systems to be commissioned: Building Envelope: include moisture and thermal integrity for the entire building envelope including systems such as crawl spaces, slabs on grade and floor assemblies. Prior response to a PPI said that Air barrier testing would not be required for this project. Will Thermography testing be required for this project?

On: Jul 27 2020.

Government Response. . Air pressure barrier testing is excluded by UFC for hangars with large doors and openings. All other building envelope testing and commissioning is required and per the project specifications. Infrared Thermography testing of the Building Envelope shall be included. Air Barrier visual Inspection is required. On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8728850	Electrical	E-001		
----------------	------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Sheet E-001 lighting legend identifies a 3.5" LCD lighting control wall station. These wall stations will most likely require 120V to illuminate. Would it be permissible to tap nearest 120V circuit for these wall stations? If not, please provide available circuit for lighting wall stations.

On: Jul 27 2020.

Government Response. . These stations are not required to illuminate or be provided as LCD nor intended to have a 120VAC power requirement. These are area multi-zone scene controllers with on/off, dimming and zone controllers specified in specification 265100 section 2.6.4. However, if Contractor is providing the wall station with a 120VAC power requirement, utilizing the nearest 120V, general-purpose, non-dedicated circuit is acceptable. On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8728854	Electrical	E-111, E-401 and E-507		
----------------	------------	------------------------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

A lighting contactor with associated time clock is shown on both E-111 and E-401 Detail 3. There is also a contactor wiring detail on Sheet E-507 Detail 2. We are unable to locate which circuits are to be routed through these (2) contactors. Please provide circuits that are to be routed through contactors.

On: Jul 27 2020.

Government Response. . Refer to specification 26 56 00 section 2.4. All exterior lighting is to route through the contactor, timeclock and photocell. On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8728855	Commissioning			Spec Section 01 91 00.15
----------------	---------------	--	--	--------------------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Spec Section 01 91 00.15 paragraph 1.3 Systems to be commissioned: Building Envelope: include moisture and thermal integrity for the entire building envelope including systems such as crawl spaces, slabs on grade and floor assemblies. Prior response to a PPI said that Air barrier testing would not be required for this project.

How will we meet the requirements of paragraph 1.3 as it pertains to Building Envelope: include moisture and thermal integrity for the entire building envelope including systems such as crawl spaces, slabs on grade and floor assemblies?

On: Jul 27 2020.

Government Response. . Air pressure barrier testing is excluded by UFC for hangars with large doors and openings. All other building envelope testing and commissioning is required and per the project specifications. Infrared Thermography testing of the Building Envelope shall be included. Air Barrier visual Inspection is required.
On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8728857	Electrical	EPD101D and E-100		
----------------	------------	-------------------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Please confirm Note 9 Sheet EP101D is an oversight. None of the areas are classified as Hazardous locations as reflected on Sheet E-100

On: Jul 27 2020.

Government Response. . Correct. This note 9 should indicate 'connect to door security circuit L1C1-26.' On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8728978	Architectural	A-402, A-801A, A-801B		
----------------	---------------	-----------------------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Can you provide more detail concerning the 5' deep metal draft curtain? I am unable to find anything in the specifications on it.

On: Jul 27 2020.

Government Response. . The draft curtain is created by the depth of the metal building steel beams, however to complete the draft curtain, the opening between the top of the structure and the roof panel above must be closed off where the purlins occur. The purlin space needs to be closed off as indicated per details 3 and 4 on A-402. These locations are indicate on sheets A-102A and A-102B per keynote 5.02 On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8728983	Civil			General
----------------	-------	--	--	---------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Should we assume there is aggregate base under the Loading dock?

On: Jul 27 2020.

Government Response. . See sheet BB601 for soil boring locations. See sheets BB602 and BB609 for drilling logs B-02, NB-14, and NB-15. On: Jul 28 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8728987	Civil			General
----------------	-------	--	--	---------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

What is the extent of the filter fabric on the Towaway?

On: Jul 27 2020.			
Government Response. . . Filter fabric is limited to wrapping of the subdrain trench and providing the overlap as shown on 1/C301 On: Jul 29 2020			
Current Request Status: Request Closed			
Information for this report is procurement sensitive.			
8728988	Civil		General
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
What is the demo depth for the asphalt and concrete pavement?			
On: Jul 27 2020.			
Government Response. . . See sheet BB601 for soil boring locations. See sheets BB605 and BB606 for drilling logs NB-01 and NB-03. On: Jul 28 2020			
Current Request Status: Request Closed			
Information for this report is procurement sensitive.			
8728989	Utilities Engineering		General
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Is the electrical line in a duct bank?			
On: Jul 27 2020.			
Government Response. . . See sheets CU201, CU202, ES101, ES102, and E509. On: Jul 28 2020			
Current Request Status: Request Closed			
Information for this report is procurement sensitive.			
8728990	Utilities Engineering		General
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
What type of material is the communication line?			
On: Jul 27 2020.			
Government Response. . . See sheets CU201, CU202, TS101 and TS102. On: Jul 28 2020			
Current Request Status: Request Closed			
Information for this report is procurement sensitive.			
8728991	Cost Engineering		General
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Are taxes exempt?			
On: Jul 27 2020.			
Government Response. . . Taxes will be handled in accordance with FAR 52.229-3 Federal, State, and Local Taxes as listed in the solicitation. On: Jul 27 2020			
Current Request Status: Request Closed			
Information for this report is procurement sensitive.			
8728995	Civil		General
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
What type of lining for the diversion ditch required?			
On: Jul 27 2020.			
Government Response. . . No liner is required. On: Jul 28 2020			

Current Request Status: Request Closed			
Information for this report is procurement sensitive.			
8728997	Civil		General
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
How thick is the staging area base?			
On: Jul 27 2020.			
Government Response. . Staging area base is estimated at 6-inches thick On: Jul 28 2020			
Current Request Status: Request Closed			
Information for this report is procurement sensitive.			
8728999	Civil		General
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Temp pond #1, has no drainage pipe, please clarify?			
On: Jul 27 2020.			
Government Response. . Because the skimmer drainage pipe is temporary, it is not shown. See sheet CG510 for skimmer detail. Schedule 40 discharge pipe to be 4". On: Jul 28 2020			
Current Request Status: Request Closed			
Information for this report is procurement sensitive.			
8729000	Civil		General
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Temp Pond #1, is it temporary or does it get backfilled at the end of the project?			
On: Jul 27 2020.			
Government Response. . It is temporary. Grading to be completed as shown on sheet CG102. On: Jul 28 2020			
Current Request Status: Request Closed			
Information for this report is procurement sensitive.			
8729857	Civil	BB601	
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Please provide the boring log for B-07 as it was not included in the subsequent pages of logs.			
On: Jul 28 2020.			
Government Response. . Geo-tech report will be provided vis amendment On: Jul 29 2020			
Current Request Status: Request Closed			
Information for this report is procurement sensitive.			
8729964	Electrical		26 24 13 2.3.2.1.a and 26 24 13 2.3.2.1.d
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
The Switchboard SWBD-1 is located in Electrical Room 125, which is inside the building. Numerous electrical panelboards, transformers, and other electrical items are also located in this room. The switchboard is the only item that is showing a requirement for 304 or 304L Stainless Steel. Can the switchboard be furnished as a standard Nema 1 In accordance with Nema PB2?			
On: Jul 28 2020.			
Government Response. . Yes. Nema 1 in accordance with Nema PB2 is acceptable On: Jul 29 2020			
Current Request Status: Request Closed			

Information for this report is procurement sensitive.				
8730229	Civil	CD101		
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Reference Sheet CD101, Demolition Note #10. Please clarify location of Building 675 not shown on Demolition Drawings. If Note #10 refers to Bldg 655, please clarify note vs legend. Per Legend, pavement demolition hatch is shown at concrete slab between the two structures which note #10 has as to remain and be retained.</p> <p>On: Jul 28 2020.</p>				
<p>Government Response. . The note will be revised to refer to Bldg 655 On: Jul 29 2020</p>				
<p>Current Request Status: Request Closed</p>				
Information for this report is procurement sensitive.				
8730301	Architectural			Roof Panels
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>The roof panel spec appears to reference a screw down panel the HR5 https://www.awipanel.com/products/hr-series-hr5-2/ this panel does not carry a weathertightness warranty. The SR2 is a standing seam roof panel that does carry the warranty but does not meet the profile dimensions https://www.awipanel.com/products/standing-seam-sr2-2/. Please advise.</p> <p>On: Jul 28 2020.</p>				
<p>Government Response. . 20 year weather tightness warranty is required. Specification will be revised and issued for steel skin option. Basis of Design options include a KingRib 5 panel by Kingspan or LS36 panels by MBCI On: Jul 29 2020</p>				
<p>Current Request Status: Request Closed</p>				
Information for this report is procurement sensitive.				
8730453	Contracting			AMENDMENT 2
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Amendment 2 specifies Technical Specification Changes and Contract Drawings additions. Please provide.</p> <p>On: Jul 28 2020.</p>				
<p>Government Response. . Amendment 0002 was posted to the solicitation notice on 24 July on beta.sam.gov. Amendment 0002 file and Conformed file uploaded. Updated 20B3002vol1.pdf file and 20B3002vol2.pdf uploaded. Three new drawing files are added (20B3002 FIO Drawings.pdf, W912HN-20-B-3002_AMD2_VOLUME1.pdf and W912HN-20-B-3002_AMD2_VOLUME2.pdf). All files for this solicitation are available. On: Jul 28 2020</p>				
<p>Current Request Status: Request Closed</p>				
Information for this report is procurement sensitive.				
8730929	Other			41 22 23.19
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Please reference Division 41 - Section 41 22 23.19. Per 2.5.3.2 Controls, 1T chain hoist is calling for flux vector controls. Please confirm this is required.</p> <p>On: Jul 28 2020.</p>				
<p>Government Response. . Provide static reversing, adjustable frequency closed loop flux vector type controller if required by system manufacturer to provide a fully functioning variable speed system and to meet functionality requirements contained within the specifications. On: Jul 29 2020</p>				
<p>Current Request Status: Request Closed</p>				
Information for this report is procurement sensitive.				
8730949	Other			41 22 13.14

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**
 Reference Division 41 - Section 41 22 13.14. Please provide drawings or details in reference to 2.3.2 - Load Block and Hook Assembly - "Hook dimensions must be as shown on the drawing".
 On: Jul 28 2020.

Government Response. . Use manufacturer's standard hook. On: Jul 29 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8730963	Other			41 22 13.14
----------------	-------	--	--	-------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**
 Reference Division 41 - Section 41 22 13.14. Per 2.4.2 Controls – Please clarify VFD controls on all motions or one-speed?
 On: Jul 28 2020.

Government Response. . Provide VFD controls on all motions On: Jul 29 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8730972	Architectural	IN101A, IN101B	ALL	
----------------	---------------	----------------	-----	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**
 IN101A and IN101B list keynotes 9.01, 9.02 and 9.03 which are colored floor striping. Are these required to be painted stripes or integral color stripes in the resinous floor coating? If they are to be painted, please provide product to be used.
 On: Jul 28 2020.

Government Response. . Use an Epoxy slip-resistant deck coating system in conformance with MPI ASM, No. 82, 2 mils total dry film thickness. On: Jul 29 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8731351	Architectural	A502 and A601	3/A502,4/A5021/A601	07 41 63 & 07 61 15
----------------	---------------	---------------	---------------------	---------------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**
 Drawings clearly imply the use of an IMP roof panel typically constructed with galvanized steel skins.
 Specifications on the other hand reference the use of aluminum skinned panels for roof and walls,IMP wall panels are available for a premium price however aluminum IMP roof panels are not available.
 Please clarify intent of documents.
 On: Jul 28 2020.

Government Response. . Specifications will be revised and issued for steel skin option. Basis of Design options include a KingRib 5 panel by Kingspan or LS36 panels by MBCI. On: Jul 29 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8732470	Architectural			Section 07 27 26 item 1.10.2
----------------	---------------	--	--	------------------------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**
 Would fluid-applied air installers who are not ABAA-certified be acceptable to install the fluid-applied air barrier?
 On: Jul 29 2020.

Government Response. . As long as the manufacturer is accredited per paragraph 1.9 and submits

	documentation, and the installer is approved by the manufacturer, then the installer does not require the ABAA certification On: Jul 29 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8732800	Architectural	IN-501	06 20 00
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Please provide details / cut sections of the restroom vanities.			
On: Jul 29 2020.			
	Government Response. . Details have been provided in Amendment #03 Submission. On: Jul 31 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8733947	Electrical		26 08 00
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
RFI Response #8728747 states that 3rd Party Electrical Tetsing is not required. This contradicts Section 26 08 00 para 1.3.1, requiring a first-tier, independent testing agency. We take RFI Response #8728747 to mean the Government is eliminating all testing requirements required in Section 26 08 00. If this is incorrect, please state the testing expectations for this project.			
On: Jul 30 2020.			
	Government Response. . Response to RFI #8728747 indicated that 3rd party testing was not required for LEED. Provide 3rd party testing for Division 26 equipment as specified is specification section 260800 and other Division 26 specification sections. On: Jul 30 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8734315	Architectural		12 50 00.13 and ProjNet
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Projnet Inquiries #8685257 and #8709081, the Government responses say FF&E is by others, however, there is nothing in the drawings, specifications or Amendments that states specifically that the FF&E is by others. Please confirm that the FF&E is by others and not a part of this contract.			
On: Jul 30 2020.			
	Government Response. . The lockers are part of the bid. The rest of the FF&E is by the Govt. Review Vol II for amended specs On: Jul 30 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8734317	Architectural	IN601	ProjNet
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
ProjNet Inquiries #8702888 and #8710807, the Government responses say that lockers, locker benches and walk off mats (EFM-1, RG-1 and RG-2) are by contractor. These items are shown on the Interior Furniture drawings but no specifications have been provided. Please confirm if these are furnished and installed by the contractor, and if so, please provide specification for lockers, benches, RG-1 and RG-2. (EFM-1 requirements are shown on the Interior Finish Legend on sheet IN601)			
On: Jul 30 2020.			
	Government Response. . See forthcoming Amendment #3 for added spec 10 51 13 On: Jul 30 2020		
	Current Request Status: Request Closed		

Information for this report is procurement sensitive.

8734321	Architectural			ProjNet
----------------	---------------	--	--	---------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

ProjNet Inquiries #8709064 and #8720879, Government responses say window blinds are to be placed in rooms 209, 210, 212, 213, 220, 221, 222 and 201. However, there is nothing in the drawings, specifications or Amendments that states this. Please confirm this requirement.

On: Jul 30 2020.

Government Response. . Volume II of specs. See spec 12 21 00 in Amendment #2 On: Jul 30 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8734323	Architectural	IF101D		ProjNet
----------------	---------------	--------	--	---------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

ProjNet Inquiry #8718234, Government response says IF101D and FF&E package to be updated in future amendment, however, this information was not provided in Amendment 0002. Please update the drawings and specifications with this information.

On: Jul 30 2020.

Government Response. . Sheet IF101D is updated as a part of forthcoming Amendment 03 On: Jul 31 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8734327	Architectural			10 21 13 and ProjNet
----------------	---------------	--	--	----------------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

ProjNet Inquiry #8718237, Government response says toilet partitions are to be "solid phenolic plastic", however, plastic and phenolic are two different materials. Specification section 10 21 13 paragraph 2.3 lists solid phenolic, however, paragraph 2.8.1 lists solid plastic. Please update specification section 10 21 13 to reflect the required material for toilet partitions and urinal screens.

On: Jul 30 2020.

Government Response. . Floor Mounted Solid Phenolic HDPE toilet partitions to be used with steel pilasters. Spec 10 21 13 to be revised in upcoming Amendment 04. On: Jul 31 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8734330	Architectural			10 28 13
----------------	---------------	--	--	----------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

10 28 13, paragraph 2.2.10 lists "Shelf, Metal, Heavy Duty (SMHD)", however this item is not shown on the drawings. It appears this is not needed, since the specified mop and broom holder (2.2.17) includes a storage shelf. If this is the case, please remove the shelf specified in 2.2.10 from the specifications.

On: Jul 30 2020.

Government Response. . Correct, not needed. Paragraph 2.2.9 Shelf, Metal, Heavy Duty (SMHD) is not used. It will be removed from specifications in upcoming Amendment 04. On: Jul 31 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8734333	Architectural			10 28 13
----------------	---------------	--	--	----------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Specification 10 28 13, paragraph 2.2.14 calls for a surface mounted waste receptacle (WR), however, sheet A-401 toilet

accessory schedule shows this item (Mark A13) as recessed. Please specify which type of waste receptacle is required.			
On: Jul 30 2020.			
	Government Response. . Please provide Surface Mounted Waste Receptacles as specified in paragraph 2.2.12 of specification section 10 28 13. Item A13 on drawing A-401 will be revised to read "SURFACE MOUNTED WASTE RECEPTACLE" in upcoming Amendment 04. On: Jul 31 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8734336	Civil	C-200	ProjNet
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Projnet Inquiry #8708999, Government response states that "The Restricted Area Boundary Warning Signs are painted on the pavement and not a traffic sign mounted on a sign post. See Detail 3 on Sheet C-200". Please update the drawings and specifications to reflect this requirement.			
On: Jul 30 2020.			
	Government Response. . Detail 3 on Sheet C-200 will be updated to clarify that this is a surface painted sign and not a sign installed on a post. On: Jul 31 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8734338	Architectural		10 14 53 and ProjNet
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Section 10 14 53 lists traffic signs, posts and delineators. However, according to the Government responses to Projnet Inquiries #8708999 and 8709007, there are no traffic signs or delineators. If this is the case, please remove section 10 14 53 from the specifications.			
On: Jul 30 2020.			
	Government Response. . Section 10 14 54 will be removed from the specifications via Amdmt #4 On: Jul 31 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8734340	Architectural		ProjNet
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
ProjNet Inquiry #8712112, Government response regarding Restricted area Boundary Warning Signs conflict with the Government response to Projnet Inquiry #8708999 and 8712100. Please update the drawings and specifications to clarify what is required for this item.			
On: Jul 30 2020.			
	Government Response. . Responses to Inquiries #8734336 and #8734338 remain. On: Jul 31 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8734873	Architectural	A-610	
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Drawing A-610 shows doors 114E, 116, 124A, and 124D that show the doors to be "BB" but have no glazing specified. Please provide correct glazing required for these doors			
On: Jul 30 2020.			
	Government Response. . The Glazing type for doors 114E, 124A and 124D shall be type GL-2. Door 116 shall be Door Type AA with no glazing On: Jul 31 2020		

Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8734923	Contracting	Page 49 of 844		Contract Clause 52.249-14
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Good Afternoon:				
Would it be possible to include this clause for Excusable Delays within this RFP?				
52.249-14 - Excusable Delays				
Thank you				
On: Jul 30 2020.				
Government Response. . No, FAR Clause 52.249-14 will not be added to this solicitation. FAR 52.249-14 is used when time-and-material contracts, and labor-hour contracts, and cost-reimbursement contracts are contemplated. The clause is not use for firm fixed priced contracts which is what this construction contract will result in. FAR 52.249-10 Default (Fixed-Price Construction) address delays from unforeseeable causes beyond the control and without the fault or negligence of the Contractor and is included in this solicitation. On: Jul 30 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8734978	Architectural	A-412		07 13 53
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Where does specification 07 13 53 apply? At the elevator pit only?				
On: Jul 30 2020.				
Government Response. . Correct, specification section 07 13 53 applies at the elevator pit only. A keynote will be added via Amendment #4 to Sections 3 and 4 on drawing A-412 to identify this. On: Jul 31 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8736194	Electrical			26 20 00 3.1.5.2 (c)
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Specification Section 26 20 00 3.1.5.2 (c) prohibits the use of EMT where subject to severe physical damage. Please clarify which rooms this requirement is applicable to. More specifically, is this requirement applicable to CTK Work Area 114, Engine Backshop 128, Dash 21 124, Weapons Work Area 118, Plumbing 126, Elec 125 and Mech 123?				
On: Jul 31 2020.				
Government Response. . This requirement is applicable to all areas where subject to physical damage. Yes, this requirement is applicable to the CTK Work Area 114, Engine Backshop 128, Dash 21 124, Weapons Work Area 118, Plumbing 126, Elec 125 and Mech 123 areas. On: Aug 03 2020				
Current Request Status: Request Closed				
Information for this report is procurement sensitive.				
8736979	Electrical	ESD101 and ES103	N/A	N/A
Comment Classification: Unclassified\For Official Use Only (U\FOUO)				
Sheet ESD101 indicates the existing electrical ductbank to be removed crossing two (2) entrance drives. The existing pavement will need to be removed to remove the ductbank. General Note 9 on sheet ES103 states that cutting and patching of existing concrete and asphalt is not permitted. Should the ductbank be left existing under these entrance drives? Please clarify.				
On: Jul 31 2020.				

	Government Response. . Sheet ES103 only pertains to existing Airfield and Apron Lighting related areas. Remove ductbank to be demolished in entirety noted on sheet ESD101. On: Aug 03 2020			
	Current Request Status: Request Closed			
Information for this report is procurement sensitive.				
8737226	Site	TSD101 and TSD102	N/A	N/A
Comment Classification: Unclassified\\For Official Use Only (U\\FOUO)				
Sheets TSD101 and TSD102 indicate telecommunication ductbanks to be removed. ESD101 and ESD102 indicate electrical ductbanks to be removed. Are these the same ductbanks? Or are there two (2) ductbanks to be removed?				
On: Jul 31 2020.				
	Government Response. . These are not the same ductbanks. These are two separate ductbanks that need to be removed. Electrical is shown on the E series sheets. Communications is shown on the T series sheets. On: Aug 03 2020			
	Current Request Status: Request Closed			
Information for this report is procurement sensitive.				
8737332	Plumbing	FX104	N/A	N/A
Comment Classification: Unclassified\\For Official Use Only (U\\FOUO)				
Keyed note 4.11 on sheet FX104 states to provide a continuous section of welded stainless steel fire water service piping to a point outside the building perimeter to within the building. Please specify where the "point" outside the building is located.				
On: Jul 31 2020.				
	Government Response. . The continuous section of welded stainless steel fire water service piping shall enter from a point outside of the building perimeter to a flanged fitting located at least one foot above finished floor within the building. On: Aug 04 2020			
	Current Request Status: Request Closed			
Information for this report is procurement sensitive.				
8737385	Electrical	ESD101 and ESD102	N/A	N/A
Comment Classification: Unclassified\\For Official Use Only (U\\FOUO)				
Is there any existing information on the electrical ductbanks to be removed? Dimensions of ductbank and depth?				
On: Jul 31 2020.				
	Government Response. . To prepare your bid for this demolition feature, assume the communications duct to be a 2x2 4-inch, 6-8 feet deep. The electrical ductbank may be assumed to be also 6-8 feet deep. On: Aug 04 2020			
	Current Request Status: Request Closed			
Information for this report is procurement sensitive.				
8737502	Civil	CD-101 and CD-102		
Comment Classification: Unclassified\\For Official Use Only (U\\FOUO)				
Please provide size of existing electrical and telecommunication duct-banks to be demolished?				
On: Jul 31 2020.				
	Government Response. . There are no as-built drawings of the existing underground duct banks that are to be demolished. To prepare your bid for this demolition feature, assume the communications duct to be a 2x2 4-inch, 6-8 feet deep. The electrical ductbank may be assumed to be also 6-8 feet deep On: Aug 04 2020			
	Current Request Status: Request Closed			
Information for this report is procurement sensitive.				
8739069	Contracting			01 35 26 1.7

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

This specification states that the government considers the Prime Contractor to be the "controlling authority" for all work site safety and health of the subcontractors.

Does this mean that the SSHO is to be a direct employee of the Prime Contractor, or a 1st-Tier subcontractor hired by the Prime Contractor?

On: Aug 03 2020.

Government Response. . SSHO is required to be prime contractor employee On: Aug 03 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8740314	Architectural	A-622		
----------------	---------------	-------	--	--

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Please specify the location of Louver L5 as it has not been located on the floor plans or elevations.

On: Aug 03 2020.

Government Response. . Louver L5 is not used On: Aug 05 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8740322	Architectural	IN601		09 65 00
----------------	---------------	-------	--	----------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Specification Section 09 65 00 calls for Type TS (vulcanized thermoset rubber) at stair treads, risers and stringers, however the finish schedule on IN601 calls for stair's 1&2 floor finish to be sealed concrete. Please advise which finish is required.

On: Aug 03 2020.

Government Response. . Follow IN601, sealed concrete stairs. Spec 09 65 00 to be revised to remove rubber stair tread language. On: Aug 05 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8740541	General			Solicitation
----------------	---------	--	--	--------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

Several RFI responses refer to amendment 0003 and 0004 being issued. The latest amendment issued was 0002. When will 0003 and 0004 be issued? Will the proposal due date be extended again?

On: Aug 03 2020.

Government Response. . Amendment #3 release is imminent. Amendment #4 should be before the end of the week. The Contracting Officer will decide on an appropriate bid due date extension. On: Aug 03 2020

Current Request Status: **Request Closed**

Information for this report is procurement sensitive.

8742014	Equipment	S-301	Details 5 & 6	UFGS 08 34 16.20
----------------	-----------	-------	---------------	------------------

Comment Classification: **Unclassified\For Official Use Only (U\FOUO)**

In the UFGS 08 34 16.20 VLF Door specification "Section 2.7.2 - Retractable Mullion Pin and Floor Strike when Utilized" and "Section 2.3.7 Limit Switches" makes reference to a Retractable Mullion Pin. However Details 5&6 shown on S-301 appear to show the VLF Door Mullion Pits for a Fixed Mullion Pin design. The VLF Door supplier provided the attached details. Is the

Fixed Pin Design or the Retractable Pin design to be utilized the mullion pins?			
(Attachment: Mullion_Pit_-_Standard_Fixed_Pin_vs_Retractable_Pin.pdf) On: Aug 04 2020.			
	Government Response. . The Standard Fixed pin mullion is to be utilized per the details on S-301 On: Aug 05 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8742670	Contracting		Amendment 3 RFP
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
The Amendment 3 RFP notes that Contract Drawings - File No. 141-185-01 are to be included in this Amendment 3, but these Drawings are not included. Please provide these drawings.			
On: Aug 04 2020.			
	Government Response. . Contracting POC in Savannah is verifying the amendment #3 posting to beta.sam.gov Correction as needed will be made ASAP On: Aug 05 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8742685	Contracting		Amendment 3 PFP
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
The Amendment 3 RFP states that Technical Specification Changes are included in this amendment, but the Revised Spec Sections are not included. Please provide these Revised Specifications.			
On: Aug 04 2020.			
	Government Response. . Contracting POC in Savannah is verifying the amendment #3 posting to beta.sam.gov Correction as needed will be made ASAP On: Aug 05 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8742800	Specifications		Division 10
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
I noticed a lot of lockers. Are these part of the scope or are they being provided by the owner? There are no specifications for them or any elevation drawings that provide dimensions.			
On: Aug 04 2020.			
	Government Response. . Corrected posting of Amendment #3 should clarify the lockers. The posting apparent error is being assessed & corrected On: Aug 05 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8742882	Architectural	A-311	07 21 13
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
What is the thickness of the perimeter underslab insulation? How far is it required to project inward from the exterior?			
On: Aug 04 2020.			
	Government Response. . Perimeter insulation shall be 2 inches thick and project inward 24 inches from the exterior edge of slab per 3.5.2 of Spec section 07 21 13 On: Aug 05 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8742892	Architectural	A-601	

<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Several of the metal stud frame wall types indicate a batt insulation. There is no specification for this insulation. Please provide.</p> <p>On: Aug 04 2020.</p>				
<p>Government Response. . All of the insulation where indicated in the interior partitions shall be 3" thick Sound attenuation Batt insulation, and shall be approved as fire blanket in fire rated partitions P23 and P23A. A min 3" thick, R-11 fiberglass Sound Attenuation Batt insulation On: Aug 05 2020</p>				
<p>Current Request Status: Request Closed</p>				
<p align="center">Information for this report is procurement sensitive.</p>				
8742897	Architectural	A-601		
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Wall type P11 depicts batt insulation per the drawing, but it is not indicated with a description as in the other similar wall types. Is batt insulation required in wall type P11 and if so, what type is required?</p> <p>On: Aug 04 2020.</p>				
<p>Government Response. . Partition type P11 shall have 3" thick sound attenuation batts, same as the other interior partitions. A min 3" thick, R-11 fiberglass Sound Attenuation Batt insulation On: Aug 05 2020</p>				
<p>Current Request Status: Request Closed</p>				
<p align="center">Information for this report is procurement sensitive.</p>				
8742944	Architectural	A-311		04 20 00
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>In section 2.6.7 of spec 042000 there are 3 different types of through wall flashing listed. Which type is required? Wall sections only indicated "metal".</p> <p>On: Aug 04 2020.</p>				
<p>Government Response. . Please provide metal thru wall flashing as indicated in the drawings, and per specification section 04 20 00 paragraphs 2.6.5.2 or 2.6.5.3. On: Aug 05 2020</p>				
<p>Current Request Status: Request Closed</p>				
<p align="center">Information for this report is procurement sensitive.</p>				
8744338	Specifications			General
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Can a spec. be provided for the oil/water separator and Fuel Spill Containment Tank?</p> <p>On: Aug 05 2020.</p>				
<p>Government Response. . See specification section 22 00 00 On: Aug 05 2020</p>				
<p>Current Request Status: Request Closed</p>				
<p align="center">Information for this report is procurement sensitive.</p>				
8744461	Civil	C-301 and C-501		32 13 14.13
<p>Comment Classification: Unclassified\For Official Use Only (U\FOUO)</p> <p>Drawings C-301 and C-501 Call for PCC pavement and Airfield Pavement jointing details. Noted to be spec section 32 13 14.13. However, spec section 32 13 14.13 is not included in the documents. Please Provide.</p> <p>On: Aug 05 2020.</p>				

	Government Response. . This specification section was provided in Amendment 03. There was an apparent error in posting this amendment. It being evaluated/assessed for necessary correction/update On: Aug 05 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8745117	General		Solicitation
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
With the expectation of additional information being posted to support amendment #3 and for amendment #4 to be issued as stated in the list of inquiries, we are requesting a minimum of a one (1) week extension to the bid due date. On: Aug 05 2020.			
	Government Response. . This is already under consideration by the Contracting Officer. Review updates in the forthcoming amendment #4 On: Aug 05 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			
8748374	Contracting	N/A	N/A
Comment Classification: Unclassified\For Official Use Only (U\FOUO)			
Amendment #3 corrected posting On: Aug 06 2020.			
	Government Response. . See corrected/updated Amendment #3 on https://beta.sam.gov/opp/d97389b9745c4f71b28ed5e313e583f5/view On: Aug 06 2020		
	Government Response. . This new text supercedes ALL previous replies. See corrected/updated Amendment #3 on https://beta.sam.gov/opp/d97389b9745c4f71b28ed5e313e583f5/view OR via whatever web link you have been accessing the IFB On: Aug 06 2020		
	Current Request Status: Request Closed		
Information for this report is procurement sensitive.			

Report Complete

UNCLASSIFIED\FOR OFFICIAL USE ONLY

Patent 11/892,984 ProjNet property of ERDC since 2004.