A.C.M. LEGEND

ALL FLOORING TILE AND MASTIC TO BE REMOVED AND DISPOSED OF AS ACM WASTE. THIS INCLUDES 12"X12", 9"X9" AND CERAMIC TILE. (APPROXIMATELY – 5,598 SF)

BLACK PIPE MASTIC TO BE REMOVED FROM WATERLINES WITHIN WALLS AND DISPOSED OF BY ASBESTOS ABATEMENT CONTRACTOR AS A.C.M. WASTE. FOR APPROXIMATE LOCATIONS AND QUANTITIES REFERENCE THE 1ST FLOOR PLUMBING AND WATER DEMO PLAN P101 AND P110 1

HARD PIPE ELBOWS AND JOINTS LONG WITH BLACK PIPE MASTIC ALONG CEILING IN SHOP AREA TO BE DISPOSED OF A.C.M. WASTE.

A.C.M. KEYED NOTES:

1 ALL DRYWALL/JOINT COMPOUND TO BE REMOVED AND DISPOSED OF BY ASBESTOS ABATEMENT CONTRACTOR AS A.C.M. WASTE. ALL EXTERIOR WALL WHICH CONSIST OF PLASTER ARE NOT TO BE DISTURBED.

DENOTES DRYWALL / JOINT LOCATIONS

2 ABOVE DROPPED CEILING IN OFFICES AND HALLWAY, BLACK PIPE AND HVAC DUCT MASTIC TO BE REMOVED AND DISPOSED OF AS A.C.M. WASTE. FOR APPROXIMATE LOCATION AND QUANTITIES REFERENCE THE 1ST FLOOR HVAC DEMO PLAN M100 1

3 SINKS CONTAINING ACM GRAY UNDERCOATING TO BE REMOVED AND DISPOSED OF AS A.C.M. WASTE. (2 SINKS)

4 ACM TRANSOM PANELS UNDER WINDOWS LOCATED, NOT TO BE ABATED.

GENERAL NOTES

1. ALL QUANTITIES AND DIMENSIONS (IF SHOWN) SHALL BE FIELD VERIFIED PRIOR TO BIDDING.
2. ALL PIPE, HVAC, ECT. ARE SHOWN APPROXIMATE, AND SHALL BE FIELD VERIFIED PRIOR TO BIDDING.
3. WHEN REMOVAL OF FLOOR COVERINGS IS DESIGNATED, IT SHALL ALSO MEAN ALL COVE BASE AND ASSOCIATED MASTICS (ON FLOOR AND WALL) TO BE REMOVED.
4. ALL PARTITIONS, SHELVING, CABINETS, ECT. INSTALLED OVER ASBESTOS FLOOR TILE SHALL BE REMOVED IN ORDER TO EXPOSE ASBESTOS FLOOR TILE FOR ABATEMENT.
5. ABATEMENT OF FIRST FLOOR SHALL BE INCLUDED IN BASE BID.

1 AB100 1ST FLOOR ASBESTOS ABATEMENT PLAN

SCALE: 3/16" = 1'-0"

CFS
Cheatham Fletcher Scott
ARCHITECTS + DESIGNERS

420 Eighth St, Augusta, Georgia 30901
P: 706-724-2668 W: cfsarchitects.com

SEALS

PROJECT TITLE
W.C. ERVIN TOWERS

1365 LANEY WALKER BLVD
AUGUSTA, GEORGIA
30901

FIRST FLOOR ASBESTOS ABATEMENT PLAN

MARK	DATE	DESCRIPTION
1	12/13/2022	NOTES CHANGE
	12/08/2022	ISSUE

PROJECT NO: 1543-105
FILE: 20221006 ERVIN TOWERS
DRAWN BY: L C
CHK'D BY:

AB100