A.C.M. LEGEND

FLOOR TILE AND MASTIC TO BE REMOVED AND DISPOSED OF AS ACM WASTE. 12"X12" AND 9"X9" – 2 LAYERS MAY BE PRESENT IN SOME AREAS CONTAINING 12" X 12".
(APPROXIMATELY – 7,221 SF)

BLACK PIPE MASTIC TO BE REMOVED FROM PIPING WITHIN WALLS AND DISPOSED OF BY ASBESTOS ABATEMENT CONTRACTOR AS A.C.M. WASTE. REFERENCE PLUMBING AND WATER DEMO P102 AND P111 1

A.C.M. KEYED NOTES:

1 ALL DRYWALL/JOINT COMPOUND TO BE REMOVED AND DISPOSED OF BY ASBESTOS ABATEMENT CONTRACTOR AS A.C.M. WASTE. ALL EXTERIOR WALL WHICH CONSIST OF PLASTER ARE NOT TO BE DISTURBED.

DENOTES DRYWALL / JOINT LOCATIONS

2 HARD PIPE JOINTS/ ELBOWS TO BE REMOVED AND DISPOSED OF BY ASBESTOS ABATEMENT CONTRACTOR AS A.C.M. WASTE.

DENOTES HARD PIPE LOCATIONS

3 ALL CEILING TEXTURE TO BE REMOVED AND DISPOSED OF AS ACM WASTE.
(APPROXIMATELY – 7,221 SF)

GENERAL NOTES

1. ALL QUANTITIES AND DIMENSIONS (IF SHOWN) SHALL BE FIELD VERIFIED PRIOR TO BIDDING.
2. ALL PIPE, HVAC, ECT. ARE SHOWN APPROXIMATE, AND SHALL BE FIELD VERIFIED PRIOR TO BIDDING.
3. WHEN REMOVAL OF FLOOR COVERINGS IS DESIGNATED, IT SHALL ALSO MEAN ALL COVE BASE AND ASSOCIATED MASTICS (ON FLOOR AND WALL) TO BE REMOVED.
4. ALL PARTITIONS, SHELVING, CABINETS, ECT. INSTALLED OVER ASBESTOS FLOOR TILE SHALL BE REMOVED IN ORDER TO EXPOSE ASBESTOS FLOOR TILE FOR ABATEMENT.
5. NUMBER OF APARTMENT FLOORS TO BE ABATED SHALL BE DETERMINED BY THE NUMBER OF ALTERNATES ACCEPTED. SEE SPECIFICATION SECTION 021300.

1 AB102 3RD/ 6TH/ 9TH FLOOR ASBESTOS ABATEMENT PLAN
SCALE: 3/16" = 1'-0"

CFS
Cheatham Fletcher Scott
ARCHITECTS + DESIGNERS

420 Eighth St, Augusta, Georgia 30901
P: 706-724-2668 W: cfsarchitects.com

SEALS

PROJECT TITLE
W.C. ERVIN TOWERS

1365 LANEY WALKER BLVD
AUGUSTA, GEORGIA
30901

3RD/ 6TH/ 9TH FLOOR ASBESTOS ABATEMENT PLAN

MARK	DATE	DESCRIPTION
1	12/13/2022	NOTES CHANGE
	12/08/2022	ISSUE

PROJECT NO: 1543-105
FILE: 20221006 ERVIN TOWERS
DRAWN BY: LC
CHK'D BY:

AB102